

NUTLEY PUBLIC SCHOOL

REVISED 5-2-18 OPTION TWO

TWO QUESTION REFERENDUM

#2962
#3380

School

YANTACAW ELEM	OPTION	QUESTION 1	QUESTION 2
	SQFT	COST/SF	COST

1.03

New Construction Perfered Option

Area A bas, 1st,2nd,3rd	12600	325	\$	4,095,000.00	\$	4,095,000.00	
Area B 1st,2nd,3rd	0	325	\$	-	\$	-	0
Area C Multi-purpose rm	6200	350	\$	2,170,000.00		\$	2,170,000.00
Kitchen Equipment			\$	-	\$	-	0
Firewall Area BB	125	500	\$	62,500.00	\$	50,000.00	\$ 12,500.00
Elevator	1		\$	250,000.00	\$	250,000.00	
Mech Mach room	1		\$	150,000.00	\$	150,000.00	

Renovations

Area A Art/Music	2300	0	\$	-	\$	-	
Area B stair/infill	1800	300	\$	540,000.00	\$	432,000.00	\$ 108,000.00
Lift/Ramp for MPR			\$	200,000.00		\$	200,000.00
Temp Egress	2		\$	100,000.00	\$	100,000.00	

MISC

M.E.P Tie-in			\$	150,000.00	\$	150,000.00	
Demo			\$	100,000.00	\$	100,000.00	
Phasing			\$	50,000.00	\$	50,000.00	
Loose Furniture			\$	-			NIC

SITE WORK

Gen Site			\$	550,000.00	\$	350,000.00	\$ 200,000.00
Water Quality			\$	250,000.00	\$	187,500.00	\$ 62,500.00
Utilities			\$	150,000.00	\$	100,000.00	\$ 50,000.00
Removal of Trailers			\$	40,000.00	\$	40,000.00	
sub-total			\$	8,857,500.00	\$	6,054,500.00	\$ 2,803,000.00
PROJECT COST	30.5%		\$	2,701,537.50	\$	1,846,622.50	\$ 854,915.00
CM Fees	3.0%		\$	265,725.00	\$	181,635.00	\$ 84,090.00
TOTAL			\$	11,824,762.50	\$	8,082,757.50	\$ 3,742,005.00

INFLATION1.03\$ 8,325,240.23\$ 3,854,265.15

Site Topo/Survey and Geo-tech required
Hazardous Material or Contaminated Soil, Temporary Facilities not included

NUTLEY PUBLIC SCHOOL

MIDDLE SCHOOL	OPTION	
	SQFT	COST/SF

New Construction

Area A Lower Level	11000	400	\$	4,400,000.00		
Area B 1st and 2nd	24000	350	\$	8,400,000.00		
Area C Multi-purpose	7300	350	\$	2,555,000.00		420000
Area D 3rd level part A	12000	400	\$	4,800,000.00		
Firewall Area BB	300	400	\$	120,000.00		
Elevator	1	250000	\$	250,000.00		

Renovations

Area A old BOE	1000	225	\$	225,000.00		
Area B LL Tie-in Reno	1000	200	\$	200,000.00		
Area C Ext. Façade Reno	5000	125	\$	625,000.00		
Main Office Reno	2700	200	\$	540,000.00		
Demo Stair / Infill 2nd fl	1366	250	\$	341,500.00		
Demo Stair / Infill 3rd fl	1120	250	\$	280,000.00		
Underpinning	100'		\$	150,000.00		

MISC

Temporary Egress			\$	350,000.00		
M.E.P Tie-in			\$	400,000.00		
A/C issues			\$	200,000.00		
Auditorium Floor Rep.	6300	25	\$	-		
Demo			\$	300,000.00		
Phasing			\$	200,000.00		
Audit. Seating			\$	-		

Loose Furniture			\$	200,000.00			
SITE WORK							
Site Entry Plaza & Ramp			\$	350,000.00			
Site Work Building			\$	1,200,000.00			
Retaining Wall			\$	450,000.00			
Water Quality			\$	300,000.00			
Demo			\$	150,000.00			
Parking Area			\$	100,000.00			
Misc			\$	-			
	sub-total		\$	27,086,500.00	\$	27,086,500.00	\$ 420,000.00
PROJECT COST	30.5%		\$	8,261,382.50			\$ 128,100.00
CM Fees	3.0%		\$	812,595.00			\$ 12,600.00
	TOTAL		\$	36,160,477.50	\$	36,160,477.50	\$ 560,700.00
			INFLATION		1.03	\$ 37,245,291.83	\$ 577,521.00
Property Cost							
Note:							\$ 37,822,812.83

* Above figures do not include cost of property, ID or Removal of Hazardous Materials

NUTLEY PUBLIC SCHOOL

School		
--------	--	--

WASHINGTON ELEM	OPTION C revised	QUESTION 1	QUESTION 2
	SQFT COST/SF COST		

New Construction

3 Story CR Addition	9900	375	\$	3,712,500.00	\$	3,712,500.00	
MULTI-P	5000	375	\$	1,875,000.00			\$ 1,875,000.00
Stairs			\$	250,000.00	\$	250,000.00	
Elevator	1		\$	300,000.00	\$	300,000.00	
Firewall			\$	75,000.00	\$	56,250.00	\$ 18,750.00

SITE WORK

Site			\$	225,000.00	\$	168,750.00	\$ 56,250.00
Utilities			\$	75,000.00	\$	75,000.00	
Temp Egress stairs			\$	250,000.00	\$	250,000.00	
water Quality			\$	50,000.00	\$	50,000.00	

Renovations

Remove Temp Trailer	\$	40,000.00	\$	40,000.00
Esisting Boiler room Demo	\$	100,000.00	\$	100,000.00

MISC

M.E.P Tie-in			\$	150,000.00	\$	150,000.00	
Demo			\$	100,000.00	\$	100,000.00	
Phasing			\$	100,000.00	\$	100,000.00	
Loose Furniture							nic
	sub-total		\$	7,302,500.00	\$	5,352,500.00	\$ 1,950,000.00
PROJECT COST	30.5%		\$	2,227,262.50	\$	1,632,512.50	\$ 594,750.00
CM Fees	3.0%		\$	219,075.00	\$	160,575.00	\$ 58,500.00
	TOTAL		\$	9,748,837.50	\$	7,145,587.50	\$ 2,603,250.00

INFLATION 1.03 \$ 7,359,955.13 \$ 2,681,347.50

NOTE:

Hazardous Material or Contaminated Soil, Temporary Facilities not included

School		COMMENTS
--------	--	----------

HIGH SCHOOL	OPTION	
	SQFT COST/SF COST	

New Construction

Media Center (New)	5500	400	\$	2,200,000.00	\$	2,200,000.00
Classrooms	0	325	\$	-		0
Phy Ed area	7000	0	\$	-	0	0

SITE WORK

Site	\$	150,000.00	\$	150,000.00
Utilities	\$	125,000.00	\$	125,000.00

Renovations

Auditorium	0	350	\$	-				
Stage lighting			\$	-				
Team Room	0	150	\$	-				
Locker Room Boys	0	150	\$	-				
Locker Room Girls	0	150	\$	-				
AUX Gym	0	0	\$	-				
Cafeteria Renovation	0	275	\$	-				
Media Center to CLRMs	8000	275	\$	2,200,000.00	\$	2,200,000.00		
Main GYM Upgrades			\$	-				
Wrestling Room	0	25	\$	-				
MISC								
M.E.P Tie-in			\$	150,000.00	\$	45,000.00	\$	105,000.00
Demo			\$	75,000.00	\$	30,000.00	\$	45,000.00
Phasing			\$	25,000.00	\$	25,000.00	\$	-
Loose Furniture								

sub-total		\$	4,925,000.00	\$	2,300,000.00	\$	2,625,000.00
PROJECT COST	30.5%	\$	1,502,125.00	\$	701,500.00	\$	800,625.00
CM Fees	3.0%	\$	147,750.00	\$	69,000.00	\$	78,750.00
TOTAL		\$	6,574,875.00	\$	3,070,500.00	\$	3,504,375.00
inc inflation		\$	6,772,121.25	\$	3,162,615.00	\$	3,609,506.25

Hazardous Material or Contaminated Soil, Temporary Facilities not included