

2023 Bid Tabulation 2A-41 INFRASTRUCTURE SURFACE REPAIR, ASPHALT TRENCH PATCHING, AND MISCELLANEOUS CURBS & SIDEWALK REPAIR VARIOUS LOCATIONS JULY 1, 2023 THROUGH JUNE 30, 2024, INCLUSIVE				J. Fletcher Cremer & Son		D&L Paving Contractors, Inc.		American Asphalt & Trucking, LLC	
Municipality: <u>Village of Rahmonstad</u>				182 East Broadway		675 Franklin Avenue		818 Summer Avenue	
County: <u> Bergen County </u>				Hackensack, NJ 07601		Northvale, NJ 07719		Newark, NJ 07104	
ITEM NO.	ITEM NAME	UNIT	QUANTITY	UNIT PRICE	PRICE	UNIT PRICE	PRICE	UNIT PRICE	PRICE
5B.	Various Trench Areas, Item Patching (1) to 24 SY) Installation of 6-inch compacted black IDMA 19464 Base Course, measured by the square yard at designated trenches, with any necessary trench excavation to install the full depth of asphalt, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, base asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	11 to 25 SY	\$155.00	\$155.00	\$185.00	\$185.00	\$180.00	\$180.00
5C.	Various Trench Areas, Item Patching (2) to 75 SY) Installation of compacted 6 inch black IDMA 19464 Base Course, measured by the square yard at designated trenches, with any necessary trench excavation to install the full depth of asphalt, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, base asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	26 to 75 SY	\$155.00	\$155.00	\$155.00	\$155.00	\$150.00	\$150.00
5D.	Various Trench Areas, Item Patching (76 and up SY) Installation of compacted 6 inch black IDMA 19464 Base Course, measured by the square yard at designated trenches, with any necessary trench excavation to install the full depth of asphalt, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, base asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	76 SY and up	\$110.00	\$110.00	\$140.00	\$140.00	\$120.00	\$120.00
6A.	Various Trench Areas, Item Course Patching (1) to 10 SY) Installation of compacted 2 inch black IDMA 33864 Top Course, measured by the square yard at designated trenches, with any necessary base asphalt preparation, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, finished top asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	1 to 10 SY	\$1.00	\$1.00	\$155.00	\$155.00	\$300.00	\$300.00
6B.	Various Trench Areas, Item Course Patching (11 to 25 SY) Installation of compacted 2 inch black IDMA 33864 Top Course, measured by the square yard at designated trenches, with any necessary base asphalt preparation, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, finished top asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	11 to 25 SY	\$1.00	\$1.00	\$135.00	\$135.00	\$180.00	\$180.00
6C.	Various Trench Areas, Item Course Patching (26 to 75 SY) Installation of compacted 2 inch black IDMA 33864 Top Course, measured by the square yard at designated trenches, with any necessary base asphalt preparation, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, finished top asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	26 to 75 SY	\$1.00	\$1.00	\$110.00	\$110.00	\$160.00	\$160.00
6D.	Various Trench Areas, Item Course Patching (76 and up SY) Installation of compacted 2 inch black IDMA 33864 Top Course, measured by the square yard at designated trenches, with any necessary base asphalt preparation, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), bonds, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, tack coating and sealing of trench edges necessary to provide a complete, finished top asphalt patch at various locations. Unit price shall also include all costs for disposal of generated debris.	S.Y.	76 SY and up	\$1.00	\$1.00	\$90.00	\$90.00	\$150.00	\$150.00
				1st	\$1,039.00	2nd	\$2,477.00	3rd	\$3,544.40

I hereby certify that this is a true copy of the bids received on April 26, 2023

Christopher J. Rulifson, P.E., Village Engineer

2023 Bid Tabulation 54-41 INFRAKED ASPHALT SURFACE REPAIR, ASPHALT TRENCH PATTERNS, AND MISCELLANEOUS CURB & SIDEWALK REPAIR VARIOUS LOCATIONS JULY 1, 2023 THROUGH JUNE 30, 2024, INCLUSIVE Municipality: Village of Ridgewood County: Queens County									
				J. Fletcher Creamer & Son		D&L Paving Contractors, Inc.		American Asphalt & Trucking, LLC	
				321 East Broadway		675 Franklin Avenue		818 Summer Avenue	
				Hicksville, NY 07601		Hicksville, NY 07610		Hicksville, NY 07614	
ITEM NO.	ITEM NAME	UNIT	QUANTITY	UNIT PRICE	PRICE	UNIT PRICE	PRICE	UNIT PRICE	PRICE
1A.	Various Trench Areas: Infused Asphalt Surface Restoration of various types of utility trenches throughout the Village of Ridgewood and the service area of Ridgewood Water Company. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, saw cutting, temporary facilities, project supervision, materials, necessary to provide a complete, smooth asphalt surface restoration of various trenches at any time of the year. This price shall also include all costs for disposal of generated debris.	S.F.	1 to 100 SF	\$19.00	\$19.00	\$15.00	\$15.00	\$87.60	\$87.60
1B.	Various Trench Areas: Infused Asphalt Surface Restoration of various types of utility trenches throughout the Village of Ridgewood and the service area of Ridgewood Water Company. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, saw cutting, temporary facilities, project supervision, materials, necessary to provide a complete, smooth asphalt surface restoration of various trenches at any time of the year. This price shall also include all costs for disposal of generated debris.	S.F.	101 to 200 SF	\$18.00	\$18.00	\$12.00	\$12.00	\$53.80	\$53.80
1C.	Various Trench Areas: Infused Asphalt Surface Restoration of various types of utility trenches throughout the Village of Ridgewood and the service area of Ridgewood Water Company. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, saw cutting, temporary facilities, project supervision, materials, necessary to provide a complete, smooth asphalt surface restoration of various trenches at any time of the year. This price shall also include all costs for disposal of generated debris.	S.F.	201 and greater SF	\$13.00	\$13.00	\$10.00	\$10.00	\$33.00	\$33.00
2A.	Various Curb Areas: 9-inch x 18-inch Concrete Vertical Curb, NIDOT Class B Air Entrained Concrete, at various locations throughout the Village of Ridgewood and the service area of Ridgewood Water Company. Locations of the work are to be more than 100 yards apart. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, materials, backfill, asphalt pavement restoration, topsoil/seed/bedrock for surface restoration necessary to provide a complete concrete curb restoration of damaged curb areas. This price shall also include all costs for disposal of generated debris.	L.F.	1 to 10 L.F.	\$20.00	\$20.00	\$100.00	\$100.00	\$280.00	\$280.00
2B.	Various Curb Areas: 9-inch x 18-inch Concrete Vertical Curb, NIDOT Class B Air Entrained Concrete, at various locations throughout the Village of Ridgewood and the service area of Ridgewood Water Company. Locations of the work are to be more than 100 yards apart. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, materials, backfill, asphalt pavement restoration, topsoil/seed/bedrock for surface restoration necessary to provide a complete concrete curb restoration of damaged curb areas. This price shall also include all costs for disposal of generated debris.	L.F.	11 to 25 L.F.	\$20.00	\$20.00	\$100.00	\$100.00	\$180.00	\$180.00
3C.	Various Curb Areas: 9-inch x 18-inch Concrete Vertical Curb, NIDOT Class B Air Entrained Concrete, at various locations throughout the Village of Ridgewood and the service area of Ridgewood Water Company. Locations of the work are to be more than 100 yards apart. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, materials, backfill, asphalt pavement restoration, topsoil/seed/bedrock for surface restoration necessary to provide a complete concrete curb restoration of damaged curb areas. This price shall also include all costs for disposal of generated debris.	L.F.	26 and up L.F.	\$20.00	\$20.00	\$75.00	\$75.00	\$100.00	\$100.00
3A.	Various Sidewalk/Driveway Areas: Installation of 7-inch thick Concrete Driveway Areas at various locations, NIDOT Class B Air Entrained Concrete. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, all materials necessary to provide a complete, new sidewalk at various locations complete with necessary site restoration (topsoil/seed/bedrock). This price shall also include all costs for disposal of generated debris.	S.Y.	1 to 10 SY	\$50.00	\$50.00	\$200.00	\$200.00	\$300.00	\$300.00
3B.	Various Sidewalk/Driveway Areas: Installation of 7-inch thick Concrete Driveway Areas at various locations, NIDOT Class B Air Entrained Concrete. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, all materials necessary to provide a complete, new sidewalk at various locations complete with necessary site restoration (topsoil/seed/bedrock). This price shall also include all costs for disposal of generated debris.	S.Y.	11 to 25 SY	\$50.00	\$50.00	\$200.00	\$200.00	\$180.00	\$180.00
3C.	Various Sidewalk/Driveway Areas: Installation of 7-inch thick Concrete Driveway Areas at various locations, NIDOT Class B Air Entrained Concrete. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, all materials necessary to provide a complete, new sidewalk at various locations complete with necessary site restoration (topsoil/seed/bedrock). This price shall also include all costs for disposal of generated debris.	S.Y.	26 and up SY	\$50.00	\$50.00	\$175.00	\$175.00	\$160.00	\$160.00
4A.	Various Sidewalk Areas: Installation of 4-inch thick Concrete sidewalk, NIDOT Class B Air Entrained Concrete. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, all materials necessary to provide a complete, new sidewalk at various locations complete with site restoration (topsoil/seed/bedrock). This price shall also include all costs for disposal of generated debris.	S.Y.	1 to 10 SY	\$65.00	\$65.00	\$150.00	\$150.00	\$300.00	\$300.00
4B.	Various Sidewalk Areas: Installation of 4-inch thick Concrete sidewalk, NIDOT Class B Air Entrained Concrete. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, all materials necessary to provide a complete, new sidewalk at various locations complete with site restoration (topsoil/seed/bedrock). This price shall also include all costs for disposal of generated debris.	S.Y.	11 to 25 SY	\$65.00	\$65.00	\$150.00	\$150.00	\$180.00	\$180.00
4C.	Various Sidewalk Areas: Installation of 4-inch thick Concrete sidewalk, NIDOT Class B Air Entrained Concrete. This price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, all materials necessary to provide a complete, new sidewalk at various locations complete with site restoration (topsoil/seed/bedrock). This price shall also include all costs for disposal of generated debris.	S.Y.	26 and up SY	\$65.00	\$65.00	\$135.00	\$135.00	\$150.00	\$150.00
5A.	Various Trench Areas: New Patios (1 to 10 SY): Installation of 4-inch compacted thick (1 to 10 SY) Base Course, measured by the square yard at designated location, with any necessary trench excavations to level the full depth of depth, price shall include all maintenance and protection of traffic (exclusive of Police Department Traffic Control Officers), loads, insurance, temporary facilities, project supervision, materials, saw cutting of excavation edges, back cutting and mixing of trench edges necessary to provide a complete, new asphalt path at various locations. This price shall also include all costs for disposal of generated debris.	S.Y.	1 to 10 SY	\$160.00	\$160.00	\$185.00	\$185.00	\$300.00	\$300.00