

DPH MECHANICAL INC,

1241 Centerton Road
PITTSRGROVE NJ 08318

Estimate

Date	Estimate #
4/2/2022	1194

Name / Address
Board Of Fire Commissioners Buean Borough Anthony Abriola

Project

Description	Qty	Rate	Total
Econ air 10' long stainless steel hood model # 4824EX-2 with 3" back stand off 430 stainless where exposed Fire cabinet on right hand side Filters with clean guard stainless steel baffles L55 series E26 Canopy light fixture 16' exhaust riser grease cup Field wrapper 18' high front left and right Factory electrical package	1	6,200.00	6,200.00
Ansul-3.0 Ansul 3 gallon fire system utility cabinet includes pre piped hood with detection, tanks, release mechanism, microswitches and pull station. MGVA2 gas valve - 2 " mechanical gas shut off switch Ansul model 28-55610		4,800.00	4,800.00
EADU85 exhaust fan high speed upblast centrifugal fan 2150 cfm 1 phase 115 volts 60 hertz		1,500.00	1,500.00
SC-110110MA 120 volt 1 phase electric controller for 1 exhaust fan, exhaust on in fire, lights out in fire, relay on/off with fan switch		1,850.00	1,850.00
16 " round stainless steel pipe duct system for exhaust including all tees and clean outs		3,500.00	3,500.00
Remove existing hood, exhaust duct work, exhaust fan. install new hood, new exhaust fan, modify existing side wall penetration, install new 16' round stainless steel exhaust pipe with cleanouts, install gas valve for ansul system, pull station, hook up electrical to fan and hood, install stainless steel wrapper. Charge and test of ansul system		3,000.00	3,000.00
costs includes complete removal and disposal, start up and test. * Does not include permit fees as permits very based on boro and installation			20,850.00
		Total	\$20,850.00