



DATE	INVOICE NO.
10/13/17	1013201771

TOWN OF PHILLIPSBURG
675 CORLISS AVENUE
PHILLIPSBURG, NJ 08865

RIVERSIDE WAY
200 AMP ELECTRICAL SERVICE

NET 10-28LATE

PLEASE REMIT TO:
PHILIP F. KAYS BOX 675 PHILLIPSBURG, NJ 08865

\$10,735.00



Kays Electric

Philip F. Kays Electrical Contractor

283 North Main St.

Phillipsburg, NJ 08865

(908) 859-1331 (908) 995-9488 (610) 258-6675

FAX (908) 859-5244

www.kayselectric.com

Proposal

Proposal Submitted To:
Town of Phillipsburg
675 Corliss Ave.
Phillipsburg, NJ

Job:
Riverview Way
200 Amp Electrical Service
Phillipsburg, NJ

Date:
September 11, 2017

We hereby submit specifications and conditions as follows:

Installation of new 200 Amp 120/240v single-phase underground enclosure electrical service to include the following:

1. 200 Amp Underground Bypass Handle equipped meter cabinet as per JCP&L specifications.
2. APEX 50" x 30" x 18" aluminum free standing outdoor rated enclosure with latching handle and backboard.
3. 200 Amp 120/240v 30 circuit Square D QO Main Breaker Panel.
4. Grounding and bonding as per the National Electrical Code.
5. PVC SCH 80 riser and underground conduit to utility pole as per JCP&L specifications.
6. Six GFI receptacles on six 120v dedicated circuits.
7. Installation of three 100 amp 240v Square D QO branch breakers to accommodate temporary sub panels for festivals and events. Sub panels to be provided and installed by others as needed.

Installation of handhole and future piping to accommodate temporary power for festivals and events to include the following:

1. Three 2" PVC conduits installed from inside of enclosure to the handhole.
2. Three 1 1/2" PVC conduits installed directly from the Main Breaker panel to the handhole.

All work to be completed in time for the Pork Roll Festival.

Price Assumes:

1. Kays Electric to provide all excavation and associated concrete work.
2. Rock and spoil removal to be excluded.
3. Kays Electric to coordinate with JCP&L as needed.
4. All labor and material to be tax exempt.

Labor and Material as above specified.....\$10,735.00

Pricing does not include permit and/or inspection fees if applicable.

Pricing does not include JCP&L and/or any other utility company fees if applicable.