

BLOCK 966 LOT 17 QUALIFICATION CODE _____ ADDRESS (SITE) 553 Nicholas Rd PERMIT NO. 17-3632



CONSTRUCTION PERMIT APPLICATION

Applicant Completes: Sections I, II, III (optional), IV, VI, and VII

I. IDENTIFICATION

1. Proposed Work Site at: 553 Nicholas Rd Brick NJ
2. Name of Owner in Fee: Curto Residence
Tel. (732) _____ e-mail _____
Address 553 Nicholas Rd Brick 08724
street municipality zip code
3. Ownership in Fee: Public _____ Private ☒
4. Principal Contractor: Reliable Power & Solar Tel. (732) 367-1166
Address 1085 Route 9 e-mail solardesign@getrpsnow.com
Howell, NJ 07731
License No. OR, if new home, Builder Reg. No. 11223B Exp. Date 3/31/18
Home Improvement Contractor Registration No. or Exemption Reason (if applicable): 13VHO5266200
Federal Emp. ID No. 16-1732531 FAX: (732) 942-3979
5. Architect or Engineer Cirangle Architects Contact LARRY
Address 14 Plaza Nine Manalapan NJ e-mail _____
Tel. (732) 303-7822 FAX: (732) _____
6. Responsible Person in Charge once Work has Begun Chris DiPasquale
Tel. (732) 367-1166 FAX: (732) 942-3979

V. FEE SUMMARY (for office use only)

		Update	Update
1. Building	\$ <u>375</u>	☒	
2. Electrical	\$ <u>375</u>	☒	
3. Plumbing			
4. Fire Protection			
5. Elevator Devices			
6. Subtotal			
7. Less 20% for State Plan Review	\$ _____		
8. Subtotal	\$ _____		
9. State Permit Surcharge Fee	\$ <u>117</u>		
10. Subtotal	\$ <u>75</u>		
11. Cert. of Occupancy			
12. Other	\$ <u>792</u>		
13. TOTAL	\$ _____		

VI. BUILDING/SITE CHARACTERISTICS

	(office use only)
1. Number of Stories	_____
2. Height of Structure	_____ ft.
3. Area — Largest Floor	_____
4. New Building Area	<u>26.1 kw</u>
5. Volume of New Structure	_____ cu. ft.
6. Max. Live Load	_____
7. Max. Occupancy Load	_____
8. If Industrialized Building: State Approved _____ HUD _____	
9. Total Land Area Disturbed	_____ sq. ft.
10. Flood Hazard Zone	_____
11. Base Flood Elevation	_____ ft.
12. Wetlands yes _____ no _____	

IIa. PROPOSED WORK

- ☐ Minor Work ☐ New Building ☐ Addition ☐ Demolition
☐ Repair ☒ Alteration ☐ Renovation ☐ Reconstruction
☐ Asbestos Abat. -Subch. 8 ☐ Lead Hazard Abatement ☐ Radon Remediation ☐ Annual Permit

IIb. SUBCODES

(Check all that apply)

- ☒ Building
☒ Electrical
☐ Plumbing
☐ Fire Protection
☐ Elevator

FOR OFFICE USE ONLY (Optional)

Est. Cost	Plans Rec'd by	Date Rec'd	Rejection Date	Approval Date	Re-viewer	Resubmission Dates Approval	Rejection	Re-viewer
<u>7493.76</u>	<u>MFF</u>	<u>10/11/17</u>		<u>10-17-17</u>	<u>JP</u>			
<u>54456.26</u>				<u>10/24/17</u>	<u>PJK</u>			

TOTAL COST 61,950

VII. DESCRIPTION OF BUILDING USE

A. RESIDENTIAL (primary use)

1. State Specific Use: _____
2. Use Group, Proposed: _____
3. Change in Use Group, Indicate Present: _____
4. No. of dwelling units: Total Units Income-restricted
Gained, Sale _____
Gained, Rental _____
Lost, Sale _____
Lost, Rental _____

B. NON-RESIDENTIAL (primary use)

1. State Specific Use: _____
2. Use Group, Proposed: _____
3. Change in Use Group, Indicate Present: _____
C. MIXED USE -List secondary use(s): _____
D. Construct. Classification: Present _____ Proposed _____

III. PLAN REVIEW (optional)

DO YOU WANT:

1. ☐ Partial Releases
2. ☐ Prototype Processing

IV. DOES OR WILL YOUR BUILDING CONTAIN ANY OF THE FOLLOWING?

1. ☐ Elevators/Escalators/Lifts/
Dumbwaiters/Moving Walks
2. ☐ High Pressure Boilers
3. ☐ Pressure Vessels
4. ☐ Refrigeration Systems
5. ☐ Cross-Connections/Backflow Preventers
6. ☐ Hazardous Uses/Places of Assembly
7. ☐ Sprinklers/Standpipes
8. ☐ Smoke Control Systems in Open Wells
9. ☐ Underground Storage Tanks
10. ☐ Swimming Pools, Spas and Hot Tubs
11. ☐ LPGas Tanks
12. ☐ Fire Alarm



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723

Date Issued 1/25/2018
Control Number C-17-004498
Permit Number 17-3632
Permit Issue Date 10/31/2017
Certificate Number 17-3632

Certificate

Construction Code Division
(Certificate of Approval)

Identification

Work Site Location: 553 NICHOLAS RD. Brick Township, NJ Block: 966 Lot: 17 Qual: _____
Owner in Fee: GURTO, NATHON
Owner Address: 553 NICHOLAS RD BRICK NJ 08724
Telephone: _____
Contractor Reliable Power & Solar, Inc.
Address 1085 Route 9 Howell NJ 07731
Telephone: (732) 367-1166 Fax: (732) 942-3979
License Number or Builders Registration Number: 11223B 13VH05266200 Federal Emp. Number: 16-1732531

Home Warranty Number: _____

Type of Warranty Plan: ☐ State ☐ Private

Use Group: R-5 Construction Classification: _____

Maximum Live Load: 0 Maximum Occupancy Load: 0

Description of Work/Use: SOLAR PANELS ...INSTALL 26.1 kw ROOF MOUNT PHOTOVOLTAIC SOLAR SYSTEM

Certificate Comments:

☐ **Certificate of Occupancy**

This serves notice that said building or structure has been constructed in accordance with the New Jersey Uniform Construction Code and is approved for occupancy.

☒ **Certificate of Approval**

This serves notice that the work completed has been constructed or installed in accordance with the New Jersey Uniform Construction Code and is approved. If the permit was issued for minor work, this certificate was based upon what was visible at the time of inspection.

☐ **Certificate of Continued Occupancy**

This serves notice that based on a general inspection of the visible parts of the building there are no imminent hazards and the building is approved for continued occupancy.

☐ **Temporary Certificate of Compliance**

The following conditions must be met no later than or the owner will be subject to fine or order to vacate:

This certificate has an expiration date of:

Conditions to be met:

☐ **Certificate of Clearance - Lead Abatement 5:17**

This serves notice that based on written certification, lead abatement was performed as per NJAC5:17 to the following extent.

- ☐ Total removal of lead-based paint hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Clearance - Asbestos Abatement**

This serves notice that based on written certification, asbestos abatement was performed to the following extent.

- ☐ Total removal of asbestos hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Compliance**

This serves notice that said potentially hazardous equipment has been installed and/or maintained in accordance with the New Jersey Uniform Construction Code and is approved for use until

☐ **Temporary Certificate of Occupancy**

The following conditions must be met no later than: or the owner will be subject to fine or order to vacate:

This certificate has an expiration date of:

Conditions to be met:

David Newman Jr

Construction Official

Fee: \$0.00

Check Number: _____

Collected By: _____

RECEIVED
OCT 13 2017

OCT 13 2017

ZONING

22

DATE DENIED:

Figure 1

DATE APPROVED:

10/13/17

INTLS:

SK-28

1. The first step in the process is to identify the problem or issue that needs to be addressed. This involves gathering information and understanding the context of the problem.

[illegible]

1

INITIALS:

10/19/17

SENT TO OWN

✓ 52

RECEIVING CLERK _____
DATE REC'D _____
BLOCK: 944 LOT: 17 QUALIFIER: _____ SITE ADDRESS: 533 Nicholas Rd

ZONING PERMIT APPLICATION

PERMIT # 27-17-01337
DATE ISSUED 10/31/17

IDENTIFICATION:

1. NAME OF OWNER IN FEE: Gusto Residence
COMPLETE ADDRESS: 533 Nicholas Rd
Brook NJ 08874
PHONE # _____ EMAIL: _____

2. NAME OF APPLICANT: Reliable Power & Sofas
APPLICANT ADDRESS: 1085 Rt 9
Howell NJ 07731
PHONE # 732 367 1116 EMAIL: sofadesign@getresnow.com

3. RESPONSIBLE PERSON FOR WORK: Chris DiPasquale
PHONE # 732 367 1116 FAX # 732 942-3979

4. SIGNATURE OF APPLICANT: [Signature]

FEE SUMMARY:

APPLICATION FEE: \$ 15-
OTHER: \$ _____
TOTAL: \$ 15-

REQUIRED BY APPLICANT

RESIDENTIAL: ✓
COMMERCIAL: _____
EXISTING USE: SFR
PROPOSED USE: SFR

BOARD APPROVAL: _____ PB _____ ZB _____
RESOLUTION#: _____
APPROVAL DATE: _____

PROJECT DESCRIPTION: (PLEASE CHECK APPLICABLE WORK & DESCRIBE)

*NEW BUILDING: _____ *ADDITION _____ *ALTERATION _____ *PORCH _____ *DECK _____

POOL: ABOVE GROUND _____ IN GROUND _____ FENCE: HEIGHT _____ TYPE _____ MATERIAL _____

HEIGHT: _____ (*IF APPLICABLE)

OTHER Roof top mounted solar panel system

DESCRIPTION: Rail/Rack mount

ZONING REVIEW: _____ DATE REVIEWED: 10-16-17 DATE DENIED: _____ DATE APPROVED: 10-16-17 INTLS: OK
(SEE BACK PAGE)



CONSTRUCTION PERMIT

Date Issued 10/31/17
Control # C-17-004498
Permit # 17-3632

IDENTIFICATION Block: 966 Lot: 17 Qualifier: _____
Work Site Location: 553 NICHOLAS RD. Brick Township, NJ Contractor: Reliable Power & Solar, Inc.
Address: 1085 Route 9 Howell NJ 07731
Owner in Fee: GURTO, NATHAN
553 NICHOLAS RD. BRICK NJ 08724 Telephone: (732) 367-1166
Telephone: _____ Lic. No. or Bldrs. Reg. No. 13VH05266200 11223B 13VH05266200
Federal Employee No. 16-1732531

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

SOLAR PANELS...INSTALL 26.1 kw ROOF MOUNT PHOTOVOLTAIC SOLAR SYSTEM

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.
Estimated Cost of Work \$61,949

D. Neumann Jr.
Construction Official

Date 10/30/17

U.C.C. F170
equiv (rev 1/04)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)	
Building	\$375
Electrical	\$225
Plumbing	\$0
Fire Protection	\$0
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$117
CO Fee	
Other	\$0
Total	\$717
Check No. <u>1565</u>	
Cash	\$0
Credit	\$0
Collected By <u>CW</u>	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

- ☒ Required inspections for all subcodes for one- and two-family dwellings are as follows:
1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
 2. Foundations and all walls up to grade level prior to back filling.
 3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and /or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
 4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

- ☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

- ☒ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

- ☒ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.

BUILDING \$375.00
ELECTRIC \$225.00
DCA \$117.00
CHECK \$792.00

RECEIVED

OCT 13 2017

ZONING

ZONING REVIEW:

DATE REVIEWED: 10/13/17 DATE DENIED: — DATE APPROVED: 10/13/17 INTLS: NC28

[illegible]

COMMENTS:

DATE:

INITIALS:

10/19/17	SENT TO OWNER
----------	---------------

Gurto Residence
533 Nicholas Road
Brick, NJ 08724





ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 9106 Lot 17 Qualification Code _____
Work Site Location 553 Nicholas Rd
Owner in Fee Gyroto Residence
Address 553 Nicholas Rd
BRICK NJ 08724
Tel () Reliable Power & Solar
Contractor 1085 RT9
Address Howell NJ 07731
Tel (732) 367-1146 FAX (732) 942-3979
Contractor License No. 13VH05366200
Federal Emp. No. 16-1732531

B. ELECTRICAL CHARACTERISTICS

Use Group Present _____ Proposed _____
[] Pole/Pad # _____ [] Temporary [] Other
Building Occupied as _____ Utility Co. SPAL
Est. Cost of Elec. Work \$ 54,456.26

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSTRUCTIONS	Dates (Month/Day)
[] No Plans Required			Type: Rough <u>Solar</u>	Failure Approval <u>12-8-17</u>
Joint Plan Review Required:				
[] Building [] Plumbing			Barrier-Free	
[] Fire [] Elevator			Trench	
[] Elec. Plans Approved			Temp. Serv.	
Date: <u>10/25/17</u>			Constr. Serv.	
Approved by: <u>[Signature]</u>			TCO	
			Other	
			Service	
			Final	
			Barrier-Free	
SUBCODE APPROVAL			Temp. Cut-in-Card Date Issued	
[] CO [] CCO [] CA			Final Cut-in-Card Date Issued	
Date: <u>1/22/18</u>			Annual Pool Inspection	
Approved by: <u>[Signature]</u>			Date of Grounding and Bonding Certification	

Date Received
Control #

Date Issued
Permit #

C. CERTIFICATION BY FIELD OF OFFICE

I, the undersigned, being duly sworn, certify that the above information is true and correct, and am authorized to make this certification.

Applicant Signature: [Signature] Date: 10/25/17

M. Licensee Signature: [Signature] Date: 10/25/17

D. TECHNICAL SITE DATA

QTY. Size of Poles _____

Lighting Fixtures _____

Receptacles _____

Switches _____

Detectors _____

Light Poles _____

Motors—Fract. HP _____

Emergency & Exit Lights _____

Communications Points _____

Alarm Devices/F.A.C. Panel _____

26.1 Kw size

TOTAL NUMBERS _____

Pool Permit/with UW Lights _____

Storable Pool/Spa/Hot Tub _____

KW Elec. Range/Receptacle _____

KW Oven/Surface Unit _____

KW Elec. Water Heater _____

KW Elec. Dryer/Receptacle _____

KW Dishwasher _____

HP Garbage Disposal _____

KW Central A/C Unit _____

HP/KW Space Heater/Air Handler _____

KW Baseboard Heat _____

HP Motors 1/4 HP _____

KW Transformer/Generator _____

AMP 200 Next Meter

AMP Subpanels 200

AMP Motor Control Center 100

KW Elec. Sign/Outline Light _____

2 Solar Edge Inverters

10

Administrative Surcharge \$

Minimum Fee \$

State Permit Surcharge Fee \$

TOTAL FEE \$

CERTIFICATION IN LIEU OF OATH

I. OWNER SECTION (to be completed if the applicant is the owner in fee)

I hereby certify that I am the owner in fee of the property listed on Page 1.

Mark the following applicable boxes:

- A. ☐ I further certify that a new home (private residence) will be constructed on this property for my own use and occupancy. This dwelling is to be occupied by myself and is not to be used for any purpose other than single family residential use. I attest that all construction, plumbing, or electrical work will be done, in whole or in part, by me or by subcontractors under my supervision, in accordance with all applicable laws; and, I further acknowledge that said new home is not covered under the New Home Warranty and Builders Registration Act (N.J.S.A. 46:3B-1 et seq.) and that such fact shall be disclosed to any person purchasing this property within ten years of the date of issuance of a certificate of occupancy.

I UNDERSTAND THAT IN MARKING BOX A, I ACKNOWLEDGE THAT I AM ASSUMING RESPONSIBILITY FOR THE WORK DONE ON SAID PROPERTY, THE CONDITION OF THE PROPERTY PRIOR TO, DURING, AND AFTER ANY WORK PERFORMED, AND FOR THE PERFORMANCE OF THE SUBCONTRACTORS I HIRE, EMPLOY, OR OTHERWISE CONTRACT OR WITH WHOM I MAKE AGREEMENTS TO PERFORM WORK. I AM VOLUNTARILY AND KNOWINGLY ASSUMING THIS RESPONSIBILITY.

- B. ☐ I further certify the following as required by the New Jersey Uniform Construction Code, N.J.A.C. 5:23-2.15(f)1.ix:

I personally prepared the plans submitted for: 1) the new home referred to in A.; or, 2) an addition, alteration, renovation, or repair to an existing single family residence owned and occupied by myself and located on the property listed on Page 1; or, 3) a new structure that will be physically separate from, but that will be deemed part of, an existing single family residence that is owned and occupied by myself and located on the property listed on Page 1.

- C. ☐ I further certify that I will perform or supervise the following work:

C.1. ☐ Building C.2. ☐ Fire Protection

I further certify that I will perform the following work:

C.3. ☐ Electrical C.4. ☐ Plumbing

- D. ☐ I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I understand that if any of the above statements are willfully false, I am subject to punishment.

Signature _____ Date _____

II. AGENT SECTION (to be completed if the applicant is not the owner in fee)

I hereby certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(d): the proposed work is authorized by the owner in fee; and I have been authorized by the owner in fee to make this application as his agent.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I understand that if any of the above statements are willfully false, I am subject to punishment.

☐ Check if contractor.

Agent Name **Reliable Power & Solar**

Address **1085 Route 9**
Howell, NJ 07731

Telephone **732 367-1166**

Signature _____

III. ☐ LEAD HAZARD ABATEMENT: Include Homeowner or Building Owner Affidavit as per N.J.A.C. 5:17.

IV. ☐ HOME ELEVATION: Include Home Elevation Contractor Certification as per N.J.S.A. 52:27D-123.16.



BUILDING SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 9606 Lot 17 Qualification Code _____

Work Site Location 533 Nicholas Rd

Owner in Fee: Guaranteed Residence

Address 533 Nicholas Rd

Tel. () 8724

Contractor Reliable Power & Solar

Address 1085 Rt 9, Howell, NJ 07731

Tel. (732) 367-1166 FAX: (732) 942-3979

Contractor License No. or Builder Registration No. 13VH05266200

Federal Emp. No. 16-1732531

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Dates (Month/Day)	Initial
☐ No Plans Required			Type:	Failure	Approval
☒ All	<u>10-17-17</u>	<u>SSP</u>	Footings		
☐ Footing			Footings Bonding		
☐ Foundation			Foundation		
☐ Frame			Slab		
☐ Other			Frame		
☐ Subcode			Truss Sys./Bracing		
☐ Plan Review			Barrier-Free		
☐ Elec.			Insulation		
☐ Plumb.			Finishes -Base Layer		
☐ Fire			Finishes -Final		
☐ Elevator			Energy		
☐ Mechanical			Mechanical		
☐ TCO			TCO		
☐ Other			Other		
☐ Final			Final		
☐ Barrier-Free			Barrier-Free		

SUBCODE APPROVAL

☐ CO ☐ CCO ☒ CA

Date: 01/19/18

Approved by: [Signature]

B. BUILDING CHARACTERISTICS

Use Group	Present	Proposed	Est. Cost of Bldg. Work:
Constr. Class	Present	Proposed	1. New Bldg. \$ <u>7,493,116</u>
No. of Stories	<u>2</u>		2. Rehabilitation \$ <u>7,493,116</u>
Height of Structure	<u>24ft</u>		3. Total (1+2) \$ <u>7,493,116</u>
Area — Largest Floor	<u>1000</u>		
New Bldg. Area/All Floors	<u>0</u>		
Volume of New Structure	<u>0</u>		
Total Land Area Disturbed	<u>0</u>		

U.C.C. F110
(rev. 07/03)

1 White = Inspector Copy
3 Pink = Office Copy

2 Canary = Office Copy
4 Hard = Applicant Copy

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Installation of pre-engineered solar racking system to accommodate photovoltaic modules.
See drawings enclosed.

TYPE OF WORK:

☐ New Building
☐ Addition
☐ Rehabilitation
☐ Roofing
☐ Siding
☐ Fence
☐ Sign
☐ Pool
☐ Asbestos Abatement Subchapter 8
☐ Lead Haz. Abatement NJAC 5:17
☒ Other Photovoltaic System Install
☐ Demolition

FEE (Office Use Only)
\$ _____

Administrative Surcharge \$ _____
Minimum Fee \$ _____
State Permit Surcharge Fee \$ _____
TOTAL FEE \$ _____

10/31/17
17-3632



Brick Township
401 Chambers Bridge Rd.

Brick, NJ 08723
(732) 262-1336

Date Issued:
Application Number:
Application Date:
Project Number:
Permit Number:
Fee:

10/31/17
ZA-17-01299
10/11/2017

22-17-01337
\$75.00

Zoning Permit

Worksite **553 NICHOLAS RD.**
Location: **Brick Township, NJ 08724**

Block: **966**
Lot: **17**
Qualifier:
Zone: **R-10**

Owner: **GURTO, NATHON**
Address: **553 NICHOLAS RD**
BRICK, NJ 08724

Applicant: **Reliable Power & Solar, Inc.**
Address: **1085 Route 9**
Howell, NJ 07731

Application Approved Date: 10/11/2017

This Certifies that an application for the issuance of a Zoning Permit has been examined.

Use is: _____
Nonconforming Use is: Single-Family Residential

Work Description:

Solar Energy System - 90- 290W Trina Solar, 26.1kW AZIMUTH micro-inverters, mounted on the roof of the house.

Additional Zoning Permit is required for additional work.

Upon review it was determined that the Zoning Permit:

- ☒ Permitted by Ordinance
- ☐ Permitted by Variance approved on: _____
- ☒ Valid Nonconforming Use is established by
 - ☐ Zoning Board of Adjustment
 - ☒ Zoning Officer



Christopher J. Romano, Assistant Zoning Officer


10/11/2017
Date




Sean Kinnevy, Zoning Officer

10/13/17
Date

26 -290W PANELS
7.54 KW
27° SLOPE, 16° AZIMUTH



15 -290W PANELS
4.35 KW
27° SLOPE, 16° AZIMUTH



FRONT MIDDLE ROOF PLAN

SCALE: 1/8" = 1'-0"

FRONT RIGHT ROOF PLAN

SCALE: 1/8" = 1'-0"

DIMENSIONS ARE RELATIVE TO SLOPE

NOTE: EXISTING STRUCTURE IS ADEQUATE TO SUPPORT
DESIGN SNOW LOAD OF 25 PSF / ROOF TL 35 PSF
DESIGN BASIC WIND SPEED OF 125 MPH / 24 PSF
ADDITIONAL DEAD LOAD OF SOLAR PANELS AT 3 PSF
WITH ALUMINUM RAIL MOUNTING SYSTEM

ENGINEERING REVIEW
APPROVED

DATE: 02/11/17
BY: [Signature]

PANEL SUMMARY:

90 - 290W PANELS
26.1 KW

USE GROUP: R5
TYPE 5B CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014

Project

GURTO RESIDENCE
533 NICHOLAS ROAD
BRICK, NJ 08724



RELIABLE POWER & SOLAR
1085 ROUTE 9
HOWELL, NJ 07731
732-367-1166

NY License No. 10687
PA License No. 1A-015580B



Circle Architects
ARCHITECTURE, INTERIOR DESIGN
14 PLAZA, SUITE 900
NEWARK, NJ 07102
(973) 305-7822

Date: 08/28/2017

Scale: 1/8" = 1'-0"

Drawn: KC

Check: LSC

Project No. 1703-105

Sheet No.

A-2

ENGINEERING PERMIT APPLICATION

RECEIVING CLERK: _____
PERMIT #: _____

BLOCK: 94 LOT: 17 ADDRESS: 533 Nicholas Rd

IDENTIFICATION

1. WORK SITE ADDRESS: 533 Nicholas Rd

2. NAME OF OWNER IN REE: Guarto Residence

ADDRESS: 533 Nicholas Rd PHONE: [REDACTED]

Bricklot 08724 FAX # ()

3. PRINCIPAL CONTRACTOR: Meluhali Powers & Son

ADDRESS: 1085 6th PHONE: 732-317-4166

Howell St 07701 FAX: 732-942-2979

4. ARCHITECT OR ENGINEER: George Architects

ADDRESS: 144022 Nee, Harkness PHONE: 732-303-7822

5. RESPONSIBLE PERSON FOR WORK: Chris DiPasquale

ADDRESS: 1085 Rt 9, Howell St 07731

PHONE: 732-317-4166 FAX: 732-942-2979 E-MAIL: Solar design

PROJECT DESCRIPTION: ☐ GRADING/CLEARING ☐ ROAD OPENING

☐ SOIL REMOVAL/FILL ☐ RETAINING WALL ☐ POOL

☐ BULWHEAD DOCK ☐ DWELLING ☐ TREE REMOVAL

OTHER: Solar Port Top Mounted Panels

LENGTH: _____ WIDTH: _____ HEIGHT: _____

ENGINEERING REVIEW

DATE RECEIVED: _____

DATE REJECTED: _____

DATE APPROVED: _____

INITIALS: _____

FEE SUMMARY

APPLICATION FEE: \$ _____

REVIEW FEE: \$ _____

INSPECTION FEE: \$ _____

OTHER: \$ _____

BONDS: \$ _____

TOTAL: \$ _____

SPECIAL CONDITIONS

OCEAN COUNTY SOILS: _____

DRAINAGE EASEMENTS: _____

UTILITY EASEMENTS: _____

CONSERVATION EASEMENTS: _____

REPAIR REQUIREMENTS: _____


D.E.P. PERMITS: _____

BOARD APPROVAL: ☐ YES ☐ NO


APPLICATION NUMBER: _____

APPROVED DATE: _____

26 -290W PANELS
7.54 KW
27° SLOPE, 16° AZIMUTH



15 -290W PANELS
4.35 KW
27° SLOPE, 16° AZIMUTH



DIMENSIONS ARE RELATIVE TO SLOPE

FRONT MIDDLE ROOF PLAN

SCALE: 1/8" = 1'-0"

FRONT RIGHT ROOF PLAN

SCALE: 1/8" = 1'-0"

NOTE: EXISTING STRUCTURE IS ADEQUATE TO SUPPORT
DESIGN SNOW LOAD OF 25 PSF / ROOF TL 35 PSF
DESIGN BASIC WIND SPEED OF 125 MPH / 24 PSF
ADDITIONAL DEAD LOAD OF SOLAR PANELS AT 3 PSF
WITH ALUMINUM RAIL MOUNTING SYSTEM

PANEL SUMMARY:
90 - 290W PANELS
26.1 KW

USE GROUP: R5
TYPE 5B CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014

Project

GURTO RESIDENCE
533 NICHOLAS ROAD
BRICK, NJ 08724



RELIABLE POWER & SOLAR
1085 ROUTE 9
HOWELL, NJ 07731
732-367-1166

PA License No. 10977
PA License No. RA-0153908



Ciringle Architects
ARCHITECTURE, INTERIOR DESIGN
141 PLAZA, NINE
73523 800-7622

Date: 08/28/2017 Project No. 1703-105


Scale: 1/8" = 1'-0" Sheet No.

Drawn: KC


Check: LSC

A-2


14-290W PANELS
4.06 KW
27° SLOPE, 196° AZIMUTH



29-290W PANELS
8.41 KW
27° SLOPE, 196° AZIMUTH



6-290W PANELS
1.74 KW
27° SLOPE, 196° AZIMUTH



REAR LEFT ROOF PLAN

SCALE: 1/8" = 1'-0"

REAR MIDDLE ROOF PLAN

SCALE: 1/8" = 1'-0"

REAR RIGHT ROOF PLAN

SCALE: 1/8" = 1'-0"

DIMENSIONS ARE RELATIVE TO SLOPE

NOTE: EXISTING STRUCTURE IS ADEQUATE TO SUPPORT
DESIGN SNOW LOAD OF 25 PSF / ROOF TL 35 PSF
DESIGN BASIC WIND SPEED OF 125 MPH / 24 PSF
ADDITIONAL DEAD LOAD OF SOLAR PANELS AT 3 PSF
WITH ALUMINUM RAIL MOUNTING SYSTEM

PANEL SUMMARY:
90-290W PANELS
26.1 KW

USE GROUP: R5
TYPE 5B CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014


Project

GURTO RESIDENCE
533 NICHOLAS ROAD
BRICK, NJ 08724



RELIABLE POWER & SOLAR
1085 ROUTE 9
HOWELL, NJ 07731
732-367-1166

NJ License No. 10877
PA License No. RA-018809



ARCHITECTURE, INTERIOR DESIGN
14 PLAZA NINE
BRICK, NJ 08726
(732) 803-7828

Date
08/18/2017

Project No.
1703-105


Scale
1/8" = 1'-0"

Sheet No.

A-1

Drawn
KC

Check
LSC



CIRANGLE ARCHITECTS

14 PLAZA NINE
MANALAPAN, NJ 07726
732-303-7822 PHONE
732-303-7833 FAX

September 27, 2017

Brick Township Municipal Building
Building Department
401 Chambersbridge Road
Brick, NJ 08723

Zoning Review

Approval

By: an

Date: 10-11-17

Attn: Mr. Michael Vecchio: Subcode Official

FILE COPY

Re: Solar Panel/Support Rack Installation

Gurto Residence

553 Nicholas Road

Brick, NJ 08724

CA Project No. 1703-105

TOWNSHIP OF BRICK	
RELEASED FOR PERMIT	INITIAL DATE
Building Subcode	
Plumbing Subcode	
Fire Subcode	
Electrical Subcode	
Plan Reviewer	<u>PJC 10/23/17</u>
Plans Released	<u>10-19-17</u>
Construction Official	

Dear Mr. Vecchio,

I am writing to address and certify the following items regarding the proposed installation of 90 roof mounted panels as manufactured by Trinasolar: Photovoltaic Module, TSM-290PA05 (41.0 lbs/panel x 90 = 3,690 lbs total), and support racks (900 lbs total) as manufactured by SnapNrack. The system shall be located over a roof area of approximately 1,584 sq ft. The contractor shall install the panels and support racks as per the code compliant planning and assembly Installation Manual: Series 100 as provided by SnapNrack.

1. The existing building is a 1 story wood framed structure with 6:12 pitch roofs. The existing roof rafter assembly can adequately support the proposed panel/rack installation using 5/16" dia. x 4" long stainless steel lag bolts @ 48" oc under IRC 2015, New Jersey edition, for materials, loads, and stresses: live load conditions based on wind loads of 125 mph (3 second gust) and exposure 'C' and Chapter 3: Building Planning, Section 301.2.1: Wind Limitations. This lag bolt fastening spacing correlates to the existing rafter spacing. There are no modifications required to the existing roof framing.
2. Support rack anchorage will comply with wind loads of 125 mph (3 second gust) as required by the IRC 2015, New Jersey edition, Chapter 3: Building Planning.
3. Photovoltaic Modules shall resist wind pressure of 24 lbs per square foot based on 125 mph wind speed and exposure 'C.'

Gurto
September 27, 2017
Page 2

4. Design snow load = 20 psf and roof TL = 40 psf (30 psf live / 10 psf dead).
5. The additional dead load of the solar panels and aluminum rail mounting system is 3 lbs per square foot.

This is to certify that as per our code/structural review, the proposed solar panel /support rail installation shown on Cirangle Architects Drawings A-1, A-2, A-3, & A-4 (dated September 26, 2017) meets or exceeds the code parameters and structural requirements cited in this letter.

Please feel free to contact me if you have any questions regarding these items.

Thank you,



Lawrence S. Cirangle
Registered Architect
NJ License No. 10677




cc: C. Di Pasquale (RPS)



29 -290W PANELS
8.41 KW
27° SLOPE, 196° AZIMUTH

6 -290W PANELS
1.74 KW
27° SLOPE, 196° AZIMUTH

14 -290W PANELS
4.06 KW
27° SLOPE, 196° AZIMUTH



REAR LEFT ROOF PLAN
SCALE: 1/8" = 1'-0"

REAR MIDDLE ROOF PLAN
SCALE: 1/8" = 1'-0"

REAR RIGHT ROOF PLAN
SCALE: 1/8" = 1'-0"

DIMENSIONS ARE RELATIVE TO SLOPE

NOTE: EXISTING STRUCTURE IS ADEQUATE TO SUPPORT
DESIGN SNOW LOAD OF 25 PSF / ROOF TL 35 PSF
DESIGN BASIC WIND SPEED OF 125 MPH / 24 PSF
ADDITIONAL DEAD LOAD OF SOLAR PANELS AT 3 PSF
WITH ALUMINUM RAIL MOUNTING SYSTEM

PANEL SUMMARY:
90 - 290W PANELS
26.1 KW

USE GROUP: R5
TYPE SB CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014

Project

GURTO RESIDENCE
553 NICHOLAS ROAD
BRICK, NJ 08724



RELIABLE POWER & SOLAR
1085 ROUTE 9
HOWELL, NJ 07731
732-367-1166



Girangle Architects
ARCHITECTURE, INTERIOR DESIGN
1401 LAZARUS AVE.
MANALAPAN, N.J. 07728
(732) 363-7822

Date
08/16/2017

Project No.
1703-105

Scale
1/8" = 1'-0"


Sheet No.

A-1

Drawn
XC


Chkd
LSC

26 -290W PANELS
7.54 KW
27° SLOPE, 16° AZIMUTH



FRONT MIDDLE ROOF PLAN
SCALE: 1/8" = 1'-0"

15 -290W PANELS
4.35 KW
27° SLOPE, 16° AZIMUTH




FRONT RIGHT ROOF PLAN
SCALE: 1/8" = 1'-0"

DIMENSIONS ARE RELATIVE TO SLOPE

NOTE: EXISTING STRUCTURE IS ADEQUATE TO SUPPORT
DESIGN SNOW LOAD OF 25 PSF / ROOF TL 35 PSF
DESIGN BASIC WIND SPEED OF 125 MPH / 24 PSF
ADDITIONAL DEAD LOAD OF SOLAR PANELS AT 3 PSF
WITH ALUMINUM RAIL MOUNTING SYSTEM


PANEL SUMMARY :
90 - 290W PANELS
26.1 KW

USE GROUP: R5
TYPE 5B CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014



GURTO RESIDENCE
533 NICHOLAS ROAD
BRICK, NJ 08724

Project	Date 09/26/2017		Project No. 1703-105
	Scale 1/8" = 1'-0"		Sheet No.
	Drawn KC		A-2
	Chkd LSC		



REAR HOUSE ELEVATION
N.T.S.

USE GROUP: R5
TYPE 5B CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014

Project GURTO RESIDENCE 533 NICHOLAS ROAD BRICK, NJ 08724	Date 09/26/2017	Project No. 1703-105
	Scale 1/8" = 1'-0"	Sheet No. A-3
	Drawn KC	
	Chkd LSC	

RELIABLE POWER & SOLAR
1085 ROUTE 9
HOWELL, NJ 07731
732-367-1166

Triangle Architects
ARCHITECTURE, INTERIOR DESIGN
14 PLAZA NINE
MANALAPAN, N.J. 07726
(732) 303-7522

GENERAL NOTES:


1. Installers shall visit the site of the proposed work and be fully acquainted with the existing conditions prior to installation in order that all requirements and conditions are fully understood. All areas and conditions indicated on the drawing must be verified by installers and subcontractors at the site prior to start of work.
2. Unknown or hidden structural deficiencies or dimensional discrepancies relating to the existing structure or the renovated area must be reported to Architect immediately upon discovery. All changes to plan must be approved by Architect. Methods and systems of erection, demolition and reconstruction and jobsite safety is the responsibility of the contractor.
3. Owner shall oversee the work of contractor unless the Architect is engaged by the owner to administer construction and periodically visit the site. Blueprint Drawings are not to scale. All dimensions to be verified and confirmed in the field by installer prior to installation or construction. Architect shall be notified immediately of any discrepancies to the Plan or of the conditions noted or implied upon discovery.

4. Roof System:


25 YEAR asphalt shingles self-sealed U.L. 790, UL 997, ASTM E108 Class 1 Fire, ASTM D3462, ASTM D3018 Type 1, ASTM D3161 Class F Wind, plywood sheathing over roof trusses or rafters, 36" wide moisture resistant granular surface self-sealing rubberized asphalt membrane in all valleys and along eaves.

5. Other Specified Materials on Drawings: Materials indicated on drawing showing specific Manufacturer are intended to be for size and shape references only.


USE GROUP: R5
TYPE 5B CONSTRUCTION
IRC 2015 NJ EDITION
NEC 2014




PORTRAIT LAYOUT DETAIL
N.T.S.



LANDSCAPE LAYOUT DETAIL
N.T.S.




RACK MOUNTING DETAIL
N.T.S.



QM-PV - COMP - 5/16" DETAIL
N.T.S.



GURTO RESIDENCE
533 NICHOLAS ROAD
BRICK, NJ 08724



Project No.	1703-105
Date	09/26/2017
Scale	1/8" = 1'-0"
Drawn	KC
Check	LSC
Sheet No.	A-4

Project

PROPOSED INSTALLATION OF SOLAR SYSTEM FOR:

Gurto Residence
533 Nicholas Road
Brick, NJ 08724

BLK- 966 LOT - 17

] **COPY**

SYSTEM INSTALLED BY
RPS INC.

RELIABLE POWER SERVICES, INC.
1085 HIGHWAY 9 SOUTH,
HOWELL, NJ 07731

NJ HOME IMPROVEMENT LICENSE
13VHO5266200

NJ ELECTRICAL LICENSE
NJ #11223B

FEDERAL TAX ID #
16-1732531

CONTACT:

CHRIS DiPASQUALE

OFFICE # 732-367-1166

FAX # 732-942-3979

EMAIL SOLAR@GETRPSNOW.COM

WWW.GETRPSNOW.COM


RELIABLE
Power&Solar
732.367.1166
Rt 9 North, Howell NJ 07731

RELIABLE POWER SERVICES, INC.
1085 RT 9 SOUTH
HOWELL, NJ 07731

ELECTRIC LIC#11223B
HOME IMPROVEMENT LIC#13VH05266200
INSURED & BONDED

Gurto Residence
533 Nicholas Road
Brick, NJ 08724

21.6 kW Grid Tie Solar System

The following is a description of the work to be done at listed address. This system is owned and maintained by the Customer.

The system installed at the above address is a Grid tie system. It uses Trina 290 watt panels and two Solar Edge 10,000 inverter(s). The system is installed on SnapNRak mount fastening systems and uses all stainless steel hardware. Roof flanges are used on all penetrations and no "L" feet will be installed directly on the roof shingle. All penetrations will be sealed using approved sealants and manufacturer's specs will be adhered to.

The electric company requires the installation of an approved net meter and disconnect from system.. The disconnect will be in sight of utility meter unless otherwise impossible and will be duly noted on drawings. If panel space allows and if it meets the requirements for sizing according to the NEC, system connection of a live bite tap will be installed before the main breaker and will be noted on paperwork. This will allow for not buss bar calculations. If both conditions do not apply then notes to drawings will be amended and listed.

All phases of work to be performed and maintained by RPS Inc. No sub contractors will be used. All licenses and insurances listed, along with bonding. Structural design by Architect listed and system design by designer listed. All parts of system to be approved or listed components. No homemade parts. IE. Shelf brackets, wood, PVC, rigid or EMT will be used to support system. All DC connections to be approved for outdoor use and no open splicing to be done. All panels and equipment are to be clearly marked for inspections, maintaining of system, and customer safety.

THIS DOCUMENT IS LIMITED TO THE INFORMATION CONTAINED HEREIN. IT IS NOT TO BE
DISSEMINATED OR USED FOR ANY OTHER PURPOSE. IT IS THE PROPERTY OF THE STATE OF NEW JERSEY
BACKGROUND AND MULTIPLE SECURITY FEATURES. PLEASE VERIFY AUTHENTICITY.

State Of New Jersey
New Jersey Office of the Attorney General
Division of Consumer Affairs

THIS IS TO CERTIFY THAT THE
Board of Exam. of Electrical Contractors


HAS LICENSED

RELIABLE POWER SERVICES INC
CHRISTOPHER J DI PASQUALE
1085 Route 9
Howell NJ 07731

FOR PRACTICE IN NEW JERSEY AS A(N): Electrical Business Permit

03/26/2015 TO 03/31/2018

VALID


Signature of Licensee/Registrant/Certificate Holder

34EB01122300

LICENSE/REGISTRATION/CERTIFICATION #


ACTING DIRECTOR

THIS DOCUMENT IS LIMITED TO THE INFORMATION CONTAINED HEREIN. IT IS NOT TO BE
DISSEMINATED OR USED FOR ANY OTHER PURPOSE. IT IS THE PROPERTY OF THE STATE OF NEW JERSEY
BACKGROUND AND MULTIPLE SECURITY FEATURES. PLEASE VERIFY AUTHENTICITY.

State Of New Jersey
New Jersey Office of the Attorney General
Division of Consumer Affairs

THIS IS TO CERTIFY THAT THE
Board of Exam. of Electrical Contractors

HAS LICENSED

CHRISTOPHER J. DI PASQUALE
1085 Route 9
HOWELL NJ 07731

FOR PRACTICE IN NEW JERSEY AS A(N): Electrical Contractor

02/11/2015 TO 03/31/2018

VALID


Signature of Licensee/Registrant/Certificate Holder

34E101122300

LICENSE/REGISTRATION/CERTIFICATION #


ACTING DIRECTOR

THIS DOCUMENT IS PRINTED ON WATERMARKED PAPER WITH A MULTI-COLORED
BACKGROUND AND MULTIPLE SECURITY FEATURES. PLEASE VERIFY AUTHENTICITY.

NOT AN
ELECTRICIAN'S
OR PLUMBER'S
LICENSE

State Of New Jersey
New Jersey Office of the Attorney General
Division of Consumer Affairs

THIS IS TO CERTIFY THAT THE
Division of Consumer Affairs

HAS REGISTERED

RELIABLE POWER SERVICES, INC
Chris DiPasquale
1085 Route 9
Howell NJ 07731

FOR PRACTICE IN NEW JERSEY AS A(N): Home Improvement Contractor

02/02/2017 TO 03/31/2018

VALID



Signature of Licensee/Registrant/Certificate Holder

13VH05266200

LICENSE/REGISTRATION/CERTIFICATION #




DIRECTOR

Gurto Residence
533 Nicholas Road
Brick, NJ 08724




Name: Gurto Residence
Address: 533 Nicholas Road,
Brick, N.J. 08724
Block: 966 L17
Azimuth: 16/196 Slope: 27



**RELIABLE
Power&Solar**

Making NJ Greener One Roof at a Time
Insured & Bonded NJ License #11223

26.1kw System



1. System Summary

1.1. System Data

1.1.1. Summary

Location Info

Project Site	14 Pine Rd, Howell, NJ 07731
Climate Data Source Location	Howell, NJ 07731 United States
Latitude	40° 10'N
Longitude	74° 13'W
Design Low Temperature	3°F (-16°C)
Design High Temperature	91°F (33°C)

Electrical Characteristics


Summary	
Total Number of Inverters	2
Inverter(s)	(2) Solar Edge SE10000A-US
Module	Trina Solar TSM-290DD05A(II) (290W)
Total Number of Modules	90
Area of array	147.3m ² (1,586ft ²)
Total STC power of array	26,100W
Total PTC power of array	23,868W
Total CEC power output	22,992W
First-Year PV Watts Prod. Estimate	35,992kWhr
Max AC output current	84A



SolarEdge Single Phase Inverters

For North America

SE3000A-US / SE3800A-US / SE5000A-US / SE6000A-US /
SE7600A-US / SE10000A-US / SE11400A-US



INVERTERS

The best choice for SolarEdge enabled systems

- Integrated arc fault protection (Type 1) for NEC 2011 690.11 compliance
- Superior efficiency (98%)
- Small, lightweight and easy to install on provided bracket
- Built-in module-level monitoring
- Internet connection through Ethernet or Wireless
- Outdoor and indoor installation
- Fixed voltage inverter, DC/AC conversion only
- Pre-assembled AC/DC Safety Switch for faster installation
- Optional – revenue grade data, ANSI C12.1

USA - GERMANY - ITALY - FRANCE - JAPAN - CHINA - AUSTRALIA - THE NETHERLANDS - ISRAEL

www.solaredge.us



Single Phase Inverters for North America

SE3000A-US / SE3800A-US / SE5000A-US / SE6000A-US /
SE7600A-US / SE10000A-US / SE11400A-US

	SE3000A-US	SE3800A-US	SE5000A-US	SE6000A-US	SE7600A-US	SE10000A-US	SE11400A-US	
OUTPUT								
Nominal AC Power Output	3000	3800	5000	6000	7600	9980 @ 208V 10000 @ 240V	11400	VA
Max. AC Power Output	3300	4150	5400 @ 208V 5450 @ 240V	6000	8350	10800 @ 208V 10950 @ 240V	12000	VA
AC Output Voltage Min.-Nom.-Max.* 183 - 208 - 229 Vac	-	-	✓	-	-	✓	-	
AC Output Voltage Min.-Nom.-Max.* 211 - 240 - 264 Vac	✓	✓	✓	✓	✓	✓	✓	
AC Frequency Min.-Nom.-Max.*	59.3 - 60 - 60.5 (with HI country setting 57 - 60 - 60.5)							Hz
Max. Continuous Output Current	12.5	16	24 @ 208V 21 @ 240V	25	32	48 @ 208V 42 @ 240V	47.5	A
GFDI	1							A
Utility Monitoring, Islanding Protection, Country Configurable Thresholds	Yes							
INPUT								
Recommended Max. DC Power** (STC)	3750	4750	6250	7500	9500	12400	14250	W
Transformer-less, Ungrounded	Yes							
Max. Input Voltage	500							Vdc
Nom. DC Input Voltage	325 @ 208V / 350 @ 240V							Vdc
Max. Input Current***	9.5	13	16.5 @ 208V 15.5 @ 240V	18	23	33 @ 208V 30.5 @ 240V	34.5	Adc
Max. Input Short Circuit Current	30							Adc
Reverse-Polarity Protection	Yes							
Ground-Fault Isolation Detection	600k Ω Sensitivity							
Maximum Inverter Efficiency	97.7	98.2	98.3	98.3	98	98	98	%
CEC Weighted Efficiency	97.5	98	97.5 @ 208V 98 @ 240V	97.5	97.5	97 @ 208V 97.5 @ 240V	97.5	%
Nighttime Power Consumption	< 2.5							W
ADDITIONAL FEATURES								
Supported Communication Interfaces	RS485, RS232, Ethernet, ZigBee (optional)							
Revenue Grade Data, ANSI C12.1	Optional							
STANDARD COMPLIANCE								
Safety	UL1741, UL1699B, UL1998, CSA 22.2							
Grid Connection Standards	IEEE1547							
Emissions	FCC part15 class B							
INSTALLATION SPECIFICATIONS								
AC output conduit size / AWG range	3/4" minimum / 24-6 AWG				3/4" minimum / 8-3 AWG			
DC input conduit size / # of strings / AWG range	3/4" minimum / 1-2 strings / 24-6 AWG				3/4" minimum / 1-2 strings / 14-6 AWG			
Dimensions with AC/DC Safety Switch (HxWxD)	30.5 x 12.5 x 7 / 775 x 315 x 172		30.5 x 12.5 x 7.5 / 775 x 315 x 191		30.5 x 12.5 x 10.5 / 775 x 315 x 260			in / mm
Weight with AC/DC Safety Switch	51.2 / 23.2		54.7 / 24.7		88.4 / 40.1			lb / kg
Cooling	Natural Convection				Fans (user replaceable)			
Noise	< 25				< 50			
Min.-Max. Operating Temperature Range	-13 to +140 / -25 to +60 (CAN version**** -40 to +60)							°F / °C
Protection Rating	NEMA 3R							

* For other regional settings please contact SolarEdge support.

** Limited to 125% for locations where the yearly average high temperature is above 77°F/25°C and to 135% for locations where it is below 77°F/25°C.

For detailed information, refer to http://www.solaredge.us/files/pdfs/inverter_dc_conversion_guide.pdf.

*** A higher current source may be used; the inverter will limit its input current to the values stated.


**** CAN P/Ns are eligible for the Ontario FIT and microFIT (microFIT exc. SE11400A-US-CAN).



RoHS

© SolarEdge Technologies, Inc. All rights reserved. SOLAREGE, the SolarEdge logo, OPTIMIZED BY SOLAREGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: 02/2014, V02. Subject to change without notice.

THE ALMAX^M PLUS⁺ MODULE



60 CELL MONOCRYSTALLINE MODULE

270-295W
POWER OUTPUT RANGE

18.0%
MAXIMUM EFFICIENCY


0~+5W
POSITIVE POWER TOLERANCE

As a leading global manufacturer of next generation photovoltaic products, we believe close cooperation with our partners is critical to success. With local presence around the globe, Trina is able to provide exceptional service to each customer in each market and supplement our innovative, reliable products with the backing of Trina as a strong, bankable partner. We are committed to building strategic, mutually beneficial collaboration with installers, developers, distributors and other partners as the backbone of our shared success in driving Smart Energy Together.

Trina Solar Limited
www.trinasolar.com

LINEAR PERFORMANCE WARRANTY

10 Year Product Warranty - 25 Year Linear Power Warranty



Trina solar
Smart Energy Together



Maximize limited space with top-end efficiency

- Up to 180 W/m² power density
- Low thermal coefficients for greater energy production at high operating temperatures



Highly reliable due to stringent quality control

- Over 30 in-house tests (UV, TC, HF, and many more)
- In-house testing goes well beyond certification requirements
- 100% EL double inspection



Certified to withstand challenging environmental conditions

- 2400 Pa wind load
- 5400 Pa snow load
- 35 mm hail stones at 97 km/h

Comprehensive products and system certificates



- IEC 61215/ IEC 61730/ UL 1703/ IEC 61701/ IEC 62716
- ISO 9001: Quality Management System
- ISO 14001: Environmental Management System
- ISO 14064: Greenhouse Gases Emissions Verification
- OHSAS 18001: Occupation Health and Safety Management System




THE ALLMAX[®] PLUS[™] MODULE

PRODUCTS	POWER RANGE
TSM-DD05A.08(II)	275-295W
TSM-DD05A.05(II)	270-290W


DIMENSIONS OF PV MODULE
unit:mm/inches



I-V CURVES OF PV MODULE(295W)



P-V CURVES OF PV MODULE(295W)



ELECTRICAL DATA (STC)

Peak Power Watts- P_{max} (Wp)*	270	275	280	285	290	295
Power Output Tolerance- P_{max} (W)	0~+5					
Maximum Power Voltage- V_{mp} (V)	31.2	31.4	31.7	31.8	32.2	32.5
Maximum Power Current- I_{mp} (A)	8.66	8.76	8.84	8.97	9.01	9.08
Open Circuit Voltage- V_{oc} (V)	38.4	38.7	39.0	39.3	39.5	39.7
Short Circuit Current- I_{sc} (A)	9.18	9.26	9.35	9.45	9.50	9.55
Module Efficiency η_m (%)	16.5	16.8	17.1	17.4	17.7	18.0

STC: Irradiance 1000 W/m², Cell Temperature 25°C, Air Mass AM1.5.
*Test Tolerance: ±3%.

ELECTRICAL DATA (NOCT)

Maximum Power- P_{max} (Wp)	201	205	209	212	216	220
Maximum Power Voltage- V_{mp} (V)	28.9	29.2	29.4	29.6	29.9	30.2
Maximum Power Current- I_{mp} (A)	6.96	7.02	7.10	7.17	7.23	7.28
Open Circuit Voltage- V_{oc} (V)	35.7	36.0	36.3	36.6	36.7	36.9
Short Circuit Current- I_{sc} (A)	7.41	7.48	7.55	7.63	7.67	7.71

NOCT: Irradiance of 800 W/m², Ambient Temperature 20°C, Wind Speed 1 m/s.

MECHANICAL DATA

Solar Cells	Monocrystalline 156 × 156 mm (6 inches)
Cell Orientation	60 cells (6 × 10)
Module Dimensions	1650 × 992 × 35 mm (65.0 × 39.1 × 1.38 inches)
Weight	18.6 kg (41.0 lb)
Glass	3.2 mm (0.13 inches), High Transmission, AR Coated Tempered Glass
Backsheet	White (DD05A.08(II)) - Black (DD05A.05(II))
Frame	Black (DD05A.08(II), DD05A.05(II))
J-Box	IP 67 or IP 68 rated
Cables	Photovoltaic Technology Cable 4.0mm ² (0.006 inches ²), 1000 mm (39.4 inches)
Connector	MC4 Compatible or Amphenol H4/UTX
Fire Type	Type 1 or Type 2

TEMPERATURE RATINGS

Nominal Operating Cell Temperature (NOCT)	44°C (± 2°C)
Temperature Coefficient of P_{max}	-0.39%/°C
Temperature Coefficient of V_{oc}	-0.29%/°C
Temperature Coefficient of I_{sc}	0.05%/°C

MAXIMUM RATINGS


Operational Temperature	-40~+85°C
Maximum System Voltage	1000V DC (IEC) 1000V DC (UL)
Max Series Fuse Rating	15A

WARRANTY

10 year Product Workmanship Warranty
25 year Linear Power Warranty
(Please refer to product warranty for details)

PACKAGING CONFIGURATION


Modules per box: 30 pieces
Modules per 40' container: 840 pieces



TSM_EN_2016_D

Meeting the Requirements of NEC 690.35 Ungrounded Photovoltaic Power Systems
Equipment Grounding in an Enphase System
Enphase Microinverters meet the requirements of NEC 690.35 Ungrounded Photovoltaic Power Systems. The article states:
690.35 Ungrounded Photovoltaic Power Systems. Photovoltaic Power Systems shall be permitted to operate with ungrounded photovoltaic source and output circuits where the system complies with 690.35(A) through (G).

- (A) Disconnects. In an Enphase system the AC and DC disconnects are the disconnecting means feeding the branch circuit. In an Enphase system, the AC circuit breaker or fused disconnect 690.9(A) Exception (b), provides overcurrent protection for the inverter output circuit. As per protection is provided by a ground fault sensing circuit.
- (B) Ground Fault Protection. In an Enphase system, ground fault protection is provided in the DC conductors must be PV Wire. The DC conductors in an Enphase Microinverter are PV Wire.
- (C) Ground Fault Protection. In an Enphase system, the AC circuit breaker or fused disconnect 690.9(A) Exception (b), provides overcurrent protection for the inverter output circuit. As per protection is provided by a ground fault sensing circuit.
- (D) The DC conductors must be PV Wire. The DC conductors in an Enphase Microinverter are PV Wire.
- (E) Allowed for use in ungrounded battery systems
- (F) Labelling. The Enphase Microinverters are labeled as specified.
- (G) Listing. The Enphase Microinverters are listed for use in an ungrounded photovoltaic system.



L Foot Mounts

Required Tools

- Hammer or Stud Finder
- Torque Wrench
- Roof Marking Crayon
- Socket Wrench



- Drill with 3/16" Pilot Drill Bit
- 1/2" Socket
- Roof Sealant

Materials Included - L Foot Flashing Kit

- (1) SnapTrack L Foot Base
- (1) SnapTrack L Foot Flashing
- (1) SnapTrack Composition L Foot
- (1) 5/16"-18 SS Flange Hex Nut
- (1) 5/16"-18 X 1-1/4" SS Flange Bolt
- (1) SnapTrack Channel Nut


Other Materials Required

- (1) 5/16" Lag Screw
- (1) 5/16" Washer




L Foot Mounts

INSTALLATION INSTRUCTIONS



1) Using roof attachment locations drawn during system layout, drill a pilot hole through the roofing material into the roof framing member.



4) Pry up shingles with a breaker bar and install flashing underneath shingle course above installed base. position flashing so base stud extends through hole in bottom edge of flashing.



2) Apply roofing sealant to the bottom of the base and directly onto the lag screw to ensure a water tight seal.



3) Attach the L Foot Base with a 5/16" lag screw, drive lag screw for minimum 2.5" embedment into the roof framing member.



6) If necessary, adjust the vertical face of the L Foot with the "live hinge" feature and adjust angle of L Foot so that the vertical face is perpendicular to the roof surface.



5) Place the L Foot on the base stud over the flashing and tighten the flange nut over the L Foot, torque to 10 - 15 ft-lbs.




Module Installation

Required Tools

- Torque Wrench
- Socket Wrench
- 1/2" Socket


Materials Included - Install Module Clamps

- Pre-Installed SnapNTrack Roof Rails
- Pre-Installed SnapNTrack Rails
- SnapNTrack Mid Clamp Assemblies
- SnapNTrack End Clamp Assemblies
- PV Modules




Mid Clamp Assembly

- (1) 5/16"-18 SS HCS Bolt
- (1) 5/16" SS Split Lock Washer
- (1) SnapNTrack Bonding Mid Clamp
- (1) 5/16"-18 SnapNTrack Channel Nut




Adjustable End Clamp Assembly

- (1) 5/16"-18 SS HCS Bolt
- (1) 5/16" SS Split Lock Washer
- (1) SnapNTrack Self Adjusting Top
- (1) SnapNTrack Self Adjusting Bottom



Universal End Clamp Assembly

- (1) 5/16"-18 X 1-1/2" SS HCS Bolt
- (1) 5/16" X 3/4" SS Flat Washer
- (1) SnapNTrack Universal Wedge
- (1) SnapNTrack Universal Wave



Module Installation

INSTALLATION INSTRUCTIONS


SnapNTrack Mid Clamp




- 1) Snap the channel nut into the top channel of the rail.



- 2) Slide the clamp flush to the module with the top lip of the mid clamp over the top edge of the module frame.



- 3) Place the next module flush to the other side of the mid clamp.




- 4) Tighten hardware, torque silver hardware to 10-15 ft-lbs and black hardware to 8-10 ft-lbs.


Module Installation

INSTALLATION INSTRUCTIONS

SnapNack Adjustable End Clamp




1) Snap the channel nut into the top channel of the rail.



2) Slide the clamp flush to the module with the top lip of the end clamp over the top edge of the module frame.



4) Install rubber end cap to finish.



3) Tighten hardware, torque silver hardware to 10-16 ft-lbs and black hardware to 8-10 ft-lbs.

MLPE Installation

Required Tools




- Torque Wrench
- Socket Wrench
- 1/2" Socket

Materials Included - MLPE Rail Attachment Kit

- (1) 5/16" X 1-1/2" X 0.125" SS Fender Washer
- (1) SnapNack Channel Nut
- (1) 5/16"-18 X 1-1/4" SS Flange Bolt


Other Materials Required

- (1) MLPE Unit




Materials Needed - Enphase Frame Mount

- (1) Enphase Microinverter
- (1) Enphase Frame Mount



Materials Needed - SolarEdge Frame Mount

- (1) SolarEdge Optimizer
- w/ Frame-Mounted Module Add-On




MLPE Installation

INSTALLATION INSTRUCTIONS - MLPE RAIL ATTACHMENT



1) Snap the SnapNTrack MLPE Rail Attachment Kit channel nut into the desired location on the rail where the microinverter will be installed.



2) Install the microinverter mounting plate onto the bolt of the MLPE Rail Attachment Kit, ensuring that the large fender washer is between the rail and mounting plate.



3) Tighten hardware, torque silver hardware to 10 ft-lbs.






3) Tighten hardware, torque silver hardware to 10 ft-lbs.


Grounding Specifications

System Bonding Methods


- 1) SnapNTrack Mid Clamp
- 2) SnapNTrack Adjustable End Clamp
- 3) SnapNTrack Standard Rail Splice



INSTALLATION INSTRUCTIONS - SOLAREGE FRAME MOUNT




1) Locate the SolarEdge optimizer with Frame-Mounted Module Add-On at a location on the module frame that will not interfere with the SnapNTrack rail.




2) Install the optimizer mounting plate onto the module frame and tighten the hardware to 7 ft-lbs.



3) Connect the module leads to the input connectors on the optimizer.




SnapNTrack Ground Lug Assembly



Grounding Specifications


Ground Path Details - SolarEdge
REV 1.0 11/15/2016



RAIL
RAIL SPACE
RAIL SPlice
EQUIPMENT GROUNDING CONDUCTOR
GROUND LUG
MODULE CLAMP
M = MID CLAMP
X = X-END CLAMP
U = UNIVERSAL END CLAMP
SOLAREDGE OPTIMIZER
TO EGC

Ground Path Details - Enphase

REV 1.0 11/15/2016



RAIL
RAIL SPACE
RAIL SPlice
EQUIPMENT GROUNDING CONDUCTOR
GROUND LUG
MODULE CLAMP
M = MID CLAMP
X = X-END CLAMP
U = UNIVERSAL END CLAMP
SOLAREDGE OPTIMIZER
TO EGC


Grounding Specifications

INSTALLATION INSTRUCTIONS
SnapTrack Ground Lug



1) Snap the SnapTrack Ground Lug into the rail channel on **one rail per module row**.

Warning: SnapTrack Ground Lugs are designed to be used in conjunction with the SnapTrack Ground Lug. Do not use any other type of ground lug or connector in the SnapTrack Ground Lug.




2) Place grounding conductor into slot underneath split ring washer.

Warning: Do not use any other type of ground lug or connector in the SnapTrack Ground Lug.



3) Tighten all hardware to a minimum of 16 ft-lbs.



Series 100 has been tested with the following UL Listed modules:

Hyundai Heavy Industries Co Ltd: HIS-M200RG Series - HIS-M205RG, HIS-M255RG, HIS-M260RG, HIS-5xxRG Series - HIS-5260RG, HIS-5265RG, HIS-5270RG, HIS-M210MG Series - HIS-M210MG, HIS-M215MG, HIS-M218MG, HIS-M220MG, HIS-M223MG, HIS-M225MG, HIS-M228MG, HIS-M230MG, HIS-M235MG, HIS-M238MG, HIS-M240MG, HIS-M243MG, HIS-M246MG, HIS-M249MG, HIS-M252MG, HIS-M255MG, HIS-M258MG, HIS-M260MG, HIS-M263MG, HIS-M265MG, HIS-M268MG, HIS-M270MG, HIS-5xxRG Series - HIS-520MG, HIS-5223MG, HIS-5225MG, HIS-5228MG, HIS-5230MG, HIS-5233MG, HIS-5235MG, HIS-5238MG, HIS-5240MG, HIS-5243MG, HIS-5245MG, HIS-5248MG, HIS-5250MG, HIS-5253MG, HIS-5255MG, HIS-5258MG, HIS-5260MG, HIS-5263MG, HIS-5265MG, HIS-5268MG, HIS-5270MG, HIS-5273MG, HIS-5275MG, all may be followed by the suffix BK or blank: HIS-5255RW Series - HIS-5255RW, HIS-5260RW, HIS-5265RW

[illegible]

Genesla Jiangsu Ltd: JCxxM-24/BB Series - JC200M-24/BB, JC205M-24/BB, JC210M-24/BB, JC215M-24/BB, JC220M-24/BB, JC225M-24/BB, JC230M-24/BB, JC235M-24/BB, JC240M-24/BB, JC245M-24/BB, JC250M-24/BB, JC255M-24/BB, JC260M-24/BB, JC265M-24/BB, JC270M-24/BB

lesun: TP660P-xxx - TP660P-240, TP660P-245, TP660P-250, TP660P-255, TP660P-250, TP660P-255

Series 100 has been tested with the following WL listed modules:

ingill Energy (China) Co Ltd: YLxxxP-29b Series - YL215P-29b, YL220P-29b, YL225P-29b, YL230P-29b, YL235P-29b, YL240P-29b, YL245P-29b, YL250P-29b, YL255P-29b, YL260P-29b; YLxxx-29b Series - YL220A-29b, YL225A-29b, YL230A-29b, YL235A-29b, YL240A-29b, YL245A-29b, YL250A-29b, YL255A-29b

Canadian Solar: C56P-xxx-P, C56P-265-P, C56P-xxx-P-SD, C56P-260-P-SD, C56P-265-P-SD; C56P-xxx-M, C56P-265-M, C56P-270-M, C56K-xxx-M, C56K-270-M, C56K-275-M, C56K-280-M; C56K-xxx-P, C56K-265-P, C56K-270-P, C56K-xxx-M, C56K-270-M, C56K-275-M, C56K-280-M; C56V-xxx-P, C56V-260-P-SD, C56V-265-P-SD, C56V-xxx-M, C56V-270-M, C56V-275-M, C56V-280-M; C56V-xxx-P, C56V-260-P, C56V-265-P, C56V-310-P, C56K-310-P, C56K-320-P

[illegible]

Solar: JAP6-60-xxx/3BB - JAP6-60-245/3BB, JAP6-60-250/3BB, JAP6-60-255/3BB, JAP6-60-260/3BB, JAP6-60-270/3BB, JAM6-60-xxx/SI - JAM6-60-245/3BB, JAM6-60-250/3BB, JAM6-60-255/SI, JAM6-60-260/SI, JAM6-60-265/SI, JAM6-60-270/SI

Solent: LGxxx51C-G4 - LG27551C-G4, LG28551C-G4, LGxxvN1K-G4 - LG300N1K-G4; LGxxxN1C-G4 - LG300N1C-G4, LG305N1C-G4, LG315N1C-G4, LG320N1C-G4

Grounding Specifications

Solar World: SWxxx-Mono (33mm frame, 5 busbar) - SW285-Mono, SW290-Mono, SW295-Mono, SW300-Mono; SWxxx-Mono Black (33mm frame) - SW280-Mono Black, SW285-Mono Black, SW290-Mono Black, SW295-Mono Black (33mm frame) - SW275-Mono Black, SW280-Mono Black, SW285-Mono Black, SW290-Mono Black, SWxxx-Poly (33mm black frame) - SW250-Mono Black, Mono (33mm frame) - SW 340 XL Mono, SW 345 XL Mono, SW 350 XL Mono, SW 355 XL Mono

Suniva Inc: OPTXXX-60-4-YYY; where XXX may be numbers 240 to 270 in increments of 5; where YYY may be 100; OPTXXX-60-4-YYY; where XXX may be numbers 235 to 265 in increments of 5; where YYY may be 180

REC Solar AS: RECxxxPE Series - REC219PE, REC220PE, REC225PE, REC230PE, REC235PE, REC240PE, REC245PE, REC250PE, REC255PE, REC260PE, REC265PE, REC270PE; may be followed by BLK; RECxxxTP Series - REC260TP, REC265TP, REC270TP, REC275TP, REC280TP; may be followed by BLK

Talesun: TP660P-xxx - TP660P-240, TP660P-250, TP660P-255, TP660P-260, TP660P-265, TP660P-xxx-B - TP660P-250-B, TP660P-255-B, TP660M-xxx - TP660M-240, TP660M-245, TP660M-250, TP660M-255, TP660M-260, TP660M-265, TP660M-xxx-B - TP660M-240-B, TP660M-245-B, TP660M-250-B, TP660M-255-B, TP660M-260-B

Trina Solar Ltd: TSM-xxxPA05 - TSM-215PA05, TSM-220PA05, TSM-225PA05, TSM-230PA05, TSM-235PA05, TSM-240PA05, TSM-245PA05, TSM-250PA05, TSM-255PA05, TSM-260PA05; TSM-xxxPA05.05 - TSM-215PA05.05, TSM-220PA05.05, TSM-225PA05.05, TSM-230PA05.05, TSM-235PA05.05, TSM-240PA05.05, TSM-245PA05.05, TSM-250PA05.05, TSM-255PA05.05, TSM-260PA05.05; TSM-xxxPA05.08 - TSM-215PA05.08, TSM-220PA05.08, TSM-225PA05.08, TSM-230PA05.08, TSM-235PA05.08, TSM-240PA05.08, TSM-245PA05.08, TSM-250PA05.08, TSM-255PA05.08, TSM-260PA05.08, TSM-265PA05.08; TSM-xxxPD05.002 - TSM-245PD05.002, TSM-250PD05.002, TSM-255PD05.002, TSM-260PD05.002, TSM-265PD05.002, TSM-270PD05.002, TSM-275PD05.002, TSM-280PD05.002, TSM-285PD05.002, TSM-290PD05.002, TSM-295PD05.002, TSM-300PD05.002, TSM-305PD05.002, TSM-310PD05.002, TSM-315PD05.002, TSM-320PD05.002, TSM-325PD05.002, TSM-330PD05.002, TSM-335PD05.002, TSM-340PD05.002, TSM-345PD05.002, TSM-350PD05.002, TSM-355PD05.002, TSM-360PD05.002, TSM-365PD05.002, TSM-370PD05.002, TSM-375PD05.002, TSM-380PD05.002, TSM-385PD05.002, TSM-390PD05.002, TSM-395PD05.002, TSM-400PD05.002, TSM-405PD05.002, TSM-410PD05.002, TSM-415PD05.002, TSM-420PD05.002, TSM-425PD05.002, TSM-430PD05.002, TSM-435PD05.002, TSM-440PD05.002, TSM-445PD05.002, TSM-450PD05.002, TSM-455PD05.002, TSM-460PD05.002, TSM-465PD05.002, TSM-470PD05.002, TSM-475PD05.002, TSM-480PD05.002, TSM-485PD05.002, TSM-490PD05.002, TSM-495PD05.002, TSM-500PD05.002, TSM-505PD05.002, TSM-510PD05.002, TSM-515PD05.002, TSM-520PD05.002, TSM-525PD05.002, TSM-530PD05.002, TSM-535PD05.002, TSM-540PD05.002, TSM-545PD05.002, TSM-550PD05.002, TSM-555PD05.002, TSM-560PD05.002, TSM-565PD05.002, TSM-570PD05.002, TSM-575PD05.002, TSM-580PD05.002, TSM-585PD05.002, TSM-590PD05.002, TSM-595PD05.002, TSM-600PD05.002, TSM-605PD05.002, TSM-610PD05.002, TSM-615PD05.002, TSM-620PD05.002, TSM-625PD05.002, TSM-630PD05.002, TSM-635PD05.002, TSM-640PD05.002, TSM-645PD05.002, TSM-650PD05.002, TSM-655PD05.002, TSM-660PD05.002, TSM-665PD05.002, TSM-670PD05.002, TSM-675PD05.002, TSM-680PD05.002, TSM-685PD05.002, TSM-690PD05.002, TSM-695PD05.002, TSM-700PD05.002, TSM-705PD05.002, TSM-710PD05.002, TSM-715PD05.002, TSM-720PD05.002, TSM-725PD05.002, TSM-730PD05.002, TSM-735PD05.002, TSM-740PD05.002, TSM-745PD05.002, TSM-750PD05.002, TSM-755PD05.002, TSM-760PD05.002, TSM-765PD05.002, TSM-770PD05.002, TSM-775PD05.002, TSM-780PD05.002, TSM-785PD05.002, TSM-790PD05.002, TSM-795PD05.002, TSM-800PD05.002, TSM-805PD05.002, TSM-810PD05.002, TSM-815PD05.002, TSM-820PD05.002, TSM-825PD05.002, TSM-830PD05.002, TSM-835PD05.002, TSM-840PD05.002, TSM-845PD05.002, TSM-850PD05.002, TSM-855PD05.002, TSM-860PD05.002, TSM-865PD05.002, TSM-870PD05.002, TSM-875PD05.002, TSM-880PD05.002, TSM-885PD05.002, TSM-890PD05.002, TSM-895PD05.002, TSM-900PD05.002, TSM-905PD05.002, TSM-910PD05.002, TSM-915PD05.002, TSM-920PD05.002, TSM-925PD05.002, TSM-930PD05.002, TSM-935PD05.002, TSM-940PD05.002, TSM-945PD05.002, TSM-950PD05.002, TSM-955PD05.002, TSM-960PD05.002, TSM-965PD05.002, TSM-970PD05.002, TSM-975PD05.002, TSM-980PD05.002, TSM-985PD05.002, TSM-990PD05.002, TSM-995PD05.002, TSM-1000PD05.002

Mechanical Loading Specifications

The UL Listing covers mechanical load ratings for the following span lengths, module orientations and positive, negative, and side load ratings:

The worst mechanical load rating is to be used based on the combination of module and system components.

Manufacturer	Module Size	Orientation	Direction	Max. Mechanical Load (psf)
Canadian Solar Modules	72 inches	Landscape	Positive	27.5
			Negative	25
	96 inches	Portrait	Positive	16.5
			Negative	16.5
Hanwha Q Cells	72 inches	Landscape	Positive	30
			Negative	30
	96 inches	Portrait	Positive	12.7
			Negative	16.6
Hyundai	72 inches	Landscape	Positive	30
			Negative	30
	96 inches	Portrait	Positive	15.5
			Negative	15.3
REC Solar PTE, LTD	72 inches	Landscape	Positive	30
			Negative	30
	96 inches	Portrait	Positive	15.6
			Negative	15.6

Mechanical Loading Specifications

Product Line	Size	Orientation	Condition	Test Method	Test Result
LG Electronics	72 inches	Landscape	Positive	20	20
			Negative	30	30
	96 inches	Portrait	Positive	16.6	16.6
			Negative	16.6	16.6
Toshiba	72 inches	Landscape	Positive	30	30
			Negative	30	30
	96 inches	Portrait	Positive	16.6	16.6
			Negative	16.6	16.6

Mechanical Loading Specifications

Mechanical Load Rating If system is using the following components:

Component	Size	Condition	Test Method	Test Result
Comp L Foot (92 deg) with L Foot Base	72 inches	Positive	27	27
		Negative	16.6	16.6
	96 inches	Positive	16.6	16.6
		Negative	14.5	14.5
All Purpose L Foot (90 deg) with L Foot Base	72 inches	Side Load	20.3	20.3
		Positive	11	11
	96 inches	Side Load	18.5	18.5
		Negative	16.6	16.6
Universal Tilt Hook	72 inches	Positive	27.4	27.4
		Negative	25	25
	96 inches	Positive	16.6	16.6
		Negative	16.6	16.6
Spot Tilt Hook	72 inches	Side Load	13	13
		Positive	16.6	16.6
	96 inches	Side Load	16.6	16.6
		Negative	16.6	16.6



ANSI Compliance Statement


GE I-210+c and I-210+ce with Itron Cellular Module

October 5, 2012

Itron supplies NJR with GE I-210+c and I-210+ce meters integrated with Itron GPRS, 1xRTT and 3G Cellular Modules. These integrated I-210+c and I-210+ce meters are utility-grade products designed, manufactured, tested, and certified to meet all applicable ANSI standards. The cellular-enabled I-210+c and I-210+ce feature all original meter hardware and soft keys enabling them to quantify the following metrics:

- Energy and Demand (I-210+c)
- Energy only (I-210+ce)

As the meter or the communication hardware or firmware changes, the integrated product must comply with the ANSI standards. The most recent ANSI certification was completed on June 11, 2012 [Ref: MET Report: EMC & TEL32232A-ANSI REV. 1]. ANSI certification can be verified by locating the meter's unique identifier printed on the label above the meter display as shown below:



Each ANSI-certified 1xRTT meter will feature one of the following labels:

ITRON
MODEL: SSI I210 1x
FCC ID: QHC-SSI2101X

SMARTSYNCH
MODEL: SSI I210 1x
FCC ID: QHC-SSI2101X



Each ANSI-certified GPRS meter will feature one of the following labels:

ITRON
MODEL: GEI210GPRSV1.0
FCC ID: QHC-I210GPRS

SMARTSYNCH
MODEL: GEI210GPRSV1.0
FCC ID: QHC-I210GPRS

Each ANSI-certified 3G meter will feature one of the following labels:

ITRON
MODEL: SSI I210 3G
FCC ID: QHC-I2103G

SMARTSYNCH
MODEL: SSI I210 3G
FCC ID: QHC-I2103G

For more information, please contact Itron Technical Support Services at 1-888-362-1780 or support@itron.com.

*Itron, Inc, Cellular Solutions
Jan Forslow, Product Management*



MET Laboratories, Inc.

914 W. Patapsco Ave. Baltimore, MD 21230
410-354-3300, Fax: 410-354-3313, 800-638-6057 www.metlabs.com

September 27, 2012

SmartSynch Inc.
4400 Old Canton Road
Suite 300
Jackson, MI 39211

Dear Mike Mathis,

It is our pleasure to inform SmartSynch Inc. that the GE Meters, have completed testing at MET Laboratories, Inc., under job #32232. The GE I-210+c Meter with the Smart Synch/Itron Communication Module meets or exceeds the requirements of the following ANSI 12.1 and ANSI 12.20 Tests.

ANSI C12.20 - 2010

- 5.5.4.1 - No Load - Test #1
- 5.5.4.2 - Starting Load - Test #2
- 5.5.4.3 - Load Performance - Test #3
- 5.5.4.4 - Variation of Power Factor - Test #4
- 5.5.4.5 - Variation of Voltage - Test #5
- 5.5.4.6 - Variation of Frequency - Test #6
- 5.5.4.8 - Internal Meter Losses - Test #8
- 5.5.4.9 - Temperature Rise - Test #9
- 5.5.4.11 - Effect of Internal Heating - Test #11
- 5.5.5.2 - Insulation - Test #15
- 5.5.5.3 - Voltage Interruptions - Test #16
- 5.5.5.4 - Effect of High Voltage Line Surges - Test #17
- 5.5.5.5 - Effect of External Magnetic Field - Test #18
- 5.5.5.1 - Performance Verification
- 5.5.5.6 - Variation of Ambient Temperature - Test #19
- 5.5.5.12 - Electrical Fast Transient/Burst - Test #25
- (ANSI C12.1-2008) - Effect of electrical oscillatory SWC - Test #25a
- 5.5.5.13 - Effect of Radio Frequency Interference - Test #26
- 5.5.5.14 - Radio Frequency Conducted and Radiated Emissions - Test #27
- 5.5.5.15 - Effect of Electrostatic Discharge - Test #28
- 5.5.5.17 - Effect of Operating Temperature - Test #30
- 5.5.5.18 - Effect of Relative Humidity - Test #31
- 5.5.5.19 - Mechanical Shock - Test #32
- 5.5.5.20 - Transportation Drop - Test #33
- 5.5.5.21 - Mechanical Vibration - Test #34
- 5.5.5.22 - Transportation Vibration - Test #35

For specific details regarding the extent of the testing and the configuration of the product tested, please consult the MET Laboratories' Detailed Test Report, EMC and TEL32232-ANSI Rev. 1. Please contact me with any questions or comments.

Sincerely,

Jim Reed
Manager, Meter Accuracy Laboratory

Manasi Bhandiwad
Manager, EMC Laboratory

PHOTOVOLTAIC SOLAR PANEL INSTALL CHECKLIST

REVISED 05/04/16

1. Construction Jacket signed & completed – Front and inside the jacket filled out completely.	Yes ☒	No ☐
2. Zoning Application completely filled out all sections.	Yes ☒	No ☐
3. Engineering Application completely filled out all sections.	Yes ☒	No ☐
4. Four true size surveys to scale showing proposed work	Yes ☒	No ☐
5. Building Subcode Tech completed	Yes ☒	No ☐
6. Electrical Subcode Tech completed	Yes ☒	No ☐
7. Copy of Home Improvement Contractor Registration	Yes ☒	No ☐
8. Two sets of detailed plans showing actual conditions of each installation signed and sealed by a licensed design professional.	Yes ☒	No ☐

USEFUL TIPS:

- Electric sub-code form must be signed and sealed by NJ licensed contractor.
- If you are cutting down trees, you will need a grading/clearing permit prior to the removal of the trees.