



CONSTRUCTION PERMIT

Date Issued 8/21/2023
Control # 308017
Permit # 23-2110

IDENTIFICATION Block: 1005 Lot: 92 Qualifier _____
Work Site Location: 92 LANTANA WAY Old Bridge Township, NJ Contractor SHAMILOV, ANTON
Address 92 LANTANA WAY SOUTH AMBOY NJ 08879
Owner in Fee SHAMILOV, ANTON
92 LANTANA WAY SOUTH AMBOY NJ 08879 Telephone: _____
Telephone: _____ Lic. No. or Bldrs. Reg. No. _____
Federal Employee No. _____

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☒ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☒ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

INTERIOR ALTERATION(S) INTERIOR RENO - REMOVE AND RELOCATE NON LOAD BEARING WALLS, GWB, REPLACE INSULATION, REPLACE EXISTING DOORS, REPLACE WINDOWS, RELOCATE EXISTING WINDOWS, INSTALL NEW PATIO DOORS, INSTALL NEW BATHROOM EXHAUST FANS, ADD BATHROOM

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$10,350

PAYMENTS (Office Use Only)

Building	\$600
Electrical	\$360
Plumbing	\$155
Fire Protection	\$100
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$20
CO Fee	
Other	\$0
Total	\$1,235
Check No.	0183
Cash	\$0
Credit	\$0
Collected By	Hazel Thompson

Construction Official _____ Date 8/21/2023

U.C.C. F170
equiv (rev 1/04)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

- ☒ Required inspections for all subcodes for one- and two-family dwellings are as follows:
1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
 2. Foundations and all walls up to grade level prior to back filling.
 3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
 4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

- ☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

- ☒ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

- ☒ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.