

BLOCK 1170.04 LOT 3

QUALIFICATION CODE

ADDRESS (SITE)

128 John Street
Brick, NJ 08724

PERMIT NO.

11-2206

CONSTRUCTION PERMIT APPLICATION

Applicant Completes: Sections I, II, III (optional), IV, VI, and VII

C11-002628

I. IDENTIFICATION

1. Proposed Work Site at: 128 John St. Brick, NJ 087242. Name of Applicant: Diane CollinsTel. [REDACTED] e-mail [REDACTED]Address Same as above3. Ownership in Fee: Public ☒ Private ☐ municipality ☒ zip code4. Principal Contractor: GeoGenix, LLC Tel. (732) 761-8841Address 8998 Route 18, Old Bridge, NJ 08857 e-mail permits@geogenix.comLicense No. OR, if new home, Builder Reg. No. I3VH02387400 Exp. Date 12-31-11

Home Improvement Contractor Registration No. or Exemption Reason (if applicable):

Federal Emp. ID No. 22-3801373 FAX: (732) 676-78005. Architect or Engineer Ascent Consulting Contact Janus malyAddress 10 High Mountain Rd Ringwood NJ 07470 e-mailTel. (973) 557-6080 FAX: (973) 835-59246. Responsible Person in Charge once Work has Begun Christy LorenzTel. (732) 761-8841 FAX: (732) 676-7800

V. FEE SUMMARY (for office use only)

		Update	Update
1. Building	\$ <u>200</u>		
2. Electrical	<u>75</u>		
3. Plumbing			
4. Fire Protection			
5. Elevator Devices			
6. Subtotal			
7. Less 20% for State Plan Review	\$		
8. Subtotal	\$		
9. State Permit Surcharge Fee	\$ <u>37</u>		
10. Subtotal	\$		
11. Cert. of Occupancy			
12. Other	<u>312</u>		
13. TOTAL	\$		

VI. BUILDING/SITE CHARACTERISTICS

	(office use only)
1. Number of Stories	
2. Height of Structure	ft.
3. Area — Largest Floor	sq. ft.
4. New Building Area	sq. ft.
5. Volume of New Structure	cu. ft.
6. Max. Live Load	
7. Max. Occupancy Load	
8. If Industrialized Building: State Approved	HUD
9. Total Land Area Disturbed	sq. ft.
10. Flood Hazard Zone	
11. Base Flood Elevation	ft.
12. Wetlands yes	no

IIa. PROPOSED WORK

- ☒ Minor Work ☐ New Building ☐ Addition ☐ Demolition
☐ Repair ☐ Alteration ☐ Renovation ☐ Reconstruction
☐ Asbestos Abat. -Subch. 8 ☐ Lead Hazard Abatement ☐ Radon Remediation ☐ Annual Permit

IIb. SUBCODES

(Check all that apply)

- ☒ Building
☒ Electrical
☐ Plumbing
☐ Fire Protection
☐ Elevator

FOR OFFICE USE ONLY (Optional)

Est. Cost	Plans Rec'd by	Date Rec'd	Rejection Date	Approval Date	Re-viewer	Resubmission Dates Approval	Rejection	Re-viewer
<u>\$7,966</u>	<u>REC'D JUL 15 2011</u>			<u>7/17/11</u>	<u>KA</u>			
<u>\$19,884</u>				<u>7/24/11</u>	<u>JT</u>			
<u>Eng</u>	<u>Exempt</u>			<u>7/18/11</u>	<u>EC</u>			

TOTAL COST \$21,850

VII. DESCRIPTION OF BUILDING USE

A. RESIDENTIAL (primary use)

1. State Specific Use: _____
 2. Use Group, Proposed: _____
 3. Change in Use Group, Indicate Present: _____
 4. No. of dwelling units: Total Units Income-restricted
 Gained, Sale _____
 Gained, Rental _____
 Lost, Sale _____
 Lost, Rental _____

B. NON-RESIDENTIAL (primary use)

1. State Specific Use: _____
 2. Use Group, Proposed: _____
 3. Change in Use Group, Indicate Present: _____

C. MIXED USE -List secondary use(s): _____

- D. Construct. Classification: Present _____
 Proposed _____

III. PLAN REVIEW (optional)

DO YOU WANT:

1. ☐ Partial Releases
 2. ☐ Prototype Processing

IV. DOES OR WILL YOUR BUILDING CONTAIN ANY OF THE FOLLOWING?

1. ☐ Elevators/Escalators/Lifts/
Dumbwaiters/Moving Walks
 2. ☐ High Pressure Boilers
 3. ☐ Pressure Vessels
 4. ☐ Refrigeration Systems
 5. ☐ Cross-Connections/Backflow Preventers
 6. ☐ Hazardous Uses/Places of Assembly
 7. ☐ Sprinklers
 8. ☐ Smoke Control Systems in Open Wells
 9. ☐ Underground Storage Tanks
 10. ☐ Swimming Pools, Spas and Hot Tubs
 11. ☐ LPGas Tanks

CERTIFICATION IN LIEU OF OATH

I. OWNER SECTION (to be completed if the applicant is the owner in fee)

I hereby certify that I am the owner in fee of the property listed on Page 1.

Mark the following applicable boxes:

- A. ☐ I further certify that a new home (private residence) will be constructed on this property for my own use and occupancy. This dwelling is to be occupied by myself and is not to be used for any purpose other than single family residential use. I attest that all construction, plumbing, or electrical work will be done, in whole or in part, by me or by subcontractors under my supervision, in accordance with all applicable laws; and, I further acknowledge that said new home is not covered under the New Home Warranty and Builders Registration Act (N.J.S.A. 46:3B-1 et seq.) and that such fact shall be disclosed to any person purchasing this property within ten years of the date of issuance of a certificate of occupancy.

I UNDERSTAND THAT IN MARKING BOX A, I ACKNOWLEDGE THAT I AM ASSUMING RESPONSIBILITY FOR THE WORK DONE ON SAID PROPERTY, THE CONDITION OF THE PROPERTY PRIOR TO, DURING, AND AFTER ANY WORK PERFORMED, AND FOR THE PERFORMANCE OF THE SUBCONTRACTORS I HIRE, EMPLOY, OR OTHERWISE CONTRACT OR WITH WHOM I MAKE AGREEMENTS TO PERFORM WORK. I AM VOLUNTARILY AND KNOWINGLY ASSUMING THIS RESPONSIBILITY.

- B. ☐ I further certify the following as required by the New Jersey Uniform Construction Code, N.J.A.C. 5:23-2.15(f)1.ix:

I personally prepared the plans submitted for: 1) the new home referred to in A.; or, 2) an addition, alteration, renovation, or repair to an existing single family residence owned and occupied by myself and located on the property listed on Page 1; or, 3) a new structure that will be physically separate from, but that will be deemed part of, an existing single family residence that is owned and occupied by myself and located on the property listed on Page 1.

- C. ☐ I further certify that I will perform or supervise the following work:

C.1. ☐ Building C.2. ☐ Fire Protection

I further certify that I will perform the following work:

C.3. ☐ Electrical C.4. ☐ Plumbing

- D. ☐ I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I understand that if any of the above statements are willfully false, I am subject to punishment.

Signature _____ Date _____

II. AGENT SECTION (to be completed if the applicant is not the owner in fee)

I hereby certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(d): the proposed work is authorized by the owner in fee; and I have been authorized by the owner in fee to make this application as his agent.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.


I understand that if any of the above statements are willfully false, I am subject to punishment.

☒ Check if contractor.

Agent Name Christy Lorenz For GeoGenix, LLC

Address 8998 Route 18, Old Bridge, NJ 08857

Telephone (732) 761-8841

Signature 

- III. ☐ LEAD HAZARD ABATEMENT: Include Homeowner or Building Owner Affidavit as per N.J.A.C. 5:17.

OFFICE DATE RECEIVED: 7-15-11 SC22

VIII. PRIOR APPROVALS CHECKLIST (office use only)	LOCAL APPROVAL		COUNTY APPROVAL		REGIONAL APPROVAL		STATE APPROVAL		COMMENTS
	Prelimin. Initial	Final Date	Prelimin. Initial	Final Date	Prelimin. Initial	Final Date	Prelimin. Initial	Final Date	
☒ Zoning Officer	SC	7/15/11	X		X		X		24-11-00965
☐ Planning Board			X		X		X		
☐ Zoning Board			X		X		X		
☐ Sewer Authority			X		X		X		
☐ Water Authority			X		X		X		
☐ Police Department			X		X		X		
☐ Health Department			X		X		X		
☐ Soil Conservation			X		X		X		
☐ N.J. Department of Community Affairs			X		X		X		
☐ N.J. Department of Transportation			X		X		X		
☐ N.J. Department of Environmental Protection			X		X		X		
☐ Utility Dig No.			X		X		X		
☐			X		X		X		
☐			X		X		X		

IX. SUBCODES AND SPECIAL REGULATIONS APPLICABLE (office use only—optional)

Name of Code & Edition	Name of Code & Edition	Other
Building _____	Energy _____	
Electrical _____	Barrier Free _____	
Plumbing _____	Flood Hazard _____	
Fire Protection _____	As Built Elevation Cert _____	
Mechanical _____	Other _____	

X. CERTIFICATES ISSUED (office use only)

	DATE ISSUED	DATE EXPIRED	DATE REISSUED	DATE EXPIRED
☐ Temporary Certificate of Occupancy	No. _____	_____	_____	_____
☐ Temporary Certificate of Compliance	No. _____	_____	_____	_____
☐ Continued Certificate of Occupancy	No. _____	_____	_____	_____
☐ Certificate of Compliance	No. _____	_____	_____	_____
☐ Certificate of Occupancy	No. _____	_____	_____	_____
☐ Certificate of Approval	No. _____	_____	_____	_____
☐ Lead Abatement Clearance Certificate	No. _____	_____	_____	_____



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723

Date Issued 9/21/2011
Control Number C-11-002628
Permit Number 11-2206
Permit Issue Date 7/25/2011
Certificate Number 11-2206

Certificate

Construction Code Division
(Certificate of Approval)

Identification

Work Site Location: 128 JOHN ST. Brick Township, NJ Block: 1170.04 Lot: 3 Qual: _____
Owner in Fee: COLLIS, BRIAN M & DIANE E
Owner Address: 128 JOHN ST BRICK NJ 08724
Telephone: _____
Contractor GEO GENIX, LLC
Address 79 EAST RIVER ROAD RUMSON NJ 07760
Telephone: (732) 895-9550 Fax: (801) 382-0751
License Number or Builders Registration Number: 13VH02387400 033044 Federal Emp. Number: 22-3801373

Home Warranty Number: _____

Type of Warranty Plan: ☐ State ☐ Private

Use Group: R-5 Construction Classification: _____

Maximum Live Load: 0 Maximum Occupancy Load: 0

Description of Work/Use: SOLAR PANELS

Certificate Comments:

☐ **Certificate of Occupancy**

This serves notice that said building or structure has been constructed in accordance with the New Jersey Uniform Construction Code and is approved for occupancy.

☒ **Certificate of Approval**

This serves notice that the work completed has been constructed or installed in accordance with the New Jersey Uniform Construction Code and is approved. If the permit was issued for minor work, this certificate was based upon what was visible at the time of inspection.

☐ **Certificate of Continued Occupancy**

This serves notice that based on a general inspection of the visible parts of the building there are no imminent hazards and the building is approved for continued occupancy.

☐ **Temporary Certificate of Compliance**

The following conditions must be met no later than or the owner will be subject to fine or order to vacate:

This certificate has an expiration date of:

Conditions to be met:

☐ **Certificate of Clearance - Lead Abatement 5:17**

This serves notice that based on written certification, lead abatement was performed as per NJAC5:17 to the following extent.

- ☐ Total removal of lead-based paint hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Clearance - Asbestos Abatement**

This serves notice that based on written certification, asbestos abatement was performed to the following extent.

- ☐ Total removal of asbestos hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Compliance**

This serves notice that said potentially hazardous equipment has been installed and/or maintained in accordance with the New Jersey Uniform Construction Code and is approved for use until

☐ **Temporary Certificate of Occupancy**

The following conditions must be met no later than: or the owner will be subject to fine or order to vacate: This certificate has an expiration date of:

Conditions to be met:

Daniel Newman Jr

Construction Official

Fee: \$0.00

Check Number: _____

Collected By: _____



CONSTRUCTION PERMIT

Date Issued _____
Control # C-11-002628
Permit # _____

IDENTIFICATION Block: 1170.04 Lot: 3 Qualifier _____
Work Site Location: 128 JOHN ST. Brick Township, NJ Contractor GEO GENIX, LLC
Address 79 EAST RIVER ROAD RUMSON NJ 07760
Owner in Fee COLLIS, BRIAN M & DIANE E
128 JOHN ST BRICK NJ 08724 Telephone: (732) 895-9550
Telephone: _____ Lic. No. or Bldrs. Reg. No. 033044
Federal Employee No. 22-3801373

Is hereby granted permission to perform the following work:

- | | | |
|--|--|--|
| ☒ BUILDING | ☐ PLUMBING | ☐ LEAD HAZARD ABATEMENT |
| ☒ ELECTRICAL | ☐ FIRE PROTECTION | ☐ DEMOLITION |
| ☐ ELEVATOR DEVICES | ☐ ASBESTOS ABATEMENT
(Subchapter 8 only) | ☐ OTHER |

DESCRIPTION OF WORK:

SOLAR PANELS

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$21,850

Construction Official _____

Date _____

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$75
Electrical	\$200
Plumbing	\$0
Fire Protection	\$0
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$37
CO Fee	
Other	\$0
Total	\$312
Check No. <u>1170.04</u>	
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☒ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.



BUILDING SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170.04 Lot 3 Qualification Code _____

Work Site Location 188 50th St.

Back of 08724

Owner in Fee: Dave Collins

Tel. _____ e-mail _____

Address Same as above Municipality _____ Zip code _____

Contractor: Geogenix, LLC Tel. (732) 761-8841

Address 8998 Route 18, Old Bridge, NJ 08857 e-mail permits@geogenix.com

Contractor License No. or Builder Registration No. 13VH02387400 Exp. Date 12-31-11

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____ FAX: (732) 676-7800

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Type	Failure	Dates (Month/Day)	Initial
						Failure	Approval
☐ No Plans Required							
☐ All							
☐ Footing							
☐ Foundation							
☐ Frame							
☒ Other							
Joint Plan Review Required							
☐ Elec.							
☐ Plumb.							
☐ Fire							
☐ Elevator							
Insulation							
Finishes - Base Layer							
Finishes - Final							
Energy							
Mechanical							
TCO							
Other							
Final							
Barrier-Free							

B. BUILDING CHARACTERISTICS

Use Group	Present	Proposed	Est. Cost of Bldg. Work:
Constr. Class	Present	Proposed	1. New Bldg. \$ <u>1,966-</u>
No. of Stories			2. Rehabilitation \$ <u>-</u>
Height of Structure			3. Total (1+2) \$ <u>1,966-</u>
Area — Largest Floor			
Sq. Ft.			
New Bldg. Area/All Floors			
Sq. Ft.			
Volume of New Structure			
Cu. Ft.			
Total Land Area Disturbed			
Sq. Ft.			

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

Signature [Signature]

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Install 20 solar electric panels on roof.

Date Received 7/25/11

Control # 11-22206

Date Issued 11-22206

TYPE OF WORK:	Height (exceeds 6')	Sq. Ft.	FEE (Office Use Only)
☐ New Building			
☐ Addition			
☐ Rehabilitation			
☐ Roofing			
☐ Siding			
☐ Fence			
☐ Sign			
☐ Pool			
☐ Retaining Wall			
☐ Asbestos Abatement Subchapter 8			
☐ Lead Haz. Abatement NJAC 5:17			
☐ Radon Remediation			
☐ Other			
☐ Demolition			

Administrative Surcharge \$	
Minimum Fee \$	
State Permit Surcharge Fee \$	
TOTAL FEE \$	

USE
NEW JERSEY
UNIFORM CONSTRUCTION
CODE
**ELECTRICAL
SUBCODE
TECHNICAL SECTION**



Date Received 7/25/11
Date Issued
Control # 11-2206
Permit #

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170.04 Lot 3 Qualification Code _____
Work Site Location Back, 1188 John St.
Owner in Fee Diane Collins
Address Same as above
Tel _____
Contractor J. A. WIG CONSTRUCTION & ELECTRIC, LLC
Address 124 BOBBIS TERRACE
NEW EGYPT, NEW JERSEY 08533
Tel (609) 758-1844 FAX (609) 758-4629
Contractor License No. 14815
Federal Emp. No. 16-1644430
B. ELECTRICAL CHARACTERISTICS 4.6 kw system
Use Group Present _____ Proposed _____
[] Pole/Pad # _____ [] Temporary [] Other
Building Occupied as Residential Utility Co. SCPL
Est. Cost of Elec. Work \$ 19,884-

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Dates (Month/Day)
[] No Plans Required			Type:	Failure Failure Approval Initial
Joint Plan Review Required:			Rough	
[] Building [] Plumbing			Barrier-Free	
[] Fire [] Elevator			Trench	
[] Elec. Plans Approved			Temp. Serv.	
Date: <u>7/24/11</u>			Constr. Serv.	
Approved by: <u>[Signature]</u>			TCO	
			Other	
			Service	
			Final	
			Barrier-Free	
SUBCODE APPROVAL				
[] CO [] CCO [] CA			Temp. Cut-in-Card Date Issued	
Date: <u>7/20/11</u>			Final Cut-in-Card Date Issued	
Approved by: <u>[Signature]</u>			Annual Pool Inspection	
			Date of Grounding and Bonding Certification	

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

Licensed Elec. Contractor [] Certified Landscape Irrigation Contr [] Exempt Applicant

TECHNICAL SITE DATA

QTY. SIZE ITEMS

Lighting Fixtures
Receptacles
Switches
Detectors
Light Poles
Motors—Fract. HP
Emergency & Exit Lights
Communications Points Array
Alarm Devices/E.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UV Lights
Storable Pool/Spa/Hot Tub
KW Elec. Range/Receptacle
KW Oven/Surface Unit
KW Elec. Water Heater
KW Elec. Dryer/Receptacle
KW Dishwasher
HP Garbage Disposal
KW Central A/C Unit
HP/KW Space Heater/Air Handler
KW Baseboard Heat
HP Motors 1/4 HP
KW Transformer/Generator
AMP Service
AMP Subpanels
AMP Motor Control Center
KW Elec. Sign/Outline Light

FEE (Office Use Only)

Administrative Surcharge \$
Minimum Fee \$
State Permit Surcharge Fee \$
TOTAL FEE \$

UCCF-120 (REV. 7/03)
Professional Printing
(856) 468-7933

1. White-Inspector copy
2. Canary- Applicant copy
3. Pink- Office Copy
4. White Tag- Office copy



Brick Township
401 Chambers Bridge Rd.

Brick, NJ 08723
(732) 262-1027

Date Issued: 7/25/11
Application Number: ZA-11-00763
Application Date: 07/15/2011
Project Number: _____
Permit Number: ZP-11-00657
Fee: \$50

Zoning Permit

Worksite **128 JOHN ST**
Location: **Laurel Acres**
BRICK, NJ 08724

Block: 1170.04

Lot: 3

Qualifier: _____

Zone: R-7.5

Owner: **COLLIS, BRIAN M & DIANE E**
Address: **128 JOHN ST**
BRICK, NJ 08724

Applicant: **Christy Lorenz; GeoGenix, LLC**
Address: **8998 Route 18**
Old Bridge, NJ 08857

Application Approved Date: 07/15/2011

This Certifies that an application for the issuance of a Zoning Permit has been examined.

Use is: Single-Family Residential

Nonconforming Use is: _____


Work Description:

Solar Panels - 20 photovoltaic 230W panels, 4.6KW, mounted on the roof of the house.

Upon review it was determined that:

- ☒ Use is permitted by Ordinance
- ☐ Use is permitted by Variance approved on: _____
- ☐ Valid Nonconforming Use is established by
 - ☐ Zoning Board of Adjustment
 - ☐ Zoning Officer


Sean Kinney, Zoning Officer


Michael P. Fowler, Township Planner

07/15/2011

Date

7/15/11 07/15/11 12:42PM 001558#7862
Date
XXD2 SERV.002

#2206	
ZPA	\$50.00
XXXTOTAL	\$50.00
CHECK	\$50.00
CHANGE	\$0.00

RECEIVING CLERK 7-15-11
DATE REC'D 7-15-11

ZONING PERMIT APPLICATION

PERMIT # 20-11-00657
DATE ISSUED 7/25/11

BLOCK: 1170.04 LOT: 3 QUALIFIER: — SITE ADDRESS: 128 JOHN STREET

IDENTIFICATION:

1. NAME OF OWNER IN FEE: Diane Collis
COMPLETE ADDRESS: 128 John Street
Brick, NJ 08724
PHONE # EMAIL:

2. NAME OF APPLICANT: Christy Lorenz for Geogenix, LLC.
APPLICANT ADDRESS: 8998 Route 18
Old Bridge, NJ 08857
PHONE # 732-761-8841 EMAIL: christy.lorenz@geogenix.com

3. RESPONSIBLE PERSON FOR WORK: Christy Lorenz
PHONE # 732-761-8841 FAX # 732-676-7800

4. SIGNATURE OF APPLICANT: Christy Lorenz, LLC.

FOR OFFICE USE ONLY

FEE SUMMARY:

APPLICATION FEE: \$ 50.00
OTHER: \$
TOTAL: \$

REQUIRED BY APPLICANT

RESIDENTIAL: X
COMMERCIAL:
EXISTING USE: SINGLE FAMILY
PROPOSED USE: SINGLE FAMILY

BOARD APPROVAL: PB ZB
RESOLUTION#:
APPROVAL DATE:

PROJECT DESCRIPTION: (PLEASE CHECK APPLICABLE WORK & DESCRIBE)

*NEW BUILDING: *ADDITION *ALTERATION *PORCH *DECK

POOL: ABOVE GROUND IN GROUND FENCE: HEIGHT TYPE

HEIGHT: (*APPLICABLE)

OTHER Solar panel installation **

DESCRIPTION: Installation of photovoltaic (solar electric) system on roof of house. No panels to be higher than existing roof ridge.

ZONING REVIEW: 7-15-11 DATE DENIED: DATE APPROVED: 7-15-11 INTLS: SC21 (SEE BACK PAGE)
DATE REVIEWED: 7-15-11

RECEIVING CLERK _____
DATE REC'D _____

ZONING PERMIT APPLICATION

PERMIT # _____
DATE ISSUED _____

BLOCK: _____ LOT: _____ QUALIFIER: _____ SITE ADDRESS: _____

IDENTIFICATION:

1. NAME OF OWNER IN FEE: _____

COMPLETE ADDRESS: _____

PHONE # _____ EMAIL: _____

2. NAME OF APPLICANT: _____

APPLICANT ADDRESS: _____

PHONE # _____ EMAIL: _____

3. RESPONSIBLE PERSON FOR WORK: _____

PHONE # _____ FAX # _____

4. SIGNATURE OF APPLICANT: _____

FOR OFFICE USE ONLY

FEE SUMMARY:

APPLICATION FEE: \$ _____

OTHER: \$ _____

TOTAL: \$ _____

REQUIRED BY APPLICANT

RESIDENTIAL: _____

COMMERCIAL: _____

EXISTING USE: _____

PROPOSED USE: _____

BOARD APPROVAL: _____ PB _____ ZB

RESOLUTION #: _____

APPROVAL DATE: _____

PROJECT DESCRIPTION: (PLEASE CHECK APPLICABLE WORK & DESCRIBE)

*NEW BUILDING: _____ *ADDITION _____ *ALTERATION _____ *PORCH _____ *DECK _____

POOL: ABOVE GROUND _____ IN GROUND _____ FENCE: HEIGHT _____ TYPE _____

HEIGHT: _____ (*APPLICABLE)

OTHER: _____

DESCRIPTION: _____

ZONING REVIEW: _____

DATE REVIEWED: _____ DATE DENIED: _____ DATE APPROVED: _____ INTLS: _____

(SEE BACK PAGE)

TOWNSHIP OF BRICK ZONING CHECKLIST

1) Two (2) copies of plot plan containing:

- All existing and proposed structures
- All dimensions of the lot and structures
- All setbacks from the structures to the property lines
- All adjacent streets and waterways
- If applicable, include a copy of the Zoning Board of Adjustment Resolution, the date that the map was signed, and/or the date that the subdivision map was filed with the Ocean County Clerk, along with the file map and number.

2) Two copies of the plans with dimensions and heights noted:

- Floor plans and elevations
- Signed site plans
- Property map
- Survey map

Choose which is applicable for submission

3) Plot plans and building plans must match for complete review

NOTE: NO PARTIAL, TAPED, FAXED, REDUCED OR ENLARGED COPIES CAN BE ACCEPTED

LAND USE

245 Attachment 5

Township of Brick

SCHEDULE OF AREA, YARD AND BUILDING REQUIREMENTS

Township of Brick
Ocean County, New Jersey

[Amended 6-26-1979 by Ord. No. 354-2B-79; 4-22-1980 by Ord. No. 354-2H-80; 10-14-1980 by Ord. No. 354-2N-80; 9-23-1980 by Ord. No. 354-1B-80; 8-25-83 by Ord. No. 354-2SS-83; 11-5-1984 by Ord. No. 354-2AAA-84; 11-5-1984 by Ord. No. 354-2CCC-84; 6-24-1986 by Ord. No. 354-2VWW-86; 9-13-1988 by Ord. No. 354-2TTT-88; 9-27-1988 by Ord. No. 354-2XXX-88; 9-12-2000 by Ord. No. 354-2EE-00; 5-9-2000 by Ord. No. 354-2Z-00; 3-26-2002 by Ord. No. 354-2C-02; 11-26-2002 by Ord. No. 354-2L-02; 3-25-2003 by Ord. No. 354-2D-03; 6-13-2006 by Ord. No. 19-06]

Zone	Minimum Lot Size			Minimum Required Yard Depth			Maximum Lot Coverage by Building	Maximum Building Height			Minimum Floor/Building Area (square feet)	Maximum Allowable Impervious Coverage
	Area (square feet)	Width (feet)	Depth (feet)	Area (square feet)	Width (feet)	Depth (feet)		Front Yard (feet)	Side Yard (feet)	Rear Yard (feet)		
R-R	40,000	150	150	40,000	150	150	25%	50	25	25	-	-
RR-2							See § 245-90.					
RR-3							See § 245-103.					
R-20	20,000	100	125	25,000	100	125	40	15	10	10	25%	-
R-15	15,000	100	115	17,250	100	115	35	12	10	10	25%	-
R-10	10,000	90	100	10,500	100	100	30	6	5	5	30%	-
R-7.5	7,500	75	90	9,000	75	90	25	6	5	5	30%	-
R-5	5,000	50	75	6,000	50	75	20	5	5	5	35%	-
O-P	15,000	100	150	15,000	100	150	50	10	20	50	35%	1,500
B-1	10,000	100	90	12,500	100	125	30	10	10	20	30%	2,000
B-2	20,000	125	125	20,000	125	125	50	10	50	50	25%	2,000
B-3	2 acres	200	200	2 acres	200	200	75	30	20	50	25%	30,000
B-4	5 acres	300	300	-	-	-	100 (150')	-	20	50	25%	5,000
M-1	5 acres	300	300	5 acres	300	300	150	75	150	150	20%	-
R-M	25 acres	350	200	-	-	-	50	50	30	30	20%	-
O-P-T	40,000	150	150	40,000	150	150	50	20	20	50	25%	2,000
H-S							See § 245-261.					70%

- NOTES:
- 1 If adjacent to residential zone or use.
 - 2 The maximum lot coverage shall refer only to that percentage of an affected lot which is suitable for building.
 - 3 For rear yard setback requirements for accessory buildings on waterfront property, see § 245-10D.

BR JUL 15 2011

JUL 15 2011

12/25

DATE REVIEWED: 7-15-11 DATE DENIED: — DATE APPROVED: 7-15-11 INTLS: See

[illegible]

GeoGenix, LLC

7713


Brick Township

Date	Type	Reference	Original Amt.	Balance Due	7/13/2011 Discount	Payment
7/12/2011	Bill	Diane Collis Zoning	50.00	50.00		50.00
				Check Amount		50.00

GeoGenix TD Bank C Diane Collis Zoning Permit Fee (lease)

50.00

FAIRWOOD LANE 50' ROW



JOHN STREET

REFERENCES:

DEED BOOK 5133, PAGE 162;


A MAP ENTITLED "LAUREL ACRES" FILED JULY 2, 1957 AS:

MAP NO. D-67;

TOWNSHIP OF BRICK TAX MAPS;

Proposed solar panels ~ Collis residence
138 John Street, Brick, NJ 08324

A WRITTEN WAIVER & DIRECTION NOT TO
SET CORNER MARKERS HAS BEEN
OBTAINED FROM THE ULTIMATE USER.
*



Brunswick Surveying Incorporated
Licensed Land Surveyors
61 Stelton Road Piscataway, New Jersey
(732) 752-0100 08854

PLAN OF SURVEY

Brian M. Collis and Diane F. Collis
Township of Brick
Ocean County, New Jersey
Block 1170.04 Lot 3

CERTIFICATE # 24GA27940000

Drawn by FH Job No. 3538-04 Date 11-2-04
Checked by RH Drawing No. Scale 1"=20'

I hereby certify this survey to:
Brian M. Collis & Diane F. Collis
husband and wife; Network Title
Services, Inc.; First American
Title Insurance Company; Thomas
J. Lanza, Esq.; Countrywide Home
Loans Inc. and/or its assigns as
their interest may appear

ROBERT M. HORVATH N.J.L.S. 27476
JAY A. STUHL, JR. N.J.L.S. 36762

R.S. KNAPP CO.

NT 34336

732 477-6670

APPROVED FOR ZONING ONLY
SEAN KINNEV, ZONING OFFICER

Kevin McCord

Jul 11 11 01:22p

JUL 15 2011

SOLAR PANELS

July 14, 2011

**Zoning Officer
Brick Twp. Building Dept.
401 Chambers Bridge Road
Brick Twp, NJ 08723**

Dear Zoning Officer,

Enclosed please find a completed Zoning application package for the installation of a photovoltaic (solar-electric) system, roof mounted, at the residence indicated below:

**Diane Collis
128 John Street
Brick, NJ 08724
Block 1170.04, Lot 3**

We are submitting the following material to the Zoning Dept.:

1. Completed Zoning Application form
2. Zoning Permit Fee \$50.00
3. Two (2) copies of diagram showing the placement of the solar panels (roof mounted).
4. Two (2) copies of detailed specification sheets for the photovoltaic panels.
5. Two (2) copies of Survey with drawings indicating the proposed installation

Please call the numbers listed below or send an email if you have any questions.

Thank you for your time and attention.

Sincerely,

Christy Lorenz

Christy Lorenz, Administrative Assistant, 732-761-8841, Christy.lorenz@geogenix.com

Enc.



GeoGenix, LLC
Leaders in Energy-Saving
Design and Construction

GeoGenix, LLC
79 East River Road
Rumson, NJ 07760
(T) 732.895.9550
(F) 801.382.0751

STRUCTURAL ENGINEER:

Ascent Consulting
James A. Marx, P.E.
10 High Mountain Road
Ringwood, NJ 07456
(T) 973.557.6080

CUSTOMER:

Diane Collis Residence
128 John Street
Brick, NJ, 08724

UTILITY COMPANY:

JCP&

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM

Solar Panel
Array Layout

PROJECT #:


DATE: 7/6/11

DRAWN BY: GLK

REV #:

SCALE: As Noted

PV-1



SOLAR PANEL ARRAY

Roof Pitch = $25^{\circ} \pm$

(20) TrinaSolar TSM PA05 230w panels (4.6 kW total)

INVERTER

(1) SB-4000us W/ (2) Strings of (10) Panels

RACKING:

DPW Power Rail System

APPROVED FOR ZONING ONLY
SEAN KINNEVY, ZONING OFFICER

SOLAR ARRAY


158°

JUL 15 2011

SEAN KINNEVY

NOTES:

1. See specifications for additional information.
2. See electrical One-line drawing (PV-2) for wiring connections.
3. North arrow and Array orientation based on "True" direction (magnetic compass reading minus Magnetic Declination of 11 degrees equals true Array orientation (Azimuth) of 158 degrees.)



Solar (Photovoltaic) Panel

Direction of Roof Slope

LEGEND:



Leaders in Energy-Saving
Design and Construction

GeoGenix, LLC

GeoGenix, LLC
79 East River Road
Rumson, NJ 07760
(T) 732.895.9550
(F) 801.382.0751

STRUCTURAL ENGINEER:

Ascent Consulting
James A. Marx, P.E.
10 High Mountain Road
Ringwood, NJ 07456
(T) 973.557.6080

CUSTOMER:

Diane Collis Residence
128 John Street
Brick, NJ, 08724

UTILITY COMPANY:

JCP&

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM
Solar Panel
Array Layout

PROJECT #:


DATE: 7/6/11

DRAWN BY: GLK

REV #:

SCALE: As Noted

PV-1



SOLAR PANEL ARRAY

Roof Pitch = $25^{\circ} \pm$

(20) TrinaSolar TSM PA05 230w panels (4.6 kW total)

INVERTER

(1) SB-4000us W/ (2) Strings of (10) Panels

RACKING:

DPW Power Rail System

APPROVED FOR ZONING ONLY
SEAN KINNEVY, ZONING OFFICER

SOLAR ARRAY


158°

JUL 15 2011

SK

NOTES:

- See specifications for additional information.
- See electrical One-line drawing (PV-2) for wiring connections.
- North arrow and Array orientation based on "True" direction (magnetic compass reading minus Magnetic Declination of 11 degrees equals true Array orientation (Azimuth) of 158 degrees.)



Solar (Photovoltaic) Panel

Direction of Roof Slope


LEGEND:

Trinasolar


TRINA TSM-PA05, 220W to 240W

I-V CURVES

I-V Curves of PV module TSM-230PA05




I-V Curves of module TSM-230PA05 at various cell temperatures



APPROVED FOR ZONING ONLY
SEAN KINNEVY, ZONING OFFICER

JUL 15 2011

DIMENSIONS



Dimensions A*B*C

1650*992*46 (mm) | 64.96*39.05*1.81 (in.)

Installation Hole E*F

941*990 (mm) | 37.05*38.98 (in.)

Cable Length G

1000 (mm) | 39.37 (in.)

*The company is not responsible for potential typing errors.



TRINA TSM-PA05, 220W to 240W

TYPICAL ELECTRICAL CHARACTERISTICS

Type	TSM-PA05	220	230	240
Max-Power	P _m (W)	220	230	240
Power Tolerance	(%)	±3	±3	±3
Max-Power Voltage	V _m (V)	29.8	30.0	30.6
Max-Power Current	I _m (A)	7.39	7.66	7.84
Open-Circuit Voltage	V _{oc} (V)	36.8	37.0	37.5
Short-Circuit Current	I _{sc} (A)	8.00	8.18	8.38
Max-System Voltage	(VDC)		600	
Cell Efficiency	η _c (%)	15.1	15.8	16.4
Module Efficiency	η _m (%)	13.4	14.1	14.7
Number, type and arrangement of cells		60 pcs. Multi-Crystalline Silicon (6x10)		
Cell Size		6" x 6" 156mm X 156mm		
No. of Bypass Diodes	(pcs.)		3	
Max. Series Fuse	(A)		14	
P _m Temperature Coefficient	(%/°C)		- 0.45	
I _{sc} Temperature Coefficient	(%/°C)		0.05	
V _{oc} Temperature Coefficient	(%/°C)		- 0.35	
NOCT- Nominal Operating Cell Temperature	(°C)		47±2	

MECHANICAL CHARACTERISTICS

Cable type, Diameter and Length	3.31mm ² (12AWG), UL Certified
Type of Connector	Tyco
Dimension A*B*C	1650*992*46 (mm) 64.96*39.05*1.81 (in.)
Weight	19.5 Kg 43 lb
No. of Draining Holes In Frame	8
Glass, Type and Thickness	High Transmission, Low Iron, Tempered Glass 3.2 mm 0.12"


PACKAGING CONFIGURATION

Packing Configuration	20 pcs./box
Quantity/Pallet	1 box / pallet
Loading Capacity	520 pcs/40ft or 120 pcs/20ft

ABSOLUTE RATINGS

Dielectric Insulation Voltage	(VDC)	3000 max.
Operating Temperature	(°C)	-40~+85
Storage Temperature	(°C)	-40~+85

*STC Conditions(1000W/m²; 1.5 AM and 25°C Cell temperature)



High Efficiency
Multicrystalline Solar Modules

STRENGTHS

- High Efficiency
- High Power Output
- High Transmission Low Iron
- Tempered Glass
- Can be used up to 25°C
- Available in 200W, 220W, 240W

WARRANTY

Material: 5 years
Power production: 10 years
30% / 25 years

CERTIFICATIONS




Trinasolar


TRINA TSM-PA05, 220W to 240W

I-V CURVES

I-V Curves of PV module TSM-230PA05



I-V Curves of module TSM-230PA05 at various cell temperatures



APPROVED FOR ZONING ONLY
SEAN KINNEVY, ZONING OFFICER



JUL 15 2011

DIMENSIONS

B = 992 mm | 39.05"

C = 46 mm | 1.81"

F = 941 mm | 37.05"



Dimensions A*B*C

1650*992*46 (mm) | 64.96*39.05*1.81 (in.)

Installation Hole E*F

941*990 (mm) | 37.05*38.98 (in.)

Cable Length G

1000 (mm) | 39.37 (in.)

The company is not responsible for potential typing errors.



TRINA TSM-PA05, 220W to 240W

TYPICAL ELECTRICAL CHARACTERISTICS

Type	TSM-PA05	220	230	240
Max-Power	P _m (W)	220	230	240
Power Tolerance	(%)	±3	±3	±3
Max-Power Voltage	V _m (V)	29.8	30.0	30.6
Max-Power Current	I _m (A)	7.39	7.66	7.84
Open-Circuit Voltage	V _{oc} (V)	36.8	37.0	37.5
Short-Circuit Current	I _{sc} (A)	8.00	8.18	8.38
Max-System Voltage	(VDC)		600	
Cell Efficiency	η _c (%)	15.1	15.8	16.4
Module Efficiency	η _m (%)	13.4	14.1	14.7
Number, type and arrangement of cells		60 pcs. Multi-Crystalline Silicon (6x10)		
Cell Size		6" x 6" 156mm X 156mm		
No. of Bypass Diodes	(pcs.)		3	
Max. Series Fuse	(A)		14	
P _m Temperature Coefficient	(%/°C)		- 0.45	
I _{sc} Temperature Coefficient	(%/°C)		0.05	
V _{oc} Temperature Coefficient	(%/°C)		- 0.35	
NOCT- Nominal Operating Cell Temperature	(°C)		47±2	

MECHANICAL CHARACTERISTICS

Cable type, Diameter and Length	3.31mm ² (12AWG), UL Certified		
Type of Connector	Tyco		
Dimension A*B*C	1650*992*46 (mm) 64.96*39.05*1.81 (in.)		
Weight	19.5 Kg 43 lb		
No. of Draining Holes In Frame	8		
Glass, Type and Thickness	High Transmission, Low Iron, Tempered Glass 3.2 mm 0.12"		


PACKAGING CONFIGURATION

Packing Configuration	20 pcs./box
Quantity/Pallet	1 box / pallet
Loading Capacity	520 pcs/40ft or 120 pcs/20ft


ABSOLUTE RATINGS

Dielectric Insulation Voltage	(VDC)	3000 max.
Operating Temperature	(°C)	-40~+85
Storage Temperature	(°C)	-40~+85

*STC Conditions (1000W/m²; 1.5 AM and 25°C Cell temperature)



High Efficiency
Multicrystalline Solar Modules





ELECTRICAL
SUBCODE
TECHNICAL SECTION

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170-04 Lot 3 Qualification Code _____

Work Site Location 123 Jona St.

Owner in Fee Back W. 03734

Address Diane Collins

Address Same as above

Address [REDACTED]

Address [REDACTED]

Address [REDACTED] N & ELECTRIC, LLC

Address 124 BOBBIS TERRACE

Address NEW EGYPT, NEW JERSEY 08533

Tel (609) 758-1844 FAX (609) 758-4629

Contractor License No. 14815

Federal Emp. No. 16-1644430

B. ELECTRICAL CHARACTERISTICS 4.6 kw system

Use Group Present _____ Proposed _____

[] Pole/Pad # _____ [] Temporary [] Other _____

Building Occupied as residential Utility Co. ICPL

Est. Cost of Elec. Work \$ 19,384

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Dates (Month/Day)
[] No Plans Required			Type:	Failure
Joint Plan Review Required:			Rough	Approval
[] Building [] Plumbing			Barrier-Free	Initial
[] Fire [] Elevator			Trench	
[] Elec. Plans Approved			Temp. Serv.	
Date: <u>7/24/11</u>			Constr. Serv.	
Approved by: <u>[Signature]</u>			TCO	
			Other	
			Service	
			Final	
			Barrier-Free	
SUBCODE APPROVAL			Temp. Cut-in-Card Date Issued	
[] CO [] CCO [] CA			Final Cut-in-Card Date Issued	
Date: _____			Annual Pool Inspection	
Approved by: _____			Date of Grounding and Bonding	
			Certification	

- 1. White-Inspector copy
- 2. Canary- Applicant copy
- 3. Pink- Office Copy
- 4. White Tag- Office copy



Date Received 7/26/11
Date Issued 11-28-11
Control #
Permit #

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature
[Signature]

[] Licensed Elec. Contractor [] Certifd Landscape Irrigation Contr [] Exempt Applicant

D. TECHNICAL SITE DATA

QTY. SIZE ITEMS

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles

Motors—Fract. HP

Emergency & Exit Lights

Communications Points Array

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UW Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptacle

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Receptacle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air Handler

KW Baseboard Heat

HP Motors 1/4 HP

KW 4.0 Transfer Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

Administrative Surcharge \$

Minimum Fee \$

State Permit Surcharge Fee \$

TOTAL FEE \$

UCC/F-120 (REV. 7/03)

Professional Printing

(856) 468-7933



ELECTRICAL
SUBCODE
TECHNICAL SECTION

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION, WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170-04 Lot 3 Qualification Code _____

Work Site Location 122 John St.

Owner in Fee Black U.I. 08124

Address Diace Collins

Address Same as above

Tel _____

Co _____

Address N & ELECTRIC, LLC

Address 124 BOBBIS TERRACE

Address NEW EGYPT, NEW JERSEY 08533

Tel (609) 758-1844 FAX (609) 758-4529

Contractor License No. 14815

Federal Emp. No. 16-1644430

B. ELECTRICAL CHARACTERISTICS 4.6 kw system

Use Group _____ Present _____ Proposed _____

[] Pole/Pad # _____ [] Temporary [] Other _____

Building Occupied as Residential Utility Co. SEPL

Est. Cost of Elec. Work \$ 19,884

JOB SUMMARY (Office Use Only)

PLAN REVIEW		INSPECTIONS		Dates (Month/Day)	
	Date	Initial	Type:	Failure	Approval
[] No Plans Required			Rough		Initial
Joint Plan Review Required:					
[] Building	[] Plumbing		Barrier-Free		
[] Fire	[] Elevator		Trench		
[] Elec. Plans Approved			Temp. Serv.		
			Constr. Serv.		
			TCO		
			Other		
			Service		
			Final		
			Barrier-Free		
SUBCODE APPROVAL					
[] CO	[] CCO	[] CA	Temp. Cut-in-Card Date Issued		
			Final Cut-in-Card Date Issued		
			Annual Pool Inspection		
			Date of Grounding and Bonding Certification		
Approved by: _____					

1. White-Inspector copy
2. Canary-Applicant copy
3. Pink-Office Copy
4. White Tag-Office copy



Date Received
Date Issued
Control #
Permit #

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

Licensed Elec. Contractor [] Cert'd Landscape Irrigation Contr [] Exempt Applicant

TECHNICAL SITE DATA

QTY. SIZE ITEMS

- Lighting Fixtures
- Receptacles
- Switches
- Detectors
- Light Poles
- Motors—Fract. HP
- Emergency & Exit Lights
- Communications Points
- Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

- Pool Permit/with UW Lights
- Storable Pool/Spa/Hot Tub
- KW Elec. Range/Receptacle
- KW Oven/Surface Unit
- KW Elec. Water Heater
- KW Elec. Dryer/Receptacle
- KW Dishwasher
- HP Garbage Disposal
- KW Central A/C Unit
- HP/KW Space Heater/Air Handler
- KW Baseboard Heat
- HP Motors 1/4 HP
- KW Transformer/Generator
- AMP Service
- AMP Subpanels
- AMP Motor Control Center
- KW Elec. Sign/Outline Light

FEE (Office Use Only)

Administrative Surcharge \$
Minimum Fee \$
State Permit Surcharge Fee \$
TOTAL FEE \$

UCC/F-120 (REV. 7/03)
Professional Printing
(856) 468-7933

DATE

JOB CONDITION / COMMENTS



BUILDING SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 3 Qualification Code _____
Work Site Location 1170 3rd St

Owner in Fee: GeoGenix, LLC e-mail _____

Tel. (732) 661-8841 e-mail _____

Address 2101 N. 1st St municipality _____ zip code _____

Contractor: GeoGenix, LLC Tel. (732) 761-8841

Address 8998 Route 18, Old Bridge, NJ 08857 e-mail permits@geogenix.com

Contractor License No. or Builder Registration No. I3VH02387400 Exp. Date 12/31/11

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. 22-3801373 FAX: (732) 676-7800

JOB SUMMARY (Office Use Only)

PLAN REVIEW		INSPECTIONS		Dates (Month/Day)	
	Initial	Type	Failure	Approval	Initial
☐ No Plans Required		Footings			
☐ All		Footings/Bonding			
☐ Footings		Foundation			
☐ Foundation		Slab			
☐ Frame		Frame			
☐ Other		Truss Sys./Bracing			
Joint Plan Review Required		Barrier-Free			
☐ Elec.		Insulation			
☐ Plumb.		Finishes—Base Layer			
☐ Fire		Finishes—Final			
SUBCODE APPROVAL		Energy			
☐ CO		Mechanical			
☐ CCO		TCO			
☐ CA		Other			
Date: _____		Final			
Approved by: _____		Barrier-Free			

B. BUILDING CHARACTERISTICS

Use Group	Present	Proposed	Est. Cost of Bldg. Work:
Constr. Class	Present	Proposed	1. New Bldg. \$ _____
No. of Stories	_____	_____	2. Rehabilitation \$ _____
Height of Structure	_____ Ft.	_____	3. Total (1+2) \$ _____
Area — Largest Floor	_____ Sq. Ft.	_____	
New Bldg. Area/All Floors	_____ Sq. Ft.	_____	
Volume of New Structure	_____ Cu. Ft.	_____	
Total Land Area Disturbed	_____ Sq. Ft.	_____	

U.C.C. F110 (rev. 7/06)

Applicant: When submitting this form to your Local Construction Code Enforcement Office, please provide one original plus three photocopies.

Date Received
Control #

Date Issued
Permit #

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

Signature _____

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Remove old water line and install new water line.

TYPE OF WORK:

- ☐ New Building
- ☐ Addition
- ☐ Rehabilitation
- ☐ Roofing
- ☐ Siding
- ☐ Fence _____ Height (exceeds 6') _____ Sq. Ft.
- ☐ Sign _____ Sq. Ft.
- ☐ Pool
- ☐ Retaining Wall _____ Sq. Ft.
- ☐ Asbestos Abatement Subchapter 8
- ☐ Lead Haz. Abatement NJAC 5:17
- ☐ Radon Remediation
- ☐ Other _____
- ☐ Demolition

FEE (Office Use Only)

Administrative Surcharge \$	_____
Minimum Fee \$	_____
State Permit Surcharge Fee \$	_____
TOTAL FEE \$	_____



July 14, 2011

Adalberto Souto, Electrical Subcode Official
Brick Township Bldg. Dept.
401 Chambers Bridge Road
Brick, NJ 08723

Dear Mr. Souto:

We have been contracted to install a photovoltaic (solar-electric) system on the roof of the residence indicated below:

Diane Collis
128 John Street
Brick, NJ 08724
Block 1170.04, Lot 3

Although we have installed many of these systems throughout the state, we realize these systems are still relatively new in New Jersey. Therefore, we are submitting the following material in hopes it will satisfy the needs of your department:

1. The construction permit, building sub-code and electrical sub-code applications.
2. Two (2) copies of detailed specification sheets for the photovoltaic panels (generate DC electricity) and inverters (change the DC electricity to AC), including references to their individual UL listings.
3. Two (2) copies of a diagram showing the placement of the solar panels on the roof of the home plus positioning of the inverter and all necessary disconnect switches.
4. Two (2) copies of a 1-line diagram showing all electrical wiring and equipment.

Please call the numbers listed below or send an email if you have any questions, comments or suggestions on how to expedite getting the permits for this installation.

Thank you for your time and attention.

Sincerely,

Christy Lorenz

Christy Lorenz, Administrative Assistant, 732-761-8841, Christy.lorenz@geogenix.com


Enc.

Trinasolar


TRINA TSM-PA05, 220W to 240W

I-V CURVES


I-V Curves of PV module TSM-230PA05



I-V Curves of module TSM-230PA05 at various cell temperatures



DIMENSIONS



Dimensions A*B*C

1650*992*46 (mm) | 64.96*39.05*1.81 (in.)

Installation Hole E*F

941*990 (mm) | 37.05*38.98 (in.)

Cable Length G

1000 (mm) | 39.37 (in.)

*The company is not responsible for potential typing errors.



TRINA TSM-PA05, 220W to 240W

TYPICAL ELECTRICAL CHARACTERISTICS

Type	TSM-PA05	220	230	240
Max-Power	P _m (W)	220	230	240
Power Tolerance	(%)	±3	±3	±3
Max-Power Voltage	V _m (V)	29.8	30.0	30.6
Max-Power Current	I _m (A)	7.39	7.66	7.84
Open-Circuit Voltage	V _{oc} (V)	36.8	37.0	37.5
Short-Circuit Current	I _{sc} (A)	8.00	8.18	8.38
Max-System Voltage	(VDC)		600	
Cell Efficiency	η _c (%)	15.1	15.8	16.4
Module Efficiency	η _m (%)	13.4	14.1	14.7
Number, type and arrangement of cells		60 pcs. Multi-Crystalline Silicon (6x10)		
Cell Size		6" x 6" 156mm X 156mm		
No. of Bypass Diodes	(pcs.)		3	
Max. Series Fuse	(A)		14	
P _m Temperature Coefficient	(%/°C)		- 0.45	
I _{sc} Temperature Coefficient	(%/°C)		0.05	
V _{oc} Temperature Coefficient	(%/°C)		- 0.35	
NOCT- Nominal Operating Cell Temperature	(°C)		47±2	

MECHANICAL CHARACTERISTICS

Cable type, Diameter and Length	3.31mm ² (12AWG), UL Certified		
Type of Connector	Tyco		
Dimension A*B*C	1650*992*46 (mm) 64.96*39.05*1.81 (in.)		
Weight	19.5 Kg 43 lb		
No. of Draining Holes In Frame	8		
Glass, Type and Thickness	High Transmission, Low Iron, Tempered Glass 3.2 mm 0.12"		


PACKAGING CONFIGURATION

Packing Configuration	20 pcs./box
Quantity/Pallet	1 box / pallet
Loading Capacity	520 pcs/40ft or 120 pcs/20ft

ABSOLUTE RATINGS

Dielectric Insulation Voltage	(VDC)	3000 max.
Operating Temperature	(°C)	-40~+85
Storage Temperature	(°C)	-40~+85

*STC Conditions(1000W/m²; 1.5 AM and 25°C Cell temperature)



High Efficiency
Multicrystalline Solar Modules

STRENGTHS

- High efficiency 18.2%
- 3 Bus Bar Configuration
- Plug & Play Connectors
- High Transmission Low Iron Tempered Glass
- Can bear loads up to 5400 Pascals (IEC 61215 2nd Ed)

WARRANTY

Manufacturing: 5 years
Power production: 10 years
30% 25 years

CERTIFICATIONS




Trinasolar


TRINA TSM-PA05, 220W to 240W

I-V CURVES


I-V Curves of PV module TSM-230PA05



I-V Curves of module TSM-230PA05 at various cell temperatures



DIMENSIONS



Dimensions A*B*C

1650*992*46 (mm) | 64.96*39.05*1.81 (in.)

Installation Hole E*F

941*990 (mm) | 37.05*38.98 (in.)

Cable Length G

1000 (mm) | 39.37 (in.)

*The company is not responsible for potential typing errors.



TRINA TSM-PA05, 220W to 240W

TYPICAL ELECTRICAL CHARACTERISTICS

Type	TSM-PA05	220	230	240
Max-Power	P _m (W)	220	230	240
Power Tolerance	(%)	±3	±3	±3
Max-Power Voltage	V _m (V)	29.8	30.0	30.6
Max-Power Current	I _m (A)	7.39	7.66	7.84
Open-Circuit Voltage	V _{oc} (V)	36.8	37.0	37.5
Short-Circuit Current	I _{sc} (A)	8.00	8.18	8.38
Max-System Voltage	(VDC)		600	
Cell Efficiency	η _c (%)	15.1	15.8	16.4
Module Efficiency	η _m (%)	13.4	14.1	14.7
Number, type and arrangement of cells		60 pcs. Multi-Crystalline Silicon (6x10)		
Cell Size		6" x 6" 156mm X 156mm		
No. of Bypass Diodes	(pcs.)		3	
Max. Series Fuse	(A)		14	
P _m Temperature Coefficient	(%/°C)		- 0.45	
I _{sc} Temperature Coefficient	(%/°C)		0.05	
V _{oc} Temperature Coefficient	(%/°C)		- 0.35	
NOCT- Nominal Operating Cell Temperature	(°C)		47±2	

MECHANICAL CHARACTERISTICS

Cable type, Diameter and Length	3.31mm ² (12AWG), UL Certified		
Type of Connector	Tyco		
Dimension A*B*C	1650*992*46 (mm) 64.96*39.05*1.81 (in.)		
Weight	19.5 Kg 43 lb		
No. of Draining Holes In Frame	8		
Glass, Type and Thickness	High Transmission, Low Iron, Tempered Glass 3.2 mm 0.12"		


PACKAGING CONFIGURATION

Packing Configuration	20 pcs./box
Quantity/Pallet	1 box / pallet
Loading Capacity	520 pcs/40ft or 120 pcs/20ft

ABSOLUTE RATINGS

Dielectric Insulation Voltage	(VDC)	3000 max.
Operating Temperature	(°C)	-40~+85
Storage Temperature	(°C)	-40~+85

*STC Conditions(1000W/m²; 1.5 AM and 25°C Cell temperature)



High Efficiency
Multicrystalline Solar Modules

STRENGTHS

- Performance & Quality
- 6 Bus Bar Configuration
- Plug & Play Connectors
- High Transmission Low Iron Tempered Glass
- Can bear loads up to 5400 Pascals (120, 3125 & 1500)

WARRANTY


Manufacturing 5 years
Power production 10% 10 years
80% 25 years

CERTIFICATIONS



SMA

SUNNY BOY 3000-US / 3800-US / 4000-US



SB 3800-US NOW AVAILABLE



UL Certified

- For countries that require UL certification (UL 1741/IEEE 1547)

Efficient

- 96.8% peak efficiency
- OptiCool™ active temperature management system

Safe

- Galvanic isolation

Simple

- Patented automatic grid voltage detection*
- Integrated DC disconnect switch

SUNNY BOY 3000-US / 3800-US / 4000-US

UL certified, reliable system managers

The Sunny Boy 3000-US, 3800-US and 4000-US inverters are specially designed for countries that require UL certification. Automatic grid voltage detection* and an integrated DC disconnect switch simplifies installation, ensuring safety as well as saving time. These models feature galvanic isolation and can be used with all types of modules—crystalline as well as thin-film. The die-cast aluminum enclosure, with the OptiCool active temperature management system, guarantees the highest yields possible and a long service life, even under extreme conditions. The Sunny Boy 3800-US is designed for projects with a current limit of 16A.

* US Patent US7352549B1

Technical data

Input (DC)

Max. recommended PV power (@ module STC)
 Max. DC power (@ $\cos \phi = 1$)
 Max. DC voltage
 DC nominal voltage
 MPP voltage range
 Min. DC voltage / start voltage
 Max. input current / per string (at DC disconnect)

Number of MPP trackers / fused strings per MPP tracker

Output (AC)

AC nominal power
 Max. AC apparent power
 Nominal AC voltage / adjustable
 AC voltage range
 AC grid frequency; range
 Max. output current
 Power factor ($\cos \phi$)
 Phase conductors / connection phases
 Harmonics

Efficiency

Max. efficiency
 CEC efficiency

Protection devices

DC reverse-polarity protection
 AC short circuit protection
 Galvanically isolated / all-pole sensitive monitoring unit
 Protection class / overvoltage category

General data

Dimensions (W / H / D) in mm (in)
 DC Disconnect dimensions (W / H / D) in mm (in)
 Packing dimensions (W / H / D) in mm (in)
 DC Disconnect packing dimensions (W / H / D) in mm (in)
 Weight / DC Disconnect weight
 Packing weight / DC Disconnect packing weight
 Operating temperature range (full power)
 Noise emission (typical)
 Internal consumption at night
 Topology
 Cooling concept
 Electronics protection rating / connection area

Features

Display: text line / graphic
 Interfaces: RS485 / Bluetooth
 Warranty: 10 / 15 / 20 years
 Certificates and permits (more available on request)

NOTE: US inverters ship with gray lids.

Data at nominal conditions

● Standard features ○ Optional features — Not available

Type designation


Sunny Boy 3000-US		Sunny Boy 3800-US		Sunny Boy 4000-US	
208 V AC	240 V AC	240 V AC	240 V AC	208 V AC	240 V AC
	3750 W	4750 W	4375 W	5000 W	
	3200 W	4200 W	4200 W		
	500 V	600 V	600 V		
	250 V	310 V	310 V		
175 - 400 V	200 - 400 V	250 - 480 V	220 - 480 V	250 - 480 V	
175 / 228 V	200 / 228 V	250 / 285 V	220 / 285 V	250 / 285 V	
	17 A / 17 A	18 A / 18 A	18 A / 18 A		
36 A @ combined terminal		36 A @ combined terminal	36 A @ combined terminal		
		1 / 4 (DC disconnect)			
	3000 W	3800 W	3500 W	4000 W	
	3000 VA	3800 VA	3500 VA	4000 VA	
208 V / ●	240 V / ●	240 V / —	208 V / ●	240 V / ●	
183 - 229 V	211 - 264 V	211 - 264 V	183 - 229 V	211 - 264 V	
60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz		
15 A	13 A	16 A	17 A		
	1	1	1		
	1 / 2	1 / 2	1 / 2		
	< 4%	< 4%	< 4%		
96.0%	96.5%	96.8%	96.5%	96.8%	
95.0%	95.5%	96.0%	95.5%	96.0%	
	●	●	●		
	●	●	●		
	● / —	● / —	● / —		
	I / III	I / III	I / III		
		450 / 350 / 235 (18 / 14 / 9)			
		187 / 297 / 190 (7 / 12 / 7.5)			
		390 / 580 / 470 (15 / 23 / 18.5)			
		370 / 240 / 280 (15 / 9 / 11)			
		38 kg (84 lb) / 3.5 kg (8 lb)			
		44 kg (97 lb) / 4 kg (9 lb)			
		-25 °C ... +45 °C (-13 °F ... +113 °F)			
40 dB(A)		www.SMA-Solar.com		37 dB(A)	
0.1 W		0.1 W		0.1 W	
LF transformer		LF transformer		LF transformer	
OptiCool		OptiCool		OptiCool	
NEMA 3R / NEMA 3R		NEMA 3R / NEMA 3R		NEMA 3R / NEMA 3R	
	● / —	● / —		● / —	
	○ / ○	○ / ○		○ / ○	
	● / ○ / ○	● / ○ / ○		● / ○ / ○	

UL1741, UL1998, IEEE 1547, FCC Part 15 (Class A & B), CSA C22.2 No. 107.1-2001

SB 3000US

SB 3800-US-10

SB 4000US



Accessories



RS485 interface
485USPB-NR



Bluetooth® Piggy Back
BTPBINV-NR



Combi-Switch
DC disconnect and PV
array combiner box
COMBO-SWITCH




Combiner Box
Simplify wiring for added
convenience and safety
SBCB-6-3R or SBCB-6-4

Toll Free +1 888 4 SMA USA
 www.SMA-America.com

SMA America, LLC

SMA

SUNNY BOY 3000-US / 3800-US / 4000-US



SB 3800-US NOW AVAILABLE



UL Certified

- For countries that require UL certification (UL 1741/IEEE 1547)

Efficient

- 96.8% peak efficiency
- OptiCool™ active temperature management system

Safe

- Galvanic isolation

Simple

- Patented automatic grid voltage detection*
- Integrated DC disconnect switch

SUNNY BOY 3000-US / 3800-US / 4000-US

UL certified, reliable system managers

The Sunny Boy 3000-US, 3800-US and 4000-US inverters are specially designed for countries that require UL certification. Automatic grid voltage detection* and an integrated DC disconnect switch simplifies installation, ensuring safety as well as saving time. These models feature galvanic isolation and can be used with all types of modules—crystalline as well as thin-film. The die-cast aluminum enclosure, with the OptiCool active temperature management system, guarantees the highest yields possible and a long service life, even under extreme conditions. The Sunny Boy 3800-US is designed for projects with a current limit of 16A.

* US Patent US7352549B1

Technical data

Input (DC)

Max. recommended PV power (@ module STC)
 Max. DC power (@ $\cos \phi = 1$)
 Max. DC voltage
 DC nominal voltage
 MPP voltage range
 Min. DC voltage / start voltage
 Max. input current / per string (at DC disconnect)

Number of MPP trackers / fused strings per MPP tracker

Output (AC)

AC nominal power
 Max. AC apparent power
 Nominal AC voltage / adjustable
 AC voltage range
 AC grid frequency; range
 Max. output current
 Power factor ($\cos \phi$)
 Phase conductors / connection phases
 Harmonics

Efficiency

Max. efficiency
 CEC efficiency

Protection devices

DC reverse-polarity protection
 AC short circuit protection
 Galvanically isolated / all-pole sensitive monitoring unit
 Protection class / overvoltage category

General data

Dimensions (W / H / D) in mm (in)
 DC Disconnect dimensions (W / H / D) in mm (in)
 Packing dimensions (W / H / D) in mm (in)
 DC Disconnect packing dimensions (W / H / D) in mm (in)
 Weight / DC Disconnect weight
 Packing weight / DC Disconnect packing weight
 Operating temperature range (full power)
 Noise emission (typical)
 Internal consumption at night
 Topology
 Cooling concept
 Electronics protection rating / connection area

Features


Display: text line / graphic
 Interfaces: RS485 / Bluetooth
 Warranty: 10 / 15 / 20 years
 Certificates and permits (more available on request)

NOTE: US inverters ship with gray lids.

Data at nominal conditions

● Standard features ○ Optional features — Not available

Type designation



Sunny Boy 3000-US		Sunny Boy 3800-US	Sunny Boy 4000-US	
208 V AC	240 V AC	240 V AC	208 V AC	240 V AC
3750 W	3200 W	4750 W	4375 W	5000 W
500 V	500 V	600 V	600 V	600 V
250 V	250 V	310 V	310 V	310 V
175 - 400 V	200 - 400 V	250 - 480 V	220 - 480 V	250 - 480 V
175 / 228 V	200 / 228 V	250 / 285 V	220 / 285 V	250 / 285 V
17 A / 17 A	17 A / 17 A	18 A / 18 A	18 A / 18 A	18 A / 18 A
36 A @ combined terminal	36 A @ combined terminal	36 A @ combined terminal	36 A @ combined terminal	36 A @ combined terminal
		1 / 4 (DC disconnect)		
3000 W	3000 VA	3800 W	3500 W	4000 W
208 V / ●	240 V / ●	3800 VA	3500 VA	4000 VA
240 V / —	240 V / —	240 V / —	208 V / ●	240 V / ●
183 - 229 V	211 - 264 V	211 - 264 V	183 - 229 V	211 - 264 V
60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz	60 Hz; 59.3 - 60.5 Hz
15 A	13 A	16 A	17 A	17 A
1	1	1	1	1
1 / 2	1 / 2	1 / 2	1 / 2	1 / 2
< 4%	< 4%	< 4%	< 4%	< 4%
96.0%	96.5%	96.8%	96.5%	96.8%
95.0%	95.5%	96.0%	95.5%	96.0%
DC reverse-polarity protection	●	●	●	●
AC short circuit protection	●	●	●	●
Galvanically isolated / all-pole sensitive monitoring unit	●/—	●/—	●/—	●/—
Protection class / overvoltage category	I / III	I / III	I / III	I / III
Dimensions (W / H / D) in mm (in)	450 / 350 / 235 (18 / 14 / 9)			
DC Disconnect dimensions (W / H / D) in mm (in)	187 / 297 / 190 (7 / 12 / 7.5)			
Packing dimensions (W / H / D) in mm (in)	390 / 580 / 470 (15 / 23 / 18.5)			
DC Disconnect packing dimensions (W / H / D) in mm (in)	370 / 240 / 280 (15 / 9 / 11)			
Weight / DC Disconnect weight	38 kg (84 lb) / 3.5 kg (8 lb)			
Packing weight / DC Disconnect packing weight	44 kg (97 lb) / 4 kg (9 lb)			
Operating temperature range (full power)	-25 °C ... +45 °C (-13 °F ... +113 °F)			
Noise emission (typical)	40 dB(A)	www.SMA-Solar.com	37 dB(A)	
Internal consumption at night	0.1 W	0.1 W	0.1 W	
Topology	LF transformer	LF transformer	LF transformer	
Cooling concept	OptiCool	OptiCool	OptiCool	
Electronics protection rating / connection area	NEMA 3R / NEMA 3R	NEMA 3R / NEMA 3R	NEMA 3R / NEMA 3R	
Display: text line / graphic	●/—	●/—	●/—	
Interfaces: RS485 / Bluetooth	○/○	○/○	○/○	
Warranty: 10 / 15 / 20 years	●/○/○	●/○/○	●/○/○	
Certificates and permits (more available on request)	UL1741, UL1998, IEEE 1547, FCC Part 15 (Class A & B), CSA C22.2 No. 107.1-2001			

SB 3000US

SB 3800-US-10

SB 4000US

Accessories



RS485 interface
485USPB-NR



Bluetooth® Piggy Back
BTPBINV-NR



Combi-Switch
DC disconnect and PV
array combiner box
COMBO-SWITCH



Combiner Box
Simplify wiring for added
convenience and safety
SBCB-6-3R or SBCB-6-4

Toll Free +1 888 4 SMA USA
 www.SMA-America.com

SMA America, LLC



GeoGenix LLC

Leaders in Energy-Saving
Design and Construction

GeoGenix, LLC

79 East River Road

Rumson, NJ 07760

(T) 732.895.9550

(F) 801.382.0751

STRUCTURAL ENGINEER:

Ascent Consulting

James A. Marx, P.E.

10 High Mountain Road

Ringwood, NJ 07456

(T) 973.557.6080

CUSTOMER:

Diane Collis Residence

128 John Street

Brick, NJ, 08724

UTILITY COMPANY:

JCPL

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM

Solar Panel


Array Layout

PROJECT #: DATE: 7/6/11

DRAWN BY: GLK REV #:

SCALE: As Noted

PV-1



SOLAR PANEL ARRAY

Roof Pitch = $25^{\circ} \pm$


(20) TrinaSolar TSM PA05 230w panels (4.6 kW total)

INVERTER

(1) SB-4000us W/ (2) Strings of (10) Panels

RACKING:

DPW Power Rail System



SOLAR ARRAY
158°



Solar (Photovoltaic) Panel

Direction of Roof Slope

LEGEND:

NOTES:

- See specifications for additional information.
- See electrical One-line drawing (PV-2) for wiring connections.
- North arrow and Array orientation based on "True" direction (magnetic compass reading minus Magnetic Declination of 11 degrees equals true Array orientation (Azimuth) of 158 degrees.)





GeoGenix LLC

Leaders in Energy-Saving
Design and Construction

GeoGenix, LLC

79 East River Road

Rumson, NJ 07760

(T) 732.895.9550

(F) 801.382.0751

STRUCTURAL ENGINEER:

Ascent Consulting

James A. Marx, P.E.

10 High Mountain Road

Ringwood, NJ 07456

(T) 973.557.6080

CUSTOMER:

Diane Collis Residence

128 John Street

Brick, NJ, 08724

UTILITY COMPANY:

JCPL

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM

Solar Panel


Array Layout

PROJECT #: DATE: 7/6/11

DRAWN BY: GLK REV #:

SCALE: As Noted

PV-1



SOLAR PANEL ARRAY

Roof Pitch = $25^{\circ} \pm$

(20) TrinaSolar TSM PA05 230w panels (4.6 kW total)

INVERTER

(1) SB-4000us W/ (2) Strings of (10) Panels

RACKING:

DPW Power Rail System


NOTES:

- See specifications for additional information.
- See electrical One-line drawing (PV-2) for wiring connections.
- North arrow and Array orientation based on "True" direction (magnetic compass reading minus Magnetic Declination of 11 degrees equals true Array orientation (Azimuth) of 158 degrees.)

1 PLAN
PV-1 N.T.S.



Solar (Photovoltaic) Panel



Direction of Roof Slope

LEGEND:

NOTES:


1. Trina solar panels utilize a negative ground system with the positive opened in the dc disconnect.
2. Use #10 USE-2 wire between solar panels, and to Junction Box.
3. Use #10 AWG copper wire to continuously ground solar panels.
4. Use #6 THWN-2 wire for grounding electrode conductors and #8 solid AWG wire for the bonding of the (racking) rails.
5. Use #10 THWN-2 wire from solar panels (Junction Box) to Inverter in either 1" PVC conduit on outside of building or 1" metallic conduit inside building.
6. *Use #6 THWN-2 wire from Inverter to the interconnection point at Main Disconnect, in 1" conduit.
7. Reverse current flow calculation: $(2-1) \times 8.18A \times 1.25 \times 10.22A < 14A$ module fuse rating therefore, no additional module fusing is necessary.

Solar Panel Ratings at Standard Test Conditions (STC)

Manufacturer: Trina Solar
 Model: TSM-PA05 230W
 Open Circuit Voltage (Voc): 37.0 V
 Operating Voltage (Vmpp): 30.0 V
 Short Circuit Current (Isc): 8.18 A
 Operating Current (Impp): 7.66 A
 Max Series Fuse: 14 A
 Peak Power: 230 Watts
 Dimensions: 39" x 65"
 Weight: 43 lbs.

PV System Specifications: per NEC 690.53 (Required Labeling)

4000 Watt Inverter No. 1 (2 strings of 10 panels):
 Rated Maximum Current = 15.3 A
 Rated Maximum Voltage = 300 V
 Maximum System Voltage = 439.1 V
 Max. (short circuit) Current = 20.5 A



Total System Size:
 20 panels @ 230 watts = 4.6
 Kilo-watts.



GeoGenix, LLC
 Leaders in Energy-Saving
 Design and Construction

79 East River Road
 Rumson, NJ 07760
 (T) 732.895.9550
 (F) 801.382.0751

**J. A. Wig Construction
 & Electrical, LLC**

Lic. #14815
 121 Bobbis Terrace
 New Egypt, NJ 08533
 (T) 732-761-8841

CUSTOMER:

Diane Collis Residence
 128 John Street
 Brick, NJ, 08724

UTILITY COMPANY:

JCPL

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM

One-Line

Wiring Diagram

PROJECT #:

DATE: 7/8/11

DRAWN BY:

GLK REV #:

SCALE:

AS NOTED

PV-2

NOTES:


1. Trina solar panels utilize a negative ground system with the positive opened in the dc disconnect.
2. Use #10 USE-2 wire between solar panels, and to Junction Box.
3. Use #10 AWG copper wire to continuously ground solar panels.
4. Use #6 THWN-2 wire for grounding electrode conductors and #8 solid AWG wire for the bonding of the (racking) rails.
5. Use #10 THWN-2 wire from solar panels (Junction Box) to Inverter in either 1" PVC conduit on outside of building or 1" metallic conduit inside building.
6. Use #6 THWN-2 wire from Inverter to the interconnection point at Main Disconnect, in 1" conduit.
7. Reverse current flow calculation: $(2-1) \times 8.18 \text{ A} \times 1.25 \times 10.22 \text{ A} < 14 \text{ A}$ module fuse rating therefore, no additional module fusing is necessary.

Solar Panel Ratings at Standard Test Conditions (STC)

Manufacturer: Trina Solar
 Model: TSM-PA05 230W
 Open Circuit Voltage (Voc) 37.0 V
 Operating Voltage (Vmpp) 30.0 V
 Short Circuit Current (Isc) 8.18 A
 Operating Current (Impp) 7.66 A
 Max Series Fuse 14 A
 Peak Power: 230 Watts
 Dimensions: 39" x 65"
 Weight: 43 lbs.

PV System Specifications: per NEC 690.53 (Required Labeling)

4000 Watt Inverter No. 1 (2 strings of 10 panels):
 Rated Maximum Current = 15.3 A
 Rated Maximum Voltage = 300 V
 Maximum System Voltage = 439.1 V
 Max. (short circuit) Current = 20.5 A



Total System Size:
 20 panels @ 230 watts = 4.6
 Kilo-watts.

AUXILIARY GROUND DC System Ground (typ.) (See Note 4)

EQUIPMENT GROUND

GROUND

PV-2



GeoGenix, LLC
 Leaders in Energy-Saving
 Design and Construction

79 East River Road
 Rumson, NJ 07760
 (T) 732.895.9550
 (F) 801.382.0751

**J. A. Wig Construction
 & Electrical, LLC**
 Lic. #14815

121 Bobbitt Terrace
 New Egypt, NJ 08533
 (T) 732-761-8841

CUSTOMER:

Diane Collis Residence
 128 John Street
 Brick, NJ, 08724

UTILITY COMPANY:

JCPL

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM
 One-Line
 Wiring Diagram

PROJECT #: DATE: 7/6/11

DRAWN BY: GLK REV #:

SCALE: AS NOTED

July 8, 2011

To: Building Department

From: James A. Marx, Jr. P.E.

Re: Engineer Statement for Collis Residence, 128 John St., Brick, NJ
for Solar Roof Installation


I have verified the adequacy and structural integrity of the existing roof rafters for mounting of solar panels and their installation will satisfy the structural roof framing design-loading requirements of the New Jersey State building code – International Residential Code (IRC) – 2009 NJ.

For the installation of the solar mounting, the mounting rails will be anchored to the rafters with Quick Mounts on the center of the rafters and will be securely fastened to the rafters with lag screws. **The design is based on the added weight of the collectors, wind speed of 115 mph, exposure B and ground snow load of 20 psf.**

The Photovoltaic system and the mounting assemblies will comply with the applicable sections of the International Residential Code– “Solar Systems” and loading requirements of roof-mounted collectors.

Thereby, I endorse the solar panel installation and certify this design to be structurally adequate.

Sincerely,



James A. Marx, Jr. P.E.
Professional Engineer
NJ GE25179

10 High Mountain Road
Ringwood, NJ 07456

Attach: PV-1 & Sheet S-2

cc: GeoGenix, Mitchell Berman

TOWNSHIP OF BRICK
RELEASED FOR PERMIT
Building Subcode _____
Fire Subcode _____
Electrical Subcode _____
Plan Reviewer _____
Plans Released _____
Construction Official _____
INITIAL KA DATE 7/19/11



GeoGenix LLC

Leaders in Energy-Saving
Design and Construction

GeoGenix, LLC

79 East River Road
Rumson, NJ 07760

(T) 732.896.9550

(F) 801.382.0751

STRUCTURAL ENGINEER:

Ascent Consulting

James A. Marx, P.E.

10 High Mountain Road

Ringwood, NJ 07456

(T) 973.557.6080

CUSTOMER:

Diane Collis Residence

128 John Street

Brick, NJ, 08724

UTILITY COMPANY:

JCPL

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM

Solar Panel


Array Layout

PROJECT #: DATE: 7/6/11

DRAWN BY: GLK REV #:

SCALE: As Noted

PV-1



SOLAR PANEL ARRAY

Roof Pitch = $25^{\circ} \pm$


(20) TrinaSolar TSM PA05 230w panels (4.6 kW total)

INVERTER

(1) SB-4000us W/ (2) Strings of (10) Panels

RACKING:

DPW Power Rail System



SOLAR ARRAY

158°

NOTES:

1. See specifications for additional information.
2. See electrical One-line drawing (PV-2) for wiring connections.
3. North arrow and Array orientation based on "True" direction (magnetic compass reading minus Magnetic Declination of 11 degrees equals true Array orientation (Azimuth) of 158 degrees.)

ASCENT CONSULTING ENGINEERING
10 HIGH MOUNTAIN ROAD, RINGWOOD, NJ 07456
246A28112100

1 PLAN
PV-1 N.T.S.


James A. Marx Jr.

JAMES A. MARX JR.

Professional Engineer

NJ Professional Engineer License GE25179

QUICK MOUNT PV WITH
5/16"Ø HANGER BOLT
(MIN. 1 3/4" | THREAD EMBED INTO RAFTER)
(TYP.)



INSTALLATION INSTRUCTION:

1. MOUNTING RAIL PERPENDICULAR TO RAFTER
INSTALLED PER MANUFACTURER INSTRUCTIONS.
2. QUICK MOUNT PV WITH FLASHING AND
MOUNT ANCHOR TO BE INSTALLED PER
MANUFACTURER INSTRUCTIONS.
3. THE SOLAR ROOF CONTRACTOR IS RESPONSIBLE
FOR MAINTAINING THE WATERPROOF INTEGRITY
OF THE ROOF INCLUDING THE SELECTION OF
THE APPROPRIATE SEALANT.

PARTIAL PLAN

TYPICAL QUICK MOUNT ARRANGEMENT

NTS

ASCENT CONSULTING ENGINEERING
10 HIGH MOUNTAIN ROAD, RINGWOOD, NJ 07458
24GA28112100

James A. Marx Jr.
JAMES A. MARX JR.
Professional Engineer
NJ Professional Engineer License GE25179



CUSTOMER:

COLLIS RESIDENCE
BRICK, NJ

TITLE:

MOUNTING RAIL DETAIL

APPROVED:

DRAWN BY:

DATE: 7/8/2011

DWG. NO.

S-2

REV.:


SOLAR ELECTRIC SYSTEM

COLLIS RESIDENCE
BRICK, NJ

STRUCTURAL DESIGN CALCULATIONS FOR SOLAR ROOF SYSTEM

ASCENT CONSULTING ENGINEERING
24GA28112100
10 High Mountain Road
Ringwood, NJ 07456

James A. Marx, Jr.
Professional Engineer


7/31/11
Pages 1 to 10

NJ Professional Engineer License GE 25179

PHOTOVOLTAIC SYSTEM STRUCTURAL ANALYSIS WORKSHEET
Photovoltaic_System_Site_Survey_Worksheet15_NO_TRUSSES.xls
Roof

OFFICE USE ONLY (COMPLETED PRIOR TO SITE SURVEY)

Job Name: Collis, Diane
 S: 128 John St
 City, State Zip: Brick, NJ 08724

SITE SURVEY

Assigned by: Mike Krokovic Custom Builder
 Date Assigned:
 Date Needed:
 Additional Instructions/Notes: Assigned by Brandon Iselin

PV MODULES

Manufacturer	
Model	
Unit Weight (lbs)	
No.	
Total Weight (lbs)	
Manufacturer	
Model	
Unit Weight (lbs)	
No.	
Total Weight (lbs)	
Manufacturer	
Model	
Unit Weight (lbs)	
Total Weight (lbs)	
Grand Total Weight (lbs)	0

RACKING SYSTEM

Rack type
 Panel Mounting Orientation
 Rack L-Foot Spacing Across Rafter (in)
 Rack L-Foot Spacing On Rafter (in)

Exposure Category: Category B
 Roof ID: Front Roof
 Roof Type: Gabled

ROOF USED FOR MOUNTING MODULES

Roof Faces...(Orientation) 158
 ROOF ANGLE
 Angle (deg): 25
 Slope (in): 5.596
 DIMENSIONS
 Length of House: 54
 Length of House (ft): 54.33
 Width of House: 28
 Width of House (ft): 28.00
 Height to Eave: 9
 Height to Eave (ft): 9.17
 Gutter-to-Ridge Length: 16
 Gutter-to-Ridge Length (ft): 16.25
 Overhang Length: 19
 Overhang Length (ft): 19.00
 Distance from Exterior Wall to Supporting Wall: 11
 Dist to Supporting Wall (ft): 11.50
 Length of Roof w/ Modules: 54
 Length of Roof w/ Modules (ft): 54.67
 Width of Roof w/ Modules: 16
 Width of Roof w/ Modules (ft): 16.25

FRAMING MEMBERS CONDITION

Wide splits? No
 Twisted rafters? No
 ROOF SUPPORT (RAFTERS)
 Size (in): 2x6
 Spacing (in): 16
 Lumber Size: Nominal
 Material: Conventional Wood
 Hurricane Ties? No

RIDGE

Size (in): 2x8
 Lumber Size: Nominal
 Material: Conventional Wood

COLLAR TIES

Size (in):
 Spacing (in):
 Lumber Size:
 Distance to bottom of ridge board (in):

CEILING SUPPORT (JOISTS)

Size (in): 2x6
 Spacing (in): 16
 Lumber Size: Nominal

FLOOR SHEATHING

Type: Tongue-and-Groove
 Thickness (in): 3/4
 Extent: 50%

POSTS SUPPORTING RIDGE BEAMS

Size (in):
 Lumber Size:
 Spacing (ft. or see "Notes"):
 Number:
 Method of supporting base:

OTHER INTERIOR SUPPORT (e.g. KNEEWALLS)


Type: Knee wall
 Size (in): 2x4
 Lumber Size: Nominal
 Spacing between studs (in): 16

Take photos... especially of any defective conditions

Provide locations of any defective conditions on a plan of the roof, showing distance from end of roof and ridge

Exposure Categories

Category B – Urban and suburban areas, wooded areas, wooded areas or other terrain with numerous closely spaced obstructions having the size of single-family dwellings or larger.
Category C – Open terrain with scattered obstructions having heights generally less than 30 ft. This includes flat open country, grasslands and water surfaces



ROOF SHEATHING

Type: Plywood
 Thickness (in): 1/2
 Decay Damage? No
 Large Holes? No
 Steel Clips? No
 Gaps between Sheathing and Rafters? No

SHINGLES

Type: Dimensional
 Layers: 1
 Age (years): 3
 Condition: Good
 Replacement Timeframe: No Need

OBSTRUCTIONS

Able to Access from Attic? Yes
 Plastic Plumbing Vents?
 Metallic Plumbing Vents?
 Non-Powered Ventilators?
 Powered Ventilators?
 Furnace/Boiler "B"-vent? Yes
 Weather Station?
 Satellite Dish(s)?
 Skylights?





ADDITIONAL NOTES

Knee wall runs for 18' from the west gable wall.

OFFICE USE ONLY (COMPLETED PRIOR TO SUBMISSION TO ENGINEERING)

Submitted by:
 Signed to:
 Date Submitted:
 Total Pages:
 Additional Notes:

COLL, DIANE



ORIENTATION
109° MAGNETIC
158° TRUE
TILT 25°



SURVEY LOCATIONS

- ① ② ③ ④
- ⑤ ⑥ ⑦ ⑧ ⑨ ⑩

Collis, Brick


IRC-2009 NJ

3
Jan
7/2/11

WIND SPEED 115 MPH EXP. B

G. SNOW 20 psf

Rafters 2x6 @ 16" Pitch 25



$$A = \frac{5.17}{2} \times 4 = 10.34 \text{ sf}$$

Dead

$$P_{DL} = 2.9(10.34) = 30.0$$

SNOW

$$P_f = 0.7(0.9)(1)(20) = 12.6 \text{ psf}$$

$$P_{SN} = 12.6 \cos 20 = 11.8 \times 10.34 = 122$$

$$W_3 = 11.8(133) = 1600$$

$$P_{UNBAL} \quad h_d = 1.35 \quad \delta = 10.6 \quad S = 2.75$$

$$\frac{h_d \delta}{\sqrt{S}} = \frac{1.35(10.6)}{\sqrt{2.75}} = 13.51 \times 10.34 = \frac{140}{2.262}$$

$$\frac{0.3}{3} h_d \sqrt{S} = \frac{0.3}{3} (1.35) \sqrt{2.75} = 5.96/9.4 = 6.34$$

WIND

$$q_z = 0.00256(0.7)(0.85)(115)^2 = 20.14 \text{ psf}$$

$$P_{WS} = -1.7(20.14)(10.34) = -354$$


$$0.16 P_D - P_W = -354 \quad \text{embed} = \frac{336}{205} = 1.64"$$

Use Quick Mount MIN 1 3/4" embed

Collis

2x6 @ 16" DF #2

4
from
7/7/11



$$M = 649 \text{ ft-lb}$$

$$f_b = \frac{649 \times 12}{7.263} = 1030 \text{ psi} < F_b \text{ OK}$$

$$F_D = 900 \times 1.15^2 \times 1.3 = 1547 \text{ psi}$$

```
*****
*                                     *
*      STAAD.Pro                     *
*      Version  2006      Bld 1004.US *
*      Proprietary Program of        *
*      Research Engineers, Intl.      *
*      Date=    JUL  8, 2011         *
*      Time=    15:14:49             *
*                                     *
*      USER ID: HPSA                 *
*****
```

```
1. STAAD PLANE AKERROOF RAFTERS WITH SOLAR PANELS
INPUT FILE: RafterFrameCollis1.STD
2. START JOB INFORMATION
3. ENGINEER DATE 29-JUN-11
4. END JOB INFORMATION
5. *
6. * ANALYSIS FILE RAFTERFRAMEAKER.STD
7. * HOUSE ROOF
8. *
9. * DESIGN BY J. MARX, P.E.
10. * ASCENT CONSULTING
11. *
12. * STAAD LOAD ANALYSIS - ROOF RAFTERS WITH SOLAR PANELS
13. *
14. * PROJECT: HOUSE RESIDENCE
15. *
16. * DESIGN CODE: IRC
17. *
18. *
19. INPUT WIDTH 79
20. *
21. UNIT FEET POUND
22. JOINT COORDINATES
23. 1 0 0 0; 2 3.63 1.69 0; 3 9.06 4.23 0; 4 13.3 6.2 0
24. MEMBER INCIDENCES
25. 1 1 2; 2 2 3; 3 3 4
26. DEFINE MATERIAL START
27. ISOTROPIC DFLR_SS_2X6
28. E 2.736E+008
29. POISSON 0.15
30. DENSITY 25
31. ALPHA 5.5E-006
32. END DEFINE MATERIAL
33. *
34. UNIT INCHES KIP
35. MEMBER PROPERTY AITC
36. 1 TO 3 TABLE ST DFLR_SS_2X6
37. *
38. CONSTANTS
39. *
40. MATERIAL DFLR_SS_2X6 ALL
```

AKERROOF RAFTERS WITH SOLAR PANELS

-- PAGE NO. 2

```

41. *
42. SUPPORTS
43. 1 PINNED
44. 4 FIXED BUT FX MZ
45. *
46. *****
47. *
48. UNIT FEET POUND
49. LOAD 1 DEAD
50. MEMBER LOAD
51. 1 TO 3 UNI GY -10
52. JOINT LOAD
53. 2 TO 4 FY -30
54. *
55. *****
56. *
57. LOAD 2 SNOW LOAD
58. MEMBER LOAD
59. 1 UNI GY -16
60. JOINT LOAD
61. 2 3 FY -58
62. 4 FY -217
63. *
64. *****
65. *
66. LOAD COMB 3 DL + SOLAR
67. 1 1.0 2 1.0
68. PERFORM ANALYSIS

```

P R O B L E M S T A T I S T I C S

```

-----
NUMBER OF JOINTS/MEMBER+ELEMENTS/SUPPORTS =      4/      3/      2
ORIGINAL/FINAL BAND-WIDTH=      1/      1/      6 DOF
TOTAL PRIMARY LOAD CASES =      2, TOTAL DEGREES OF FREEDOM =      9
SIZE OF STIFFNESS MATRIX =      1 DOUBLE KILO-WORDS
REQRD/AVAIL. DISK SPACE =      12.0/ 11768.8 MB

```

69. PRINT SUPPORT REACTION

SUPPORT REACTIONS -UNIT POUN FEET STRUCTURE TYPE = PLANE

JOINT	LOAD	FORCE-X	FORCE-Y	FORCE-Z	MOM-X	MOM-Y	MOM Z
1	1	0.00	104.75	0.00	0.00	0.00	0.00
	2	0.00	115.98	0.00	0.00	0.00	0.00
	3	0.00	220.74	0.00	0.00	0.00	0.00
4	1	0.00	131.99	0.00	0.00	0.00	0.00
	2	0.00	281.08	0.00	0.00	0.00	0.00
	3	0.00	413.07	0.00	0.00	0.00	0.00

***** END OF LATEST ANALYSIS RESULT *****

- 70. LOAD LIST 3
- 71. *
- 72. PARAMETER 1
- 73. CODE AITC
- 74. BEAM 1 ALL
- 75. CSF 1.3 ALL
- 76. CDT 1.15 ALL
- 77. CHECK CODE MEMB 2

STAAD.Pro CODE CHECKING - (AITC)

ALL UNITS ARE - POUN FEET (UNLESS OTHERWISE NOTED)

MEMBER	TABLE	RESULT/ FX	CRITICAL COND/ MY	RATIO/ MZ	LOADING/ LOCATION
--------	-------	---------------	----------------------	--------------	----------------------

2 ST DFLR_SS_2X6

PASS	CL.5.9.2	0.486	3
1.55 C	0.00	-648.84	2.4978

```

-----
| LEZ = 71.936 LEY = 71.936 LUZ = 71.936 LUY = 71.936 INCHES |
|-----|
| CD = 1.150 CMB = 1.000 CMT = 1.000 CMC = 1.000 CMP = 1.000 |
| CMV = 1.000 CME = 1.000 CFB = 1.000 CFT = 1.000 CFC = 1.000 |
| CFU = 1.000 CR = 1.000 CTT = 1.000 CC = 1.000 CF = 1.300 |
| CT = 1.000 CH = 1.000 CB = 1.000 CI = 1.000 CV = 0.000 |
| CLY = 1.000 CLZ = 0.977 CP = 0.170 c = 0.800 E' = 1900000.122 PSI |
|-----|
| ACTUAL STRESSES : (POUND INCH) |
| fc = 0.188 ft = 0.000 |
| f_cby = 0.000 f_cbz = 1029.494 |
| fv = 0.000 |
| ALLOWABLE STRESSES: (POUND INCH) |
| FC = 331.753 FT = 1150.000 |
| FCBY = 2117.513 FCBZ = 2117.513 |
| FCEY = 0.000 FCEZ = 4642.555 |
| FBE = 345.314 |
| FTB = 2167.750 F**TB = 2117.513 |
| FV = 0.000 SLENDERNESS = 50.000 |
|-----|

```

78. PRINT MEMBER FORCES ALL

MEMBER END FORCES STRUCTURE TYPE = PLANE

ALL UNITS ARE -- POUN FEET (LOCAL)

MEMBER	LOAD	JT	AXIAL	SHEAR-Y	SHEAR-Z	TORSION	MOM-Y	MOM-Z
1	3	1	93.17	200.11	0.00	0.00	0.00	0.00
		2	-49.23	-105.73	0.00	0.00	0.00	612.32
2	3	2	12.13	25.93	0.00	0.00	0.00	-612.32
		3	13.27	28.37	0.00	0.00	0.00	605.02
3	3	3	-50.28	-108.21	0.00	0.00	0.00	-605.02
		4	69.98	150.61	0.00	0.00	0.00	0.00

***** END OF LATEST ANALYSIS RESULT *****

79. FINISH

***** END OF THE STAAD.Pro RUN *****

**** DATE= JUL 8,2011 TIME= 15:14:49 ****

Quick Mount PV[®]

Your ***Solution*** in Mounting Products

Solar • H₂O • Conduit • HVAC • Custom

Composition Mount Specifications - 5/16" - PV -

Quick Mount PV[®] is an all-in-one waterproof flashing and mount to anchor photovoltaic racking systems, solar thermal panels, air conditioning units, satellite dishes, or anything you may need to secure to a new or existing roof. It is made in the USA of all aluminum and includes stainless steel hardware. It works with all standard racks, installs seamlessly and saves labor by not needing to cut away any roofing, will out live galvanized 2 to 1, and is a better low-profile mount.

Split Lock Washer SS 5/16" (Not a theft-prevention feature)

Fender Washer SS 5/16" x 1"

EPDM Rubber Washer 60 Durometer 5/16"

Sealing Washer SS 5/16"

Hanger Bolt SS 5/16" x 6"

1 1/4" Machine, 1 3/4" Spacer, 3" Lag

Mount & Flashing Aluminum

Mount 1 1/4" x 1 1/4" x 2 1/4" Beveled Block

Flashing .05" thick

For standard composition roofs:


flashing is 12" x 12"

mount is attached 3" off center



ESR-2835

(2) Hex Nuts SS 5/16"



Lag pull-out (withdrawal) capacities (lbs) in typical lumber:

	Specific gravity	Lag Bolt Specifications	
		5/16" shaft per 3" thread depth	5/16" shaft per 1" thread depth
Douglas Fir, Larch	.50	798	266
Douglas Fir, South	.46	705	235
Engelmann Spruce, Lodgepole Pine (MSR 1650 f & higher)	.46	705	235
Hem, Fir	.43	636	212
Hem, Fir. (North)	.46	705	235
Southern Pine	.55	921	307
Spruce, Pine, Fir	.42	615	205
Spruce, Pine, Fir (E of 2 million psi and higher grades of MSR and MEL)	.50	798	266

Sources: Uniform Building Code; American Wood Council

Notes: 1) Thread must be embedded in a rafter or other structural roof member.

2) Pull-out values incorporate a 1.6 safety factor recommended by the American Wood Council.

3) See IBC for required edge distances.

936 Detroit Ave Suite D, Concord, CA. 94518

Phone: (925) 687-6686 Fax: (925) 687-6689

Email: info@quickmountpv.com www.quickmountpv.com

July 14, 2011

Daniel Newman Jr., Construction Official
Brick Township Bldg. Dept.
401 Chambers Bridge Road
Brick, NJ 08723

Dear Mr. Newman:

We have been contracted to install a photovoltaic (solar-electric) system on the roof of the residence indicated below:

Diane Collis
128 John Street
Brick, NJ 08724
Block 1170.04, Lot 3

Although we have installed many of these systems throughout the state, we realize these systems are still relatively new in New Jersey. Therefore, we are submitting the following material in hopes it will satisfy the needs of your department:

1. The construction permit, building sub-code and electrical sub-code applications.
2. Two (2) copies of NJ Home Improvement Contractors License (No. 13VH02387400).
3. Two (2) copies of detailed specification sheets for the photovoltaic panels (generate DC electricity) and racking system (attach the panels to the roof).
4. Two (2) copies of a diagram showing the placement of the solar panels on the roof of the home plus positioning of the inverter and all necessary disconnect switches.
5. Two (2) signed and sealed copies of the engineer's structural analysis of the roof, including recommendations for its reinforcement, if required

Please call the numbers listed below or send an email if you have any questions, comments or suggestions on how to expedite getting the permits for this installation.

Thank you for your time and attention.

Sincerely

Christy Lorenz

Christy Lorenz, Administrative Assistant, 732-761-8841, Christy.lorenz@geogenix.com

Enc.

NOT AN
ELECTRICIAN'S
OR PLUMBER'S
LICENSE

State Of New Jersey
New Jersey Office of the Attorney General
Division of Consumer Affairs

THIS IS TO CERTIFY THAT THE
Division of Consumer Affairs

HAS REGISTERED

GeoGenix LLC
Thomas Matulewcz
79 E River Rd
Rumson NJ 07760

FOR PRACTICE IN NEW JERSEY AS A(N): Home Improvement Contractor

10/25/2010 TO 12/31/2011
VALID

Signature of Licensee/Registrant/Certificate Holder

13VH02387400
LICENSE/REGISTRATION/CERTIFICATION #

ACTING DIRECTOR

New Jersey Office of the Attorney General
Division of Consumer Affairs

THIS IS TO CERTIFY THAT THE
Division of Consumer Affairs
HAS REGISTERED
GeoGenix LLC
Home Improvement Contractor

NOT AN ELECTRICIAN'S OR PLUMBER'S LICENSE
10/25/2010 TO 12/31/2011

VALID

13VH02387400

License/Registration/Certificate #

SIGNATURE

ACTING DIRECTOR

PLEASE DETACH HERE
IF YOUR LICENSE/REGISTRATION/
CERTIFICATE ID CARD IS LOST
PLEASE NOTIFY:

Division of Consumer Affairs
P.O. Box 46016
Newark, NJ 07101

PLEASE DETACH HERE

NOT AN
ELECTRICIAN'S
OR PLUMBER'S
LICENSE

State Of New Jersey
New Jersey Office of the Attorney General
Division of Consumer Affairs


THIS IS TO CERTIFY THAT THE
Division of Consumer Affairs

HAS REGISTERED

GeoGenix LLC
Thomas Matulewcz
79 E River Rd
Rumson NJ 07760

FOR PRACTICE IN NEW JERSEY AS A(N): **Home Improvement Contractor**

10/25/2010 TO 12/31/2011
VALID


Signature of Licensee/Registrant/Certificate Holder

13VH02387400
LICENSE/REGISTRATION/CERTIFICATION #


ACTING DIRECTOR

New Jersey Office of the Attorney General
Division of Consumer Affairs

THIS IS TO CERTIFY THAT THE
Division of Consumer Affairs
HAS REGISTERED
GeoGenix LLC
Home Improvement Contractor

NOT AN ELECTRICIAN'S OR PLUMBER'S LICENSE
10/25/2010 TO 12/31/2011

VALID

SIGNATURE

13VH02387400

License/Registration/Certificate #

ACTING DIRECTOR

PLEASE DETACH HERE
IF YOUR LICENSE/REGISTRATION/
CERTIFICATE ID CARD IS LOST
PLEASE NOTIFY:

Division of Consumer Affairs
P.O. Box 46016
Newark, NJ 07101


PLEASE DETACH HERE

Trinasolar


TRINA TSM-PA05, 220W to 240W

I-V CURVES


I-V Curves of PV module TSM-230PA05



I-V Curves of module TSM-230PA05 at various cell temperatures



DIMENSIONS



Dimensions A*B*C

1650*992*46 (mm) | 64.96*39.05*1.81 (in.)

Installation Hole E*F

941*990 (mm) | 37.05*38.98 (in.)

Cable Length G

1000 (mm) | 39.37 (in.)

The company is not responsible for potential typing errors.



TRINA TSM-PA05, 220W to 240W

TYPICAL ELECTRICAL CHARACTERISTICS

Type	TSM-PA05	220	230	240
Max-Power	P _m (W)	220	230	240
Power Tolerance	(%)	±3	±3	±3
Max-Power Voltage	V _m (V)	29.8	30.0	30.6
Max-Power Current	I _m (A)	7.39	7.66	7.84
Open-Circuit Voltage	V _{oc} (V)	36.8	37.0	37.5
Short-Circuit Current	I _{sc} (A)	8.00	8.18	8.38
Max-System Voltage	(VDC)		600	
Cell Efficiency	η _c (%)	15.1	15.8	16.4
Module Efficiency	η _m (%)	13.4	14.1	14.7
Number, type and arrangement of cells		60 pcs. Multi-Crystalline Silicon (6x10)		
Cell Size		6" x 6" 156mm X 156mm		
No. of Bypass Diodes	(pcs.)		3	
Max. Series Fuse	(A)		14	
P _m Temperature Coefficient	(%/°C)		- 0.45	
I _{sc} Temperature Coefficient	(%/°C)		0.05	
V _{oc} Temperature Coefficient	(%/°C)		- 0.35	
NOCT- Nominal Operating Cell Temperature	(°C)		47±2	

MECHANICAL CHARACTERISTICS

Cable type, Diameter and Length	3.31mm ² (12AWG), UL Certified		
Type of Connector	Tyco		
Dimension A*B*C	1650*992*46 (mm) 64.96*39.05*1.81 (in.)		
Weight	19.5 Kg 43 lb		
No. of Draining Holes In Frame	8		
Glass, Type and Thickness	High Transmission, Low Iron, Tempered Glass 3.2 mm 0.12"		


PACKAGING CONFIGURATION

Packing Configuration	20 pcs./box
Quantity/Pallet	1 box / pallet
Loading Capacity	520 pcs/40ft or 120 pcs/20ft

ABSOLUTE RATINGS

Dielectric Insulation Voltage	(VDC)	3000 max.
Operating Temperature	(°C)	-40~+85
Storage Temperature	(°C)	-40~+85

*STC Conditions (1000W/m²; 1.5 AM and 25°C Cell temperature)



High Efficiency
Multicrystalline Solar Modules

STRENGTHS

• Tolerant to 8°
• Plus 3-4 Configuration
• Plug & Play Connectors
• High Transmission Low Iron
• Tempered Glass
• Can bear loads up to 5400
• Panels (IEC 61215 2004)

WARRANTY

Manufacturing 5 years
Power production 10-15 years
30-35 years

CERTIFICATIONS




Trinasolar


TRINA TSM-PA05, 220W to 240W

I-V CURVES


I-V Curves of PV module TSM-230PA05



I-V Curves of module TSM-230PA05 at various cell temperatures



DIMENSIONS



Dimensions A*B*C

1650*992*46 (mm) | 64.96*39.05*1.81 (in.)

Installation Hole E*F

941*990 (mm) | 37.05*38.98 (in.)

Cable Length G

1000 (mm) | 39.37 (in.)

*The company is not responsible for potential typing errors.



TRINA TSM-PA05, 220W to 240W

TYPICAL ELECTRICAL CHARACTERISTICS

Type	TSM-PA05	220	230	240
Max-Power	P _m (W)	220	230	240
Power Tolerance	(%)	±3	±3	±3
Max-Power Voltage	V _m (V)	29.8	30.0	30.6
Max-Power Current	I _m (A)	7.39	7.66	7.84
Open-Circuit Voltage	V _{oc} (V)	36.8	37.0	37.5
Short-Circuit Current	I _{sc} (A)	8.00	8.18	8.38
Max-System Voltage	(VDC)		600	
Cell Efficiency	η _c (%)	15.1	15.8	16.4
Module Efficiency	η _m (%)	13.4	14.1	14.7
Number, type and arrangement of cells		60 pcs. Multi-Crystalline Silicon (6x10)		
Cell Size		6" x 6" 156mm X 156mm		
No. of Bypass Diodes	(pcs.)		3	
Max. Series Fuse	(A)		14	
P _m Temperature Coefficient	(%/°C)		- 0.45	
I _{sc} Temperature Coefficient	(%/°C)		0.05	
V _{oc} Temperature Coefficient	(%/°C)		- 0.35	
NOCT- Nominal Operating Cell Temperature	(°C)		47±2	

MECHANICAL CHARACTERISTICS

Cable type, Diameter and Length	3.31mm ² (12AWG), UL Certified		
Type of Connector	Tyco		
Dimension A*B*C	1650*992*46 (mm) 64.96*39.05*1.81 (in.)		
Weight	19.5 Kg 43 lb		
No. of Draining Holes In Frame	8		
Glass, Type and Thickness	High Transmission, Low Iron, Tempered Glass 3.2 mm 0.12"		


PACKAGING CONFIGURATION

Packing Configuration	20 pcs./box
Quantity/Pallet	1 box / pallet
Loading Capacity	520 pcs/40ft or 120 pcs/20ft

ABSOLUTE RATINGS

Dielectric Insulation Voltage	(VDC)	3000 max.
Operating Temperature	(°C)	-40~+85
Storage Temperature	(°C)	-40~+85

*STC Conditions(1000W/m²; 1.5 AM and 25°C Cell temperature)



High Efficiency
Multicrystalline Solar Modules

STRENGTHS

- Tolerance ± 3%
- 3 Bus Bar Configuration
- Plug & Play Connectors
- High Transmission Low Iron Tempered Glass
- Can bear loads up to 5400 Pascals (14.66psi)

WARRANTY

Manufacturing 5 years
Power production 90% 10 years
80% 25 years

CERTIFICATIONS






DPW | SOLAR



PREFORMED LINE PRODUCTS



POWER RAIL™ P6 ASSEMBLY INSTRUCTIONS

**step-by-step
assembly and installation**

Power Rail™ P6

A Few words about these Assembly Instructions

These instructions:

- Do not include any information on the selection or installation of attaching hardware to be mounted to the roof substrate. For information on compatible attaching hardware see our publication titled “Power Rail Design Guidelines”.
- Begin after all roof mounted attaching hardware has been installed and secured to the roof substrate.
- Show the Power Rail Mounting System being installed on our “Power Rail PV Flash” roof attachment system.
- Are intended to be used by individuals with sufficient technical skills for the task. Knowledge and use of hand tools, measuring devices and torque values is also required.
- Within these instructions are various precautions in the forms of Notes, Cautions, and Warnings. These are to assist in the assembly process and/or to draw attention to the fact that certain assembly steps may be dangerous and could cause serious personal injury and/or damage to components. Following the step-by-step procedures and these precautions should minimize the risk of any personal injury or damage to components while making the installation not only safe but an efficient process.

WARNING:
Follow the
procedures and
precautions in
these instructions
carefully.


For questions on a specific installation please call us or e-mail us at:

Phone: 800-260-3792

Email: info@power-fab.com

Required Tools

- ☐ 1/2 inch wrench or socket for 5/16 inch module clamp hardware
- ☐ Torque wrench
- ☐ Ratchet wrench
- ☐ Ratchet extension bar
- ☐ Framing square
- ☐ Tape Measure



Item	Description	Qty
1	Universal End Clamp	2 per Power Rail
2	Mid Clamp, (5/16" x *) carriage bolt, flange nut	2 per 3/8" gap between modules
3	Splice Plate, set of (5/16" x 3/4") carriage bolt, flange nut	1 per rail joint
4	Power Rail P6	2 per Rail Set
5	L Foot, (5/16" x 3/4") carriage bolt, flange nut	Refer to Power Rail Design Guidelines
6	RAD Mid-Clamp, (5/16" x *) bolt, flange nut	2 per 3/8" gap between modules
7	RAD End-Clamp, (5/16" x *) bolt, flange nut	4 per Rail Set
8	End-Clamp, (5/16" x *) carriage bolt, flange nut	4 per Rail Set
* 2", 2 1/4" or 2 1/2" bolt. Length is dependent on depth of PV Module frame		
Notes: 1. Option to install Mid Clamp with carriage bolt or RAD Mid Clamp.		
2. Option to install Universal End Clamp, End Clamp with Carriage Bolt or RAD End Clamp.		

Power Rail P6 Parts Identification

NOTE:

L-feet can be attached directly to the roof substrate with the proper hardware. See Power Rail Design Guidelines for more information.

Step 1: Securing Attaching Hardware

The selection of attaching hardware is dependent on the roof substrate and site design conditions. Please consult the design manual for specifics. Instructions for attaching anchoring hardware to the roof or structure are available on an individual product basis.

- Place the L-foot onto the PV Flash hanger bolt aligning it to the slot of the compression block.
- Secure L-foot with 5/16" flat washer and hex nut. **Torque to 22-25 ft.-lbs.**




Figure 1-1: Attaching L-foot to the PV Flash

Step 2: Attach Power Rail to Roof Anchors

The Power Rail is secured to the L-feet using a 5/16" x 3/4" carriage bolt. Hardware will vary depending on design-specific requirements.

The Power Rail overhangs beyond the outermost L-foot. This overhang is referred to as "cantilever, or abbreviated as "C'ver"". The length of cantilever is dependent on several factors and unique to each installation and is determined by the system design. The distance between adjacent L-feet is referred to as "Span". The length of span is dependent on several factors and unique to each installation and is determined by the system design.

- Measure and mark the cantilever dimension supplied by design manual onto the Power Rail.




Figure 2-1: Cantilever Measurement and Marking

CAUTION:

Cantilever and span dimensions are a design specification. Consult the design manual to match these dimensions to site conditions. It's important to use the unique cantilever and span dimension specific to the install. Failure to do so could lead to excessive deflection and/or premature system failure.

NOTE:

If using carriage bolts, be certain to slide the appropriate quantity of bolts into the Power Rail before both ends of the Power Rail have been secured.

NOTE:

Before tightening any flange nuts first install all bolts and flange nuts into L-feet along entire length of Power Rail. If tightened, the adjacent bolts cannot be passed into downstream L-feet.

- B. Line up the mark with the center of the outermost L-foot.
- C. Starting at the outermost L-foot mounting position, insert one 5/16" x 3/4" bolt into the Power Rail.
- D. Holding the Power Rail, line-up and insert the 5/16" x 3/4" bolt into the L-foot and loosely secure with 5/16" flange nut. Do not tighten until all bolts have been positioned in the entire length of Power Rail and the bolts have been aligned and passed thru the L-feet and the flange nuts loosely started.
- E. Double-check that the cantilever mark is lined up with the center of the outermost L-foot. If needed, adjust its position to bring into alignment.
- F. Double-check the cantilever alignment before tightening Power Rail to L-feet. Tighten all flange nuts and **Torque to 22-25 ft.-lbs.**




Figure 2-2: Attaching Power Rail to L-foot

Step 3: Splicing Power Rail with Splice Plates

Splice Plates are used to butt-joint Power Rail sections and extend their length as needed. They are attached to the Power Rail using two 5/16" x 3/4" carriage bolts and flange nuts.

- A. Insert one 5/16" x 3/4" carriage bolt into the end of each Power Rail section to be spliced.
- B. Hold the two ends of Power Rail together.
- C. Position the Splice Plate onto the Power Rail and the two carriage bolts.
- D. Align the Splice Plate so that it's equally divided along the Power Rail butt-joint.
- E. Secure the Splice Plate to Power Rails with two 5/16" flange nuts. **Torque to 22-25 ft.-lbs.**




Figure 3-1: Splice Plate Installation

Step 3: Installing PV Modules to Power Rails with Module Clamps

WARNING:

This is a two person activity. In addition to working on a sloped rooftop PV Modules are heavy. One person should hold and align the modules while a second person secures modules with clamping hardware. Failure to do so could lead to serious personal injury and/or damaged components.

NOTE:

Hardware is dependent on particular features and system design therefore it may appear different from these instructions.

PV Modules are secured to the Power Rail using Mid Clamps and End Clamps, both use 5/16" bolts and flange nuts.

Start with an exterior PV Module. These instructions include three options of clamping hardware, they are "Universal End Clamp" (step B1), "Standard End Clamp" (step B2), or "RAD Clamps" (step B3).

- A. Place exterior PV Module on two Power Rails, centering it lengthwise. Use a square to square-up Module to Power Rails.
- B1. For use with "**Universal End Clamps**": Position Universal Clamp underneath module with notches facing the outside edge of the module, and rail centered between 'forks' of the clamp. Slide clamp notches towards module flange until the flange bottoms out in the notches. Tighten 5/16" bolt on bottom of universal end clamp. **Torque to 75-80 in.-lbs.** Repeat for both end clamps.




Figure 3-1: Installing PV Modules using Universal End Clamp

- B2. For use with "**Standard End Clamps**". Insert one 5/16" x 2, 2 1/4 or 2 1/2" bolt into the top slot of the Power Rail. Push the bolt until flush with edge of module frame. Position end clamp with hole facing upwards and center hole over bolt. Seat end clamp over bolt flush with module frame. Thread 5/16" flange nut onto clamp and tighten. When desired alignment is obtained, tighten the nut and end clamp. **Torque End Clamps to 75-80 in.-lbs.** (figure 3-2)




Figure 3-2: Installing PV Modules using Standard End-Clamp

B3. For use with “**RAD Hardware**” the process is much the same as in step B2 above, the difference is RAD bolts can be inserted anywhere along the run of Power Rail, not just the ends of the rail as shown in Figure 3-2 above.

Although this step demonstrates installing a *Mid-Clamp* the procedure for an *End-Clamp* is much the same when using RAD hardware.

Insert RAD bolt into Power Rail and rotate 90-degrees to lock into rail. Install module clamp (End or Mid-Clamp) onto bolt by aligning the flat portion of the clamp with that of the bolt. Thread 5/16" flange nut onto clamp and tighten. When desired alignment is obtained, tighten the nut and end clamp. **Torque End Clamps to 75-80 in.-lbs.**




Figure 3-3: Installing PV Modules using RAD Hardware

NOTE:

If using standard 5/16" carriage bolts for Mid Clamps they must be inserted into Power Rail before installing interior PV Modules.

If using RAD hardware they can be inserted anytime at any position along the Power Rail.

Installing interior PV Modules.

- A. Before placing an interior PV Module onto the Power Rails, first insert 5/16" x 2, 2 1/4, or 2 1/2 inch carriage bolts (bolt length is dependent on depth of PV Module frame) into the Module Rail, sliding the bolts inward adjacent to the previously installed exterior PV Module.
- B. Slide the mid clamp fasteners to be flush with the edge of the installed module frame, opposite the end clamps.




Figure 3-4: Inserting Mid Clamp Hardware into Power Rail

(continued on next page)

WARNING:

This is a two person activity. In addition to working on a sloped rooftop PV Modules are heavy. One person should hold and align the modules while a second person secures modules with clamping hardware. Failure to do so could lead to serious personal injury and/or damaged components.

WARNING:

Be certain that all Flange Nuts on End and Mid Clamps are tightened and torque to the stated values. Failure to do so could lead to serious personal injury and/or damaged components and property.

- C. Place the interior PV Module onto the Power Rails, aligning it with the previously installed exterior PV Module. Positioning it adjacent to 5/16" bolts and the previously installed exterior PV Module.
- D. Use a square to square-up Module to Power Rails.
- E. Install one Mid Clamp on each of the 5/16" bolts that are between each of the interior PV Modules. Be sure that the tabs of the Mid Clamp rests between the two Modules. Secure each of the Mid Clamps with a 5/16" flange nut. **Torque Mid Clamps to 80-85 in.-lbs.**





Figure 3-5: Inserting Mid Clamps



4000-B Vassar Drive NE
Albuquerque, New Mexico 87107
USA

Telephone: 800.260.3792
Fax: 505.889.3548
Web Site: www.DPWSolar.com
E-mail: info@power-fab.com


© 2010 Preformed Line Products
PCN 090310-1
Version 1, Rev C



DPW | SOLAR



PP PREFORMED LINE PRODUCTS



POWER RAIL™ P6 ASSEMBLY INSTRUCTIONS

step-by-step
assembly and installation

Power Rail™ P6

A Few words about these Assembly Instructions

These instructions:

- Do not include any information on the selection or installation of attaching hardware to be mounted to the roof substrate. For information on compatible attaching hardware see our publication titled "Power Rail Design Guidelines".
- Begin after all roof mounted attaching hardware has been installed and secured to the roof substrate.
- Show the Power Rail Mounting System being installed on our "Power Rail PV Flash" roof attachment system.
- Are intended to be used by individuals with sufficient technical skills for the task. Knowledge and use of hand tools, measuring devices and torque values is also required.
- Within these instructions are various precautions in the forms of Notes, Cautions, and Warnings. These are to assist in the assembly process and/or to draw attention to the fact that certain assembly steps may be dangerous and could cause serious personal injury and/or damage to components. Following the step-by-step procedures and these precautions should minimize the risk of any personal injury or damage to components while making the installation not only safe but an efficient process.

WARNING:
Follow the
procedures and
precautions in
these instructions
carefully.


For questions on a specific installation please call us or e-mail us at:

Phone: 800-260-3792

Email: info@power-fab.com

Required Tools ☒

- ☐ 1/2 inch wrench or socket for 5/16 inch module clamp hardware
- ☐ Torque wrench
- ☐ Ratchet wrench
- ☐ Ratchet extension bar
- ☐ Framing square
- ☐ Tape Measure



Item	Description	Qty
1	Universal End Clamp	2 per Power Rail
2	Mid Clamp, (5/16" x *) carriage bolt, flange nut	2 per 3/8" gap between modules
3	Splice Plate, set of (5/16" x 3/4") carriage bolt, flange nut	1 per rail joint
4	Power Rail P6	2 per Rail Set
5	L Foot, (5/16" x 3/4") carriage bolt, flange nut	Refer to Power Rail Design Guidelines
6	RAD Mid-Clamp, (5/16" x *) bolt, flange nut	2 per 3/8" gap between modules
7	RAD End-Clamp, (5/16" x *) bolt, flange nut	4 per Rail Set
8	End-Clamp, (5/16" x *) carriage bolt, flange nut	4 per Rail Set
* 2", 2 1/4" or 2 1/2" bolt. Length is dependent on depth of PV Module frame		
Notes: 1. Option to install Mid Clamp with carriage bolt or RAD Mid Clamp.		
2. Option to install Universal End Clamp, End Clamp with Carriage Bolt or RAD End Clamp.		

Power Rail P6 Parts Identification

NOTE:

L-feet can be attached directly to the roof substrate with the proper hardware. See Power Rail Design Guidelines for more information.

Step 1: Securing Attaching Hardware

The selection of attaching hardware is dependent on the roof substrate and site design conditions. Please consult the design manual for specifics. Instructions for attaching anchoring hardware to the roof or structure are available on an individual product basis.

- A. Place the L-foot onto the PV Flash hanger bolt aligning it to the slot of the compression block.
- B. Secure L-foot with 5/16" flat washer and hex nut. **Torque to 22-25 ft.-lbs.**




Figure 1-1: Attaching L-foot to the PV Flash

Step 2: Attach Power Rail to Roof Anchors

The Power Rail is secured to the L-feet using a 5/16" x 3/4" carriage bolt. Hardware will vary depending on design-specific requirements.

The Power Rail overhangs beyond the outermost L-foot. This overhang is referred to as "cantilever, or abbreviated as "C'ver"". The length of cantilever is dependent on several factors and unique to each installation and is determined by the system design. The distance between adjacent L-feet is referred to as "Span". The length of span is dependent on several factors and unique to each installation and is determined by the system design.

- A. Measure and mark the cantilever dimension supplied by design manual onto the Power Rail.




Figure 2-1: Cantilever Measurement and Marking

CAUTION:

Cantilever and span dimensions are a design specification. Consult the design manual to match these dimensions to site conditions. It's important to use the unique cantilever and span dimension specific to the install. Failure to do so could lead to excessive deflection and/or premature system failure.

NOTE:

If using carriage bolts, be certain to slide the appropriate quantity of bolts into the Power Rail before both ends of the Power Rail have been secured.

NOTE:

Before tightening any flange nuts first install all bolts and flange nuts into L-feet along entire length of Power Rail. If tightened, the adjacent bolts cannot be passed into downstream L-feet.

- B. Line up the mark with the center of the outermost L-foot.
- C. Starting at the outermost L-foot mounting position, insert one 5/16" x 3/4" bolt into the Power Rail.
- D. Holding the Power Rail, line-up and insert the 5/16" x 3/4" bolt into the L-foot and loosely secure with 5/16" flange nut. Do not tighten until all bolts have been positioned in the entire length of Power Rail and the bolts have been aligned and passed thru the L-feet and the flange nuts loosely started.
- E. Double-check that the cantilever mark is lined up with the center of the outermost L-foot. If needed, adjust its position to bring into alignment.
- F. Double-check the cantilever alignment before tightening Power Rail to L-feet. Tighten all flange nuts and **Torque to 22-25 ft.-lbs.**




Figure 2-2: Attaching Power Rail to L-foot

Step 3: Splicing Power Rail with Splice Plates

Splice Plates are used to butt-joint Power Rail sections and extend their length as needed. They are attached to the Power Rail using two 5/16" x 3/4" carriage bolts and flange nuts.

- A. Insert one 5/16" x 3/4" carriage bolt into the end of each Power Rail section to be spliced.
- B. Hold the two ends of Power Rail together.
- C. Position the Splice Plate onto the Power Rail and the two carriage bolts.
- D. Align the Splice Plate so that it's equally divided along the Power Rail butt-joint.
- E. Secure the Splice Plate to Power Rails with two 5/16" flange nuts. **Torque to 22-25 ft.-lbs.**




Figure 3-1: Splice Plate Installation

Step 3: Installing PV Modules to Power Rails with Module Clamps

WARNING:

This is a two person activity. In addition to working on a sloped rooftop PV Modules are heavy. One person should hold and align the modules while a second person secures modules with clamping hardware. Failure to do so could lead to serious personal injury and/or damaged components.

NOTE:

Hardware is dependent on particular features and system design therefore it may appear different from these instructions.

PV Modules are secured to the Power Rail using Mid Clamps and End Clamps, both use 5/16" bolts and flange nuts.

Start with an exterior PV Module. These instructions include three options of clamping hardware, they are "Universal End Clamp" (step B1), "Standard End Clamp" (step B2), or "RAD Clamps" (step B3).

- A. Place exterior PV Module on two Power Rails, centering it lengthwise. Use a square to square-up Module to Power Rails.
- B1. For use with "**Universal End Clamps**": Position Universal Clamp underneath module with notches facing the outside edge of the module, and rail centered between 'forks' of the clamp. Slide clamp notches towards module flange until the flange bottoms out in the notches. Tighten 5/16" bolt on bottom of universal end clamp. **Torque to 75-80 in.-lbs.** Repeat for both end clamps.




Figure 3-1: Installing PV Modules using Universal End Clamp

- B2. For use with "**Standard End Clamps**". Insert one 5/16" x 2, 2 1/4 or 2 1/2" bolt into the top slot of the Power Rail. Push the bolt until flush with edge of module frame. Position end clamp with hole facing upwards and center hole over bolt. Seat end clamp over bolt flush with module frame. Thread 5/16" flange nut onto clamp and tighten. When desired alignment is obtained, tighten the nut and end clamp. **Torque End Clamps to 75-80 in.-lbs.** (figure 3-2)




Figure 3-2: Installing PV Modules using Standard End-Clamp

B3. For use with “**RAD Hardware**” the process is much the same as in step B2 above, the difference is RAD bolts can be inserted anywhere along the run of Power Rail, not just the ends of the rail as shown in Figure 3-2 above.

Although this step demonstrates installing a *Mid-Clamp* the procedure for an *End-Clamp* is much the same when using RAD hardware.

Insert RAD bolt into Power Rail and rotate 90-degrees to lock into rail. Install module clamp (End or Mid-Clamp) onto bolt by aligning the flat portion of the clamp with that of the bolt. Thread 5/16" flange nut onto clamp and tighten. When desired alignment is obtained, tighten the nut and end clamp. **Torque End Clamps to 75-80 in.-lbs.**




Figure 3-3: Installing PV Modules using RAD Hardware

NOTE:

If using standard 5/16" carriage bolts for Mid Clamps they must be inserted into Power Rail before installing interior PV Modules.

If using RAD hardware they can be inserted anytime at any position along the Power Rail.

Installing interior PV Modules.

- A. Before placing an interior PV Module onto the Power Rails, first insert 5/16" x 2, 2 1/4, or 2 1/2 inch carriage bolts (bolt length is dependent on depth of PV Module frame) into the Module Rail, sliding the bolts inward adjacent to the previously installed exterior PV Module.
- B. Slide the mid clamp fasteners to be flush with the edge of the installed module frame, opposite the end clamps.




Figure 3-4: Inserting Mid Clamp Hardware into Power Rail

(continued on next page)

WARNING:

This is a two person activity. In addition to working on a sloped rooftop PV Modules are heavy. One person should hold and align the modules while a second person secures modules with clamping hardware. Failure to do so could lead to serious personal injury and/or damaged components.

WARNING:

Be certain that all Flange Nuts on End and Mid Clamps are tightened and torque to the stated values. Failure to do so could lead to serious personal injury and/or damaged components and property.

- C. Place the interior PV Module onto the Power Rails, aligning it with the previously installed exterior PV Module. Positioning it adjacent to 5/16" bolts and the previously installed exterior PV Module.
- D. Use a square to square-up Module to Power Rails.
- E. Install one Mid Clamp on each of the 5/16" bolts that are between each of the interior PV Modules. Be sure that the tabs of the Mid Clamp rests between the two Modules. Secure each of the Mid Clamps with a 5/16" flange nut. **Torque Mid Clamps to 80-85 in.-lbs.**





Figure 3-5: Inserting Mid Clamps



4000-B Vassar Drive NE
Albuquerque, New Mexico 87107
USA

Telephone: 800.260.3792
Fax: 505.889.3548
Web Site: www.DPWSolar.com
E-mail: info@power-fab.com

© 2010 Preformed Line Products
PCN 090310-1
Version 1, Rev C



GeoGenix LLC

Leaders in Energy-Saving
Design and Construction

GeoGenix, LLC

79 East River Road

Rumson, NJ 07760

(T) 732.895.9550

(F) 801.382.0751

STRUCTURAL ENGINEER:

Ascent Consulting

James A. Marx, P.E.

10 High Mountain Road

Ringwood, NJ 07456

(T) 973.557.6080

CUSTOMER:

Diane Collis Residence

128 John Street

Brick, NJ, 08724

UTILITY COMPANY:

JOPL

UTILITY ACCOUNT #:

10 00 59 9522 6 5

SHEET:

PHOTOVOLTAIC SYSTEM

Solar Panel

Array Layout

PROJECT #:


DATE: 7/6/11

DRAWN BY: GLK

REV #:

SCALE: As Noted

PV-1



Exist. Utility
Electric Meter
Point of Service

Inverter outside,
w/ built-in
disconnects

Roof 1 (13" higher than Roof 2)

Roof 2

Gutter

Gutter

SOLAR PANEL ARRAY

Roof Pitch = $25^{\circ} \pm$


(20) TrinaSolar TSM PA05 230w panels (4.6 kW total)

INVERTER

(1) SB-4000us W/ (2) Strings of (10) Panels

RACKING:

DPW Power Rail System



SOLAR ARRAY
158°



NOTES:

- See specifications for additional information.
- See electrical One-line drawing (PV-2) for wiring connections.
- North arrow and Array orientation based on "True" direction (magnetic compass reading minus Magnetic Declination of 11 degrees equals true Array orientation (Azimuth) of 158 degrees.)

1 PLAN
PV-1 N.T.S.

LEGEND:



The Experts to Trust

Brick Twp. Building Dept.
401 Chambers Bridge Road
Brick, NJ 08723

Dear Building Department:

Please find a check for \$312.00 (che
photovoltaic (solar-electric) system c
NJ 08724 (Block 1170.04, Lot 3).

Please mail the Permit Approval "pa

Should you have any questions, ple
application so quickly, it is very muc

KUMON
MATH. READING

Please ret
permits w/ enclosure
envelope. Thank you! ☺

Kumon of Howell
4242 Route 9 South • Howell, New Jersey 07731
732-889-4385 • www.kumonhowellnj.com

GeoGenix, LLC

Brick Township

Date 7/22/2011
Type Bill
Reference Collis Permit Fee

7753

7/22/2011

Discount

Balance Due

312.00

Original Amt.

312.00

Check Amount

Payment

312.00

312.00

GeoGenix TD Bank C Collis Permit Fee

312.00

Route 18
08857

ion of a
Brick,

velope.

this

UNIVERSITY CONSTRUCTION PERMIT

Date Issued

Permit #

IDENTIFICATION Block 1170.04 Lot 3 Qualification Code _____
Work Site Location 128 John St. Contractor GeoGenix, LLC
Brix, NJ 08724 Address 8998 Route 18
Owner in Fee Diane Collis Old Bridge, NJ 08857
Address Same as above Tel. (732) 761-8841
_____ Lic. No. or Bldrs. Reg. No. I3VH02387400
Tel. _____

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT ☒ OTHER Solar Panels
(Subchapter 8 only)

DESCRIPTION OF WORK:

Install 20 solar electric panels on roof.

NOTE: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$ 21,850-

Construction Official

Date

U.C.C. F170 (rev. 01/04)

PAYMENTS (Office Use Only)

Building _____
Electrical _____
Plumbing _____
Fire Protection _____
Elevator Devices _____
Other _____
DCA State Permit Fee _____
Cert. of Occupancy _____
Other _____
Total _____
Check No. _____
Cash _____
Collected by _____

(see reverse side)

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval given.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in the case of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. Utility services, including septic.
4. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.

☐ Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

CONSTRUCTION PERMIT

Date Issued _____
Permit # _____

IDENTIFICATION Block 1170.04 Lot 3 Qualification Code _____
 Work Site Location 128 Jona St. Contractor GeoGenix, LLC
Briev, NJ 08724 Address 8998 Route 18
 Owner in Fee Diane Collins Old Bridge, NJ 08857
 Address Same as above Tel. (732) 761-8841
 _____ Lic. No. or Bldrs. Reg. No. 13VH02387400
 Tel. _____

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT ☒ OTHER Solar Panels
 (Subchapter 8 only)

DESCRIPTION OF WORK:

Install 20 solar electric panels on roof.

NOTE: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$ 21,850

Construction Official _____

Date _____

U.C.C. F170 (rev. 01/04)

PAYMENTS (Office Use Only)	
Building	_____
Electrical	_____
Plumbing	_____
Fire Protection	_____
Elevator Devices	_____
Other	_____
DCA State Permit Fee	_____
Cert. of Occupancy	_____
Other	_____
Total	_____
Check No.	_____
Cash	_____
Collected by	_____

(see reverse side)

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval given.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in the case of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. Utility services, including septic.
4. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.

☐ Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

CONSTRUCTION **PERMIT**

Date Issued _____

Permit # _____

IDENTIFICATION Block 1170.04 Lot 3 Qualification Code _____
 Work Site Location 145 TOWNSHIP ST. Contractor GeoGenix, LLC
DOCK 116 377241 Address 8998 Route 18
 Owner in Fee Dave Gouge Old Bridge, NJ 08857
 Address above Tel. (732) 761-8841
 _____ Lic. No. or Bldrs. Reg. No. I3VH02387400

Allowing work:

- ☒ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT ☒ OTHER Solar Panels
 (Subchapter 8 only)

DESCRIPTION OF WORK:

Install 20 solar electric panels on roof.

NOTE: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$ 21,850

Construction Official _____

Date _____

U.C.C. F170 (rev. 01/04)

PAYMENTS (Office Use Only)

Building _____
 Electrical _____
 Plumbing _____
 Fire Protection _____
 Elevator Devices _____
 Other _____
 DCA State Permit Fee _____
 Cert. of Occupancy _____
 Other _____
 Total _____
 Check No. _____
 Cash _____
 Collected by _____

(see reverse side)

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval given.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in the case of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. Utility services, including septic.
4. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.

☐ Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

UNIFORM CONSTRUCTION PERMIT

Date Issued

Permit #

IDENTIFICATION Block 1170 Lot 3 Qualification Code _____
Work Site Location _____ Contractor GeoGenix, LLC
Address 8998 Route 18
Owner in Fee _____ Old Bridge, NJ 08857
Address _____ Tel. (732) 761-8841
Tel. (732) 761-8841 Lic. No. or Bldrs. Reg. No. 13VH02387400

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT ☒ OTHER Solar Panels
(Subchapter 8 only)

DESCRIPTION OF WORK:

NOTE: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$ _____

Construction Official _____

Date _____

U.C.C. F170 (rev. 01/04)

PAYMENTS (Office Use Only)

Building _____
Electrical _____
Plumbing _____
Fire Protection _____
Elevator Devices _____
Other _____
DCA State Permit Fee _____
Cert. of Occupancy _____
Other _____
Total _____
Check No. _____
Cash _____
Collected by _____

(see reverse side)

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval given.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in the case of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. Utility services, including septic.
4. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.

☐ Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier-Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier-Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.