

LOCK 1170 LOT E QUALIFICATION CODE ADDRESS (SITE) 1722 NJ STATE RT 88 PERMIT NO. 09-0158



CONSTRUCTION PERMIT APPLICATION

Applicant Completes: Sections I, II, III (optional), IV, VI, and VII

I. IDENTIFICATION

1. Proposed Work Site at: 1722 NJ STATE ROUTE 88, BRICK, NJ

2. Name of Owner in Fee: THE HOME DEPOT

Tel. (732) 926-2626 e-mail BRUCE_TALVY@HOMEDEPOT.COM

Address 2026 HAMILTON BLVD., S. PLAINFIELD, NJ 07080

3. Ownership in Fee: Public ☒ Private ☒

4. Principal Contractor: 848-209-1838 Tel. () e-mail ()

License No. OR, if new home, Builder Reg. No. Exp. Date

Home Improvement Contractor Registration No. or Exemption Reason (if applicable):

Federal Emp. ID No. FAX: ()

5. Architect or Engineer: CASCO Suite 201 Contact: PETER PUSKULOTIAN

Address 1090 KING GEORGE POST RD, EDISON, NJ e-mail 08837

Tel. (732) 661-1400 FAX: (732) 661-1399

6. Responsible Person in Charge once Work has Begun: BRUCE TALVY

Tel. (732) 926-2626 FAX: (732) 926-2972

V. FEE SUMMARY (for office use only)

		Update	Update
1. Building	\$ 65943		
2. Electrical	13135		
3. Plumbing	2200		
4. Fire Protection	1800	705	225
5. Elevator Devices			
6. Subtotal			
7. Less 20% for State Plan Review	\$		
8. Subtotal	\$ 8074	14	
9. State Permit Surcharge Fee			
10. Subtotal	\$ 35		
11. Cert. of Occupancy	60		
12. Other	137		
13. TOTAL	\$ 91232	779	225

VI. BUILDING/SITE CHARACTERISTICS

		(office use only)
1. Number of Stories	(1) ONE	
2. Height of Structure	36'-0"	
3. Area - Largest Floor	127,025	21,309
4. New Building Area	21,309	
5. Volume of New Structure	240,305	100 PSF
6. Max. Live Load		3459
7. Max. Occupancy Load	4,070 PERSONS	
8. If Industrialized Building: State Approved	HUD	
9. Total Land Area Disturbed		
10. Flood Hazard Zone		X
11. Base Flood Elevation		NA
12. Wetlands	yes no	

IIa. PROPOSED WORK

- ☐ Minor Work ☐ New Building ☒ Addition ☐ Demolition
- ☐ Repair ☐ Alteration ☐ Renovation ☒ Reconstruction
- ☐ Asbestos Abat. -Subch. 8 ☐ Lead Hazard Abatement ☐ Radon Remediation ☐ Annual Permit

IIb. SUBCODES

(Check all that apply)

- ☒ Building
- ☒ Electrical
- ☒ Plumbing
- ☒ Fire Protection
- ☐ Elev

TOTAL COST

FOR OFFICE USE ONLY (Optional)

Est. Cost	Plans Rec'd by	Date Rec'd	Rejection Date	Approval Date	Re-viewer	Resubmission Dates	Re-viewer
4,350,000	2	2	1/16/09 KA			1/28/09 4/24/09 KA	KA
1,200,000				12/5/08 KM	3-17-9	U/D	28
275,000				12/22/08 AB	4-23-9	U/D	28
159,000				11-7-08 DS	6-16-9	212	28
	2	11/7/08	11/7/08		11/4/08		11/4/08

III. PLAN REVIEW (optional)

DO YOU WANT:

1. ☐ Partial Releases
2. ☐ Prototype Processing

IV. DOES OR WILL YOUR BUILDING CONTAIN ANY OF THE FOLLOWING?

1. ☐ Elevators/Escalators/Lifts/
Dumbwaiters/Moving Walks
2. ☐ High Pressure Boilers
3. ☐ Pressure Vessels
4. ☐ Refrigeration Systems
5. ☐ Cross-Connections/Backflow Preventers
6. ☐ Hazardous Uses/Places of Assembly
7. ☒ Sprinklers
8. ☐ Smoke Control Systems in Open Wells
9. ☐ Underground Storage Tanks
10. ☐ Swimming Pools, Spas and Hot Tubs
11. ☐ LPGas Tanks

VII. DESCRIPTION OF BUILDING USE

A. RESIDENTIAL (primary use)

1. State Specific Use:
2. Use Group, Proposed:
3. Change in Use Group, Indicate Present:
4. No. of dwelling units: Total Units Income-restricted
- | Gained, Sale | |
|----------------|--|
| Gained, Rental | |
| Lost, Sale | |
| Lost, Rental | |

B. NON-RESIDENTIAL (primary use)

1. State Specific Use: RETAIL
2. Use Group, Proposed: M
3. Change in Use Group, Indicate Present: M
4. MIXED USE -List secondary use(s): B, G, I
5. Construct. Classification: Present 11-B Proposed 11-B

CERTIFICATION IN LIEU OF OATH

I. OWNER SECTION (to be completed if the applicant is the owner in fee)

I hereby certify that I am the owner in fee of the property listed on Page 1.

Mark the following applicable boxes:

- A. ☐ I further certify that a new home (private residence) will be constructed on this property for my own use and occupancy. This dwelling is to be occupied by myself and is not to be used for any purpose other than single family residential use. I attest that all construction, plumbing, or electrical work will be done, in whole or in part, by me or by subcontractors under my supervision, in accordance with all applicable laws; and, I further acknowledge that said new home is not covered under the New Home Warranty and Builders Registration Act (N.J.S.A. 46:3B-1 et seq.) and that such fact shall be disclosed to any person purchasing this property within ten years of the date of issuance of a certificate of occupancy.

I UNDERSTAND THAT IN MARKING BOX A, I ACKNOWLEDGE THAT I AM ASSUMING RESPONSIBILITY FOR THE WORK DONE ON SAID PROPERTY, THE CONDITION OF THE PROPERTY PRIOR TO, DURING, AND AFTER ANY WORK PERFORMED, AND FOR THE PERFORMANCE OF THE SUBCONTRACTORS I HIRE, EMPLOY, OR OTHERWISE CONTRACT OR WITH WHOM I MAKE AGREEMENTS TO PERFORM WORK. I AM VOLUNTARILY AND KNOWINGLY ASSUMING THIS RESPONSIBILITY.

- B. ☐ I further certify the following as required by the New Jersey Uniform Construction Code, N.J.A.C. 5:23-2.15(e)1.ix:

I personally prepared the plans submitted for: 1) the new home referred to in A.; or, 2) an addition, alteration, renovation, or repair to an existing single family residence owned and occupied by myself and located on the property listed on Page 1; or, 3) a new structure that will be physically separate from, but that will be deemed part of, an existing single family residence that is owned and occupied by myself and located on the property listed on Page 1.

- C. ☐ I further certify that I will perform or supervise the following work:

C.1. ☐ Building C.2. ☐ Fire Protection

I further certify that I will perform the following work:

C.3. ☐ Electrical C.4. ☐ Plumbing

- D. ☒ I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I understand that if any of the above statements are willfully false, I am subject to punishment.

Signature

John R. Patten

Date

9.26.08

II. AGENT SECTION (to be completed if the applicant is not the owner in fee)

I hereby certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(d): the proposed work is authorized by the owner in fee; and I have been authorized by the owner in fee to make this application as his agent.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I understand that if any of the above statements are willfully false, I am subject to punishment.

☐ Check if contractor.

* Agent Name JOHN BINOCCHIO / CACCIO
Address 1090 KING GEORGE POST RD.
EDISON, NJ 08837
Telephone (732) 661-1400
Signature *John Binocchio*

III. ☐ LEAD HAZARD ABATEMENT: Include Homeowner or Building Owner Affidavit as per N.J.A.C. 5:17.

OFFICE DATE RECEIVED: _____

VII. PRIOR APPROVALS CHECKLIST (office use only)	LOCAL APPROVAL		COUNTY APPROVAL		REGIONAL APPROVAL		STATE APPROVAL		COMMENTS
	Prelimin. Initial	Final Date	Prelimin. Initial	Final Date	Prelimin. Initial	Final Date	Prelimin. Initial	Final Date	
☐ Zoning Officer									
☐ Planning Board									
☐ Zoning Board									
☐ Sewer Authority									
☐ Water Authority									
☐ Police Department									
☐ Health Department									
☐ Soil Conservation									
☐ N.J. Department of Community Affairs									
☐ N.J. Department of Transportation									
☐ N.J. Department of Environmental Protection									
☐ Utility Dig No.									
☐									
☐									

IX. SUBCODES AND SPECIAL REGULATIONS APPLICABLE (office use only—optional)

Name of Code & Edition	Name of Code & Edition	Other
Building _____	Energy _____	
Electrical _____	Barrier Free _____	
Plumbing _____	Flood Hazard _____	
Fire Protection _____	As Built Elevation Cert. _____	
Mechanical _____	Other _____	

X. CERTIFICATES ISSUED (office use only)

	DATE ISSUED	DATE EXPIRED	DATE REISSUED	DATE EXPIRED
☐ Temporary Certificate of Occupancy	No. _____	_____	_____	_____
☐ Temporary Certificate of Compliance	No. _____	_____	_____	_____
☐ Continued Certificate of Occupancy	No. _____	_____	_____	_____
☐ Certificate of Compliance	No. _____	_____	_____	_____
☐ Certificate of Occupancy	No. _____	_____	_____	_____
☐ Certificate of Approval	No. _____	_____	_____	_____
☐ Lead Abatement Clearance Certificate	No. _____	_____	_____	_____



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723

Date Issued 07/08/2009
Control Number C-08-004682
Permit Number 09-0158
Permit Issue Date 01/30/2009
Certificate Number 09-0158

Certificate

Construction Code Division

(Temporary Certificate of Occupancy)

Identification

Work Site Location: 1722 ROUTE 88 Brick Township, NJ Block: 1170 Lot: 5 Qual: _____
Owner in Fee: THE HOME DEPOT
Owner Address: 3096 HAMILTON BLVD S PLAINFIELD NJ 07080
Telephone: (732) 926-3626
Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Telephone: (732) 661-1400 Fax: _____
License Number or Builders Registration Number: _____ Federal Emp. Number: _____

Home Warranty Number: _____

Type of Warranty Plan: ☐ State ☐ Private

Use Group: M Construction Classification: Type I

Maximum Live Load: 0 Maximum Occupancy Load: 0

Description of Work/Use: ALTERATION - -COMMERCIAL CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

Certificate Comments:

☐ **Certificate of Occupancy**

This serves notice that said building or structure has been constructed in accordance with the New Jersey Uniform Construction Code and is approved for occupancy.

☐ **Certificate of Approval**

This serves notice that the work completed has been constructed or installed in accordance with the New Jersey Uniform Construction Code and is approved. If the permit was issued for minor work, this certificate was based upon what was visible at the time of inspection.

☐ **Certificate of Continued Occupancy**

This serves notice that based on a general inspection of the visible parts of the building there are no imminent hazards and the building is approved for continued occupancy.

☐ **Temporary Certificate of Compliance**

The following conditions must be met no later than or the owner will be subject to fine or order to vacate:
This certificate has an expiration date of:
Conditions to be met:

☐ **Certificate of Clearance - Lead Abatement 5:17**

This serves notice that based on written certification, lead abatement was performed as per NJACS:17 to the following extent.

- ☐ Total removal of lead-based paint hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Clearance - Asbestos Abatement**

This serves notice that based on written certification, asbestos abatement was performed to the following extent.

- ☐ Total removal of asbestos hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Compliance**


This serves notice that said potentially hazardous equipment has been installed and/or maintained in accordance with the New Jersey Uniform Construction Code and is approved for use until

☒ **Temporary Certificate of Occupancy**

The following conditions must be met no later than: 08/20/2009
or the owner will be subject to fine or order to vacate:

This certificate has an expiration date of: 08/20/2009
Conditions to be met:

 For Stocking Shelves and Merchandising Only


Construction Official

ADD FOR
DN

Date Printed: 07/08/2009

U.C.C. F260 (rev. 08/05)

See
Conditions

Fee: \$0.00
Check Number: _____
Collected By: _____



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723

Date Issued 08/14/2009
Control Number C-08-004682
Permit Number 09-0158
Permit Issue Date 01/30/2009
Certificate Number 09-0158

Certificate

Construction Code Division
(Temporary Certificate of Occupancy)

Identification

Work Site Location: 1722 ROUTE 88 Brick Township, NJ Block: 1170 Lot: 5 Qual: _____
Owner in Fee: THE HOME DEPOT
Owner Address: 3096 HAMILTON BLVD S PLAINFIELD NJ 07080
Telephone: (732) 926-3626
Contractor: CASCO
Address: 1090 KING GEORGE POST RD EDISON NJ 08837
Telephone: (732) 661-1400 Fax: _____
License Number or Builders Registration Number: _____ Federal Emp. Number: _____

Home Warranty Number: _____

Type of Warranty Plan: ☐ State ☐ Private

Use Group: M Construction Classification: Type I

Maximum Live Load: 0 Maximum Occupancy Load: 0

Description of Work/Use: ALTERATION - -COMMERCIAL CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

Certificate Comments:

☐ **Certificate of Occupancy**

This serves notice that said building or structure has been constructed in accordance with the New Jersey Uniform Construction Code and is approved for occupancy.

☐ **Certificate of Approval**

This serves notice that the work completed has been constructed or installed in accordance with the New Jersey Uniform Construction Code and is approved. If the permit was issued for minor work, this certificate was based upon what was visible at the time of inspection.

☐ **Certificate of Continued Occupancy**

This serves notice that based on a general inspection of the visible parts of the building there are no imminent hazards and the building is approved for continued occupancy.

☐ **Temporary Certificate of Compliance**

The following conditions must be met no later than or the owner will be subject to fine or order to vacate:
This certificate has an expiration date of:
Conditions to be met:

☐ **Certificate of Clearance - Lead Abatement 5:17**

This serves notice that based on written certification, lead abatement was performed as per NJAC5:17 to the following extent.

- ☐ Total removal of lead-based paint hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Clearance - Asbestos Abatement**

This serves notice that based on written certification, asbestos abatement was performed to the following extent.

- ☐ Total removal of asbestos hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Compliance**

This serves notice that said potentially hazardous equipment has been installed and/or maintained in accordance with the New Jersey Uniform Construction Code and is approved for use until

☒ **Temporary Certificate of Occupancy**

The following conditions must be met no later than: 10/09/2009
or the owner will be subject to fine or order to vacate:
This certificate has an expiration date of: 10/09/2009
Conditions to be met:

Engineering Temporary until October 9, 2009 for Store Opening

Construction Official
31409
ALC
209
DN

Fee: \$0.00
Check Number: _____
Collected By: _____



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723

Date Issued 10/09/2009
Control Number C-08-004682
Permit Number 09-0158
Permit Issue Date 01/30/2009
Certificate Number 09-0158

Certificate

Construction Code Division
(Temporary Certificate of Occupancy)

Identification

Work Site Location: 1722 ROUTE 88 Brick Township, NJ Block: 1170 Lot: 5 Qual: _____
Owner in Fee: THE HOME DEPOT
Owner Address: 3096 HAMILTON BLVD S PLAINFIELD NJ 07080
Telephone: (732) 926-3626
Contractor: CASCO
Address: 1090 KING GEORGE POST RD EDISON NJ 08837
Telephone: (732) 661-1400 Fax: _____
License Number or Builders Registration Number: _____ Federal Emp. Number: _____

Home Warranty Number: _____

Type of Warranty Plan: ☐ State ☐ Private

Use Group: M Construction Classification: Type I

Maximum Live Load: 0 Maximum Occupancy Load: 0

Description of Work/Use: ALTERATION - -COMMERCIAL CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

Certificate Comments:

☐ **Certificate of Occupancy**

This serves notice that said building or structure has been constructed in accordance with the New Jersey Uniform Construction Code and is approved for occupancy.

☐ **Certificate of Approval**

This serves notice that the work completed has been constructed or installed in accordance with the New Jersey Uniform Construction Code and is approved. If the permit was issued for minor work, this certificate was based upon what was visible at the time of inspection.

☐ **Certificate of Continued Occupancy**

This serves notice that based on a general inspection of the visible parts of the building there are no imminent hazards and the building is approved for continued occupancy.

☐ **Temporary Certificate of Compliance**

The following conditions must be met no later than or the owner will be subject to fine or order to vacate:

This certificate has an expiration date of:

Conditions to be met:

☐ **Certificate of Clearance - Lead Abatement 5:17**

This serves notice that based on written certification, lead abatement was performed as per NJAC5:17 to the following extent.

- ☐ Total removal of lead-based paint hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Clearance - Asbestos Abatement**

This serves notice that based on written certification, asbestos abatement was performed to the following extent.

- ☐ Total removal of asbestos hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Compliance**

This serves notice that said potentially hazardous equipment has been installed and/or maintained in accordance with the New Jersey Uniform Construction Code and is approved for use until

☒ **Temporary Certificate of Occupancy**

The following conditions must be met no later than: or the owner will be subject to fine or order to vacate:

This certificate has an expiration date of: 11/13/2009

Conditions to be met:

Engineering Temporary until November 13, 2009

Construction Official

Fee: \$0.00

Check Number: _____

Collected By: _____



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723

Date Issued 11/13/2009
Control Number C-08-004682
Permit Number 09-0158
Permit Issue Date 01/30/2009
Certificate Number 09-0158

Certificate

Construction Code Division
(Certificate of Occupancy)

Identification

Work Site Location: 1722 ROUTE 88 Brick Township, NJ Block: 1170 Lot: 5 Qual: _____
Owner in Fee: THE HOME DEPOT
Owner Address: 3096 HAMILTON BLVD S PLAINFIELD NJ 07080
Telephone: (732) 926-3626
Contractor: CASCO
Address: 1090 KING GEORGE POST RD EDISON NJ 08837
Telephone: (732) 661-1400 Fax: _____
License Number or Builders Registration Number: _____ Federal Emp. Number: _____

Home Warranty Number: _____

Type of Warranty Plan: ☐ State ☐ Private

Use Group: M Construction Classification: Type I

Maximum Live Load: 0 Maximum Occupancy Load: 0

Description of Work/Use: ALTERATION - -COMMERCIAL CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

Certificate Comments:

☒ **Certificate of Occupancy**

This serves notice that said building or structure has been constructed in accordance with the New Jersey Uniform Construction Code and is approved for occupancy.

☐ **Certificate of Approval**

This serves notice that the work completed has been constructed or installed in accordance with the New Jersey Uniform Construction Code and is approved. If the permit was issued for minor work, this certificate was based upon what was visible at the time of inspection.

☐ **Certificate of Continued Occupancy**

This serves notice that based on a general inspection of the visible parts of the building there are no imminent hazards and the building is approved for continued occupancy.

☐ **Temporary Certificate of Compliance**

The following conditions must be met no later than or the owner will be subject to fine or order to vacate:
This certificate has an expiration date of:
Conditions to be met:

☐ **Certificate of Clearance - Lead Abatement 5:17**

This serves notice that based on written certification, lead abatement was performed as per NJAC5:17 to the following extent.

- ☐ Total removal of lead-based paint hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Clearance - Asbestos Abatement**

This serves notice that based on written certification, asbestos abatement was performed to the following extent.

- ☐ Total removal of asbestos hazards in scope of work
☐ Partial or limited time period (years); see file

☐ **Certificate of Compliance**

This serves notice that said potentially hazardous equipment has been installed and/or maintained in accordance with the New Jersey Uniform Construction Code and is approved for use until

☐ **Temporary Certificate of Occupancy**

The following conditions must be met no later than: or the owner will be subject to fine or order to vacate:
This certificate has an expiration date of:
Conditions to be met:

Construction Official

Fee: \$35.00
Check Number: 1354
Collected By: Inspection Account



PERMIT UPDATE

Date Update Issued 1-30-09
Control # C-08-004682+A
Permit # +A

09-0158 +A

IDENTIFICATION Block: 1170 Lot: 5 Qualifier _____
Work Site Location: 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Telephone: (732) 661-1400
Telephone: (732) 926-3626 Lic. No. or Bldrs. Reg. No. _____
Federal Employee No. _____

Is hereby granted permission to perform the following work:

- ☐ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☐ ELECTRICAL ☒ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

FIRE SUPPRESSION ALTERATIONS ADD/REMOVE/RELOCATE TO MATCH REMODELED BUILDING.

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$10,000

Construction Official [Signature]

Date 1-30-09

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$0
Electrical	\$0
Plumbing	\$0
Fire Protection	\$765
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$14
CO Fee	
Other	\$0
Total	\$779
Check No.	<u>42590</u>
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements: 01/30/09 3:48PM 00155848746
XX02 SERV.002

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.

#01558

FIRE

\$765.00

\$14.00

\$779.00



PERMIT UPDATE

03-10-09
Date Update Issued
Control # C-09-000458
Permit # 09-0158+B

IDENTIFICATION Block: 1170 Lot: 5 Qualifier
Work Site Location: 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Telephone: (732) 661-1400
Telephone: (732) 926-3626 Lic. No. or Bldrs. Reg. No.
Federal Employee No.

Is hereby granted permission to perform the following work:

- ☐ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☐ ELECTRICAL ☒ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

ALARM SYSTEM (BURGLAR OR FIRE), FIRE ALTERATIONS CONVERT AN EXISTING
"COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN
EXTERIOR GARDEN CENTER.

Note: If construction does not commence within one (1) year of date of issuance, or if
construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$50,000

Construction Official

Date

2-27-09

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$0
Electrical	\$0
Plumbing	\$0
Fire Protection	\$225
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$0
CO Fee	
Other	\$0
Total	\$225
Check No.	
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

- ☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:
1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
 2. Foundations and all walls up to grade level prior to back filling.
 3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and /or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
 4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

- ☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

- ☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

- ☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.



PERMIT UPDATE

Date Update Issued
Control # C-09-000642
Permit # 09-0158+C

IDENTIFICATION Block: 1170 Lot: 5 Qualifier
Work Site Location: 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Telephone: (732) 661-1400
Telephone: (732) 926-3626 Lic. No. or Bldrs. Reg. No.
Federal Employee No.

Is hereby granted permission to perform the following work:

- ☐ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

ALARM SYSTEM (BURGLAR OR FIRE)

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$3,000

Construction Official

Date

K. L. Newman 3/12/09

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$0
Electrical	\$40
Plumbing	\$0
Fire Protection	\$0
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$4
CO Fee	
Other	\$0
Total	\$44
Check No.	
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.



PERMIT UPDATE

Date Update Issued 6-19-09
Control # C-09-002073
Permit # 09-0158+E

IDENTIFICATION Block: 1170 Lot: 5 Qualifier _____
Work Site Location: 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT Telephone: (732) 661-1400
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Lic. No. or Bldrs. Reg. No. _____
Telephone: (732) 926-3626 Federal Employee No. _____

Is hereby granted permission to perform the following work:

- | | | |
|--|--|--|
| ☐ BUILDING | ☐ PLUMBING | ☐ LEAD HAZARD ABATEMENT |
| ☒ ELECTRICAL | ☐ FIRE PROTECTION | ☐ DEMOLITION |
| ☐ ELEVATOR DEVICES | ☐ ASBESTOS ABATEMENT
(Subchapter 8 only) | ☐ OTHER |

DESCRIPTION OF WORK:

COMMUNICATION POINTS

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$50,000

Construction Official [Signature]

Date 6-15-07

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$0
Electrical	\$60
Plumbing	\$0
Fire Protection	\$0
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	<u>\$10</u> \$85
CO Fee	
Other	\$0
Total	<u>146</u> \$446
Check No.	<u>7032</u>
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.



PERMIT UPDATE

Date Update Issued 8-10-09
Control # C-09-000746
Permit # 09-0158+D

IDENTIFICATION Block: 1170 Lot: 5 Qualifier _____
Work Site Location: 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT Telephone: (732) 661-1400
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Lic. No. or Bldrs. Reg. No. _____
Telephone: (732) 926-3626 Federal Employee. No. _____

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☐ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☐ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

ALTERATION - COMMERCIAL LIGHT POLES CASCO HAS ISSUED A CHANGE BULLETIN 1B
SITE AND BUILDING DATE 01-18-09

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$52,800

Construction Official [Signature]

Date 8-10-09

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$1,200
Electrical	\$45
Plumbing	\$0
Fire Protection	\$0
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$90
CO Fee	
Other	\$0
Total	\$1,335
Check No.	<u>1375</u>
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

- ☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

1. The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
2. Foundations and all walls up to grade level prior to back filling.
3. All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
4. Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

- ☐ Required special inspections. The applicant by accepting the permit will be deemed to have consented to these requirements:

- ☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

- ☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.

1200.00
ELECTRIC \$45.00
DCA \$90.00
1335.00



CONSTRUCTION PERMIT

Date Issued 1-30-09
Control # C-08-004682
Permit # 09-0158

IDENTIFICATION Block: 1170 Lot: 5 Qualifier _____
Work Site Location: 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Telephone: (732) 661-1400
Telephone: (732) 926-3626 Lic. No. or Bldrs. Reg. No. _____
Federal Employee. No. _____

Is hereby granted permission to perform the following work:

- ☒ BUILDING ☒ PLUMBING ☐ LEAD HAZARD ABATEMENT
☒ ELECTRICAL ☒ FIRE PROTECTION ☐ DEMOLITION
☐ ELEVATOR DEVICES ☐ ASBESTOS ABATEMENT (Subchapter 8 only) ☐ OTHER

DESCRIPTION OF WORK:

ALTERATION - COMMERCIAL CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

Note: If construction does not commence within one (1) year of date of issuance, or if construction ceases for a period of six (6) months, this permit is void.

Estimated Cost of Work \$5,975,000

Construction Official [Signature]

Date 1-30-09

U.C.C. F170
equiv (rev 8/03)

1 WHITE - INSPECTOR

2 CANARY - OFFICE

3 PINK - TAX ASSESSOR

4 GOLD - APPLICANT

PAYMENTS (Office Use Only)

Building	\$65,850
Electrical	\$13,125
Plumbing	\$2,200
Fire Protection	\$1,800
Elevator Devices	\$0
Other	\$0.00
DCA Training Fee	\$8,065
CO Fee	
Other	\$60
Total	\$91,100
Check No.	<u>43540</u>
Cash	\$0
Credit	\$0
Collected By	

REQUIRED INSPECTIONS

Construction work must be inspected in accordance with the State Uniform Construction Code Regulations N.J.A.C. 5:23-2.18. This agency will carry out such periodic inspections during the progress of work as are necessary to insure that the work installed conforms with the requirements of the Uniform Construction Code.

The owner or other responsible person in charge of work must notify this agency when work is ready for any required inspections specified below. Requests for inspections must be made at least 24 hours prior to the time the inspection is desired. Inspections will be performed within three business days of the time for which they are requested. The work must not proceed in a manner which will preclude the inspection until it has been made and approval granted.

☐ Required inspections for all subcodes for one- and two-family dwellings are as follows:

- The bottom of footing trenches before placement of footings, except that in cases of pile foundations, inspections shall be made in accordance with the requirements of the building subcode.
- Foundations and all walls up to grade level prior to back filling.
- All structural framing, connections, wall and roof sheathing and insulation; electrical rough wiring, panel and service installation; rough plumbing. The framing inspection shall take place after the rough electrical and plumbing inspections and after the installation of the heating, ventilation and/or air conditioning duct system. The insulation inspection shall be performed after all other subcode rough inspections and prior to the installation of any interior finish material.
- Installation of all finished materials, sealings of exterior joints, plumbing piping, trim and fixtures; electrical wiring, devices and fixtures; mechanical systems equipment.

Additional required inspections for all subcodes of construction, for other than one- and two-family dwellings, are fire suppression systems, heat producing devices and Barrier Free subcode accessibility, if applicable.

☐ Required special inspections: The applicant by accepting the permit will be deemed to have consented to these requirements: 001558/18743
XX02 SERV.002

#0158

☐ A final inspection is required for each applicable subcode area before a final Certificate of Occupancy or Approval may be issued. The final inspections include the installation of all interior and exterior finish materials, sealing of exterior joints, mechanical system and other required equipment; electrical wiring, devices and fixtures; plumbing pipes, trim and fixtures; tests required by any provision of the adopted subcodes, Barrier Free accessibility, if applicable; and verification of compliance with NJAC 5:23-3.5, "Posting structures".

☐ A complete copy of released plans must be kept on the job site.

If you do not understand any of this information, please ask.

Clissa

~~Post~~ ~~intensity~~ $\frac{50}{100}$ $\frac{1}{4}$ 3/30

I recall you working with the
Engineer concerning some lighting
changes. Was the location of the
poles one of the changes or just
lighting intensity? M. Chas

INSPECTOR: Russell Harris

DATE: 11/11/09

JOB: Home Depot SECTION:

TYPE OF WORK: Final CO

WEATHER: Overcast/Rain

LOCATION: Rt. 70 & Rt. 88

TEMPERATURE: 50's

BLOCK: 1170

LOT: 5

**ENGINEERING RECOMMENDATIONS FOR
CERTIFICATE OF OCCUPANCY
INSPECTION CHECK LIST**

ITEMS TO BE COMPLETED	COMPLETED	DEFICIENT
1. Driveway	✓	
2. Grading	✓	
3. Sidewalk	✓	
4. Road Pavement	✓	
5. Landscaping & Sodding	see comment below	
6. Clean-up Procedures	✓	
7. Note on going construction in immediate area	see comment below	
8. Safety	✓	

COMMENTS REFERENCING ITEM NUMBER:

5. Additional remediation will be required in the Spring.
Item will remain open on the site bond.

7. Require meeting & schedule to ~~complete~~ review
& start work to complete remaining site bond items.

RECOMMENDATIONS:

☐ TEMP. C.O.

☒ FINAL C.O.

☐ DETAILED REINSPECTION

☐ HOLD INSPECTION UNTIL LOT ELEVATION FIELD VERIFIED

PLANNING BOARD ENGINEER

E.C. [Signature]

MUNICIPAL ENGINEER

I, _____, Authorized representative of _____, hereby acknowledge the above deficiencies, and further realize that the Certificate of Occupancy will be conditioned upon the acceptable resolution thereof within _____ days of the issuance of Certificate of Occupancy.

INSPECTOR: Russell Harris

DATE: 10/9/09

JOB: Home Depot SECTION:

TYPE OF WORK: Temp CO renewal

Job #205234112548

WEATHER: Clear

LOCATION: 1722 Route 88

TEMPERATURE: 60's

BLOCK: 1170

LOT: 5

**ENGINEERING RECOMMENDATIONS FOR
CERTIFICATE OF OCCUPANCY
INSPECTION CHECK LIST**

ITEMS TO BE COMPLETED	COMPLETED	DEFICIENT
1. Driveway	✓	
2. Grading	✓	
3. Sidewalk	✓	
4. Road Pavement	✓	
5. Landscaping & Sodding		✓
6. Clean-up Procedures	✓	
7. Note on going construction in immediate area	✓	
8. Safety	✓	

COMMENTS REFERENCING ITEM NUMBER:

5. Monitor lawn restorations. Check status of conditions
GN 10/30/09

Temp expires 11/13/09

RECOMMENDATIONS:

☒ TEMP. C.O.

☐ FINAL C.O.

☐ DETAILED REINSPECTION

☐ HOLD INSPECTION UNTIL LOT ELEVATION FIELD VERIFIED

[Signature]

PLANNING BOARD ENGINEER

[Signature]

MUNICIPAL ENGINEER

I, _____, Authorized representative of
_____, hereby acknowledge the
above deficiencies, and further realize that the Certificate of Occupancy will be conditioned upon the acceptable resolution
thereof within _____ days of the issuance of Certificate of Occupancy.

INSPECTOR: Russell Harris

DATE: 8/14/09

JOB: Home Depot SECTION:

TYPE OF WORK: Final CO

WEATHER: Clear

LOCATION: 1722 Rt. 88

TEMPERATURE: 85+

BLOCK: 1170

LOT: 5

**ENGINEERING RECOMMENDATIONS FOR
CERTIFICATE OF OCCUPANCY
INSPECTION CHECK LIST**

ITEMS TO BE COMPLETED	COMPLETED	DEFICIENT
1. Driveway	✓	
2. Grading	✓	
3. Sidewalk	✓	
4. Road Pavement	✓	
5. Landscaping & Sodding		✓ lawn areas require maintenance see letter
6. Clean-up Procedures	✓	
7. Note on going construction in immediate area	Merchandising Store	
8. Safety	✓	

COMMENTS REFERENCING ITEM NUMBER:

RECOMMENDATIONS: For Store Opening

☒ TEMP. C.O. Exp. October 9th, 2009

☐ FINAL C.O.

☐ DETAILED REINSPECTION

☐ HOLD INSPECTION UNTIL LOT ELEVATION FIELD VERIFIED

PLANNING BOARD ENGINEER

EC Com

MUNICIPAL ENGINEER

I, _____, Authorized representative of _____, hereby acknowledge the above deficiencies, and further realize that the Certificate of Occupancy will be conditioned upon the acceptable resolution thereof within _____ days of the issuance of Certificate of Occupancy.



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location The Home Depot

Owner in Fee: The Home Depot

Tel. (732) 926-5626 e-mail _____

Address 1722 W State Route 28 Brick NJ

Contractor: HomeLand Security & Life Safety Systems Tel. (201) 955-9110

Address 22 Pershing Place e-mail _____

North Arlington NJ 07031

Contractor License No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: (_____) _____

B-ELECTRICAL CHARACTERISTICS

Use Group Present _____ Proposed _____

☐ Pole/Pad # _____ ☐ Temporary ☐ Other _____

Building Occupied as _____ Utility Co. _____

Est. Cost of Elec. Work \$ 3,000.00

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☒ No Plans Required 3-179

☐ Partial - Underslab Utilities Approved

Date: _____ Approved by: _____

☐ Electric Plans Approved

Date: _____ Approved by: _____

Joint Plan Review Required:

☐ Bldg. ☐ Plumb. ☐ Fire. ☐ Elev.

SUBCODE APPROVAL for PERMIT

Date: _____

Approved by: _____

SUBCODE APPROVAL for CERTIFICATE

☐ CO ☐ CCO ☐ CA

Date: _____

Approved by: _____

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

Beit

[] Licensed Elec. Contractor [] Certifd Landscape Irrigation Contr [] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Date Received
Control #
Date Issued
Permit #

QTY. SIZE

ITEMS

FEE (Office Use Only)

Lighting Fixtures
Receptacles
Switches
Detectors
Light Poles
Motors—Fract. HP
Emergency & Exit Lights
Communications Points
Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UW Lights
Storable Pool/Spa/Hot Tub
KW Elec. Range/Receptacle
KW Oven/Surface Unit
KW Elec. Water Heater
KW Elec. Dryer/Receptacle
KW Dishwasher
HP Garbage Disposal
KW Central A/C Unit
HP/KW Space Heater/Air Handler
KW Baseboard Heat
HP Motors 1/+ HP
KW Transformer/Generator
AMP Service
AMP Subpanels
AMP Motor Control Center
KW Elec. Sign/Outline Light
Anti Theft system

Administrative Surcharge \$

Minimum Fee \$

State Permit Surcharge Fee \$

TOTAL FEE \$



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____
Work Site Location The Home Depot

Owner in Fee: The Home Depot

Tel. (732) 226-3636 e-mail _____

Address 1702 NY State Route 28 Brick NJ

Contractor: HomeLand Security + Life Safety Systems Tel. (201) 955-9110

Address 22 Pershing Place e-mail _____
North Arlington NJ 07031

Contractor License No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: (____) _____

B. ELECTRICAL CHARACTERISTICS
Use Group Present _____ Proposed _____

[] Pole/Pad # _____ [] Temporary [] Other _____

Building Occupied as _____ Utility Co. _____

Est. Cost of Elec. Work \$ 3,000.00

JOB SUMMARY (Office Use Only)		INSPECTIONS		Dates (Month/Day)		Initial	
PLAN REVIEW	Type:	Failure	Failure	Approval			
[] No Plans Required <u>3-129 AS</u>	Rough						
[] Partial - Underslab Utilities Approved	Barrier-Free						
Date: _____	Trench						
[] Electric Plans Approved	Temp. Serv.						
Date: _____	Constr. Serv.						
[] Joint Plan Review Required	TCO						
[] Bldg. [] Plumb. [] Fire. [] Elev. Service	Other						
SUBCODE APPROVAL for PERMIT	Final						
Date: _____	Barrier-Free						
Approved by: _____	Temp. Cut-in-Card Date Issued						
SUBCODE APPROVAL for CERTIFICATE	Final Cut-in-Card Date Issued						
[] CO [] CCO [] CA	Annual Pool Inspection						
Date: _____	Date of Grounding and Bonding						
Approved by: _____	Certification						

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Signature
Burt Burt

[] Licensed Elec. Contractor [] Certified Landscape Irrigation Contractor [] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

QTY. SIZE

ITEMS

FEE (Office Use Only)

Lighting Fixtures
Receptacles
Switches
Detectors
Light Poles
Motors—Fract. HP
Emergency & Exit Lights
Communications Points
Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UV Lights
Storable Pool/Spa/Hot Tub
KW Elec. Range/Receptacle
KW Oven/Surface Unit
KW Elec. Water Heater
KW Elec. Dryer/Receptacle
KW Dishwasher
HP Garbage Disposal
KW Central A/C Unit
HP/KW Space-Heater/Air Handler
KW Baseboard Heat
HP Motors 1/4 HP
KW Transformer/Generator
AMP Service
AMP Subpanels
AMP Motor Control Center
KW Elec. Sign/Outline Light
Anti Theft System

Date Received
Control #

Date Issued
Permit #

3/30/09

Administrative Surcharge \$

Minimum Fee \$

State Permit Surcharge Fee \$

TOTAL FEE \$

INSPECTOR: Russell Harris

DATE: 8/10/09

JOB: Home Depot SECTION:

TYPE OF WORK: Final CO

WEATHER: Clear

LOCATION: NISH Rte 88

TEMPERATURE: 90+

BLOCK: 1170

LOT: 5

**ENGINEERING RECOMMENDATIONS FOR
CERTIFICATE OF OCCUPANCY
INSPECTION CHECK LIST**

ITEMS TO BE COMPLETED	COMPLETED	DEFICIENT
1. Driveway	✓	
2. Grading	✓	
3. Sidewalk	✓	
4. Road Pavement		✓ striping/signage incomplete
5. Landscaping & Sodding		✓ Landscape incomplete ✓ Lawn requires maint.
6. Clean-up Procedures		✓ construction debris on site
7. Note on going construction in immediate area		✓ striping, signage ✓ Landscaping
8. Safety		✓ stormwater spill off entry vestibule

COMMENTS REFERENCING ITEM NUMBER:

RECOMMENDATIONS:

☐ TEMP. C.O.

☐ FINAL C.O.

☒ DETAILED REINSPECTION

☐ HOLD INSPECTION UNTIL LOT ELEVATION FIELD VERIFIED

PLANNING BOARD ENGINEER

ECC

MUNICIPAL ENGINEER

I, _____, Authorized representative of _____, hereby acknowledge the above deficiencies, and further realize that the Certificate of Occupancy will be conditioned upon the acceptable resolution thereof within _____ days of the issuance of Certificate of Occupancy.

INSPECTOR: Russell Harris

DATE: 8/10/09

JOB: Home Depot SECTION: off Rt. 88
i Rt. 70

TYPE OF WORK: Temp for stocking
shelves.

WEATHER: Sunny/Clear

LOCATION: 1722 Rt. 88

TEMPERATURE: 90+

BLOCK: 1170

LOT: 5

**ENGINEERING RECOMMENDATIONS FOR
CERTIFICATE OF OCCUPANCY
INSPECTION CHECK LIST**

ITEMS TO BE COMPLETED	COMPLETED	DEFICIENT
1. Driveway	✓	signage/stripping in progress
2. Grading	✓	
3. Sidewalk	✓	
4. Road Pavement	✓	
5. Landscaping & Sodding		✓ lawn/landscape issues
6. Clean-up Procedures		✓ ongoing
7. Note on going construction in immediate area		✓ ongoing site/bldg.
8. Safety	✓	

COMMENTS REFERENCING ITEM NUMBER:


RECOMMENDATIONS:


☒ TEMP. C.O. for employee merchandising "only" till 8/20/09

☐ FINAL C.O.

☐ DETAILED REINSPECTION

☐ HOLD INSPECTION UNTIL LOT ELEVATION FIELD VERIFIED

 PLANNING BOARD ENGINEER

 MUNICIPAL ENGINEER

I _____, Authorized representative of
_____, hereby acknowledge the
above deficiencies, and further realize that the Certificate of Occupancy will be conditioned upon the acceptable resolution
thereof within _____ days of the issuance of Certificate of Occupancy.

INSPECTOR:

KShaffer / R Harris

DATE:

7-2-09

JOB:

Home
Depot

SECTION:

0A
R+88/70

TYPE OF WORK:

Temp for Staging
Shelving

LOCATION:

1722 R+88

BLOCK:

1170

LOT:

5

WEATHER:

Pt Sunny

TEMPERATURE:

80°

ENGINEERING RECOMMENDATIONS FOR CERTIFICATE OF OCCUPANCY INSPECTION CHECK LIST

ITEMS TO BE COMPLETED	COMPLETED	DEFICIENT
1. Driveway	✓	* Signage / Supply Drill off
2. Grading	✓	
3. Sidewalk	✓	
4. Road Pavement		✓ on going R+88
5. Landscaping & Sodding		✓ on going
6. Clean-up Procedures	✓	
7. Note on going construction in immediate area		✓ on going
8. Safety	✓	

COMMENTS REFERENCING ITEM NUMBER:

Store Employees only

RECOMMENDATIONS:

* TEMP. C.O. for employee merchandising "only" until 8/10/09

☐ FINAL C.O.

☐ DETAILED REINSPECTION

☐ HOLD INSPECTION UNTIL LOT ELEVATION FIELD VERIFIED

☐ PLANNING BOARD ENGINEER

☐ MUNICIPAL ENGINEER

_____, Authorized representative of

_____, hereby acknowledge the
above deficiencies, and further realize that the Certificate of Occupancy will be conditioned upon the acceptable resolution
thereof within _____ days of the issuance of Certificate of Occupancy.

**THE BRICK TOWNSHIP
MUNICIPAL UTILITIES AUTHORITY**

1551 HIGHWAY 88 WEST
BRICK, NEW JERSEY 08724
(732) 458-7000

CERTIFICATE OF COMPLIANCE

Date 7/6/09

NAME Home Depot 0912

ADDRESS 1722 Route 88 W Brick NJ 08724

PROPERTY LOCATION 1722 Route 88 W-Home Depot

Account No 17304002-2 Block 1170 Lot 5

I hereby certify that the above applicant has complied with all Rules and Regulations of this Authority and has paid all required fees and charges.

For the Authority

Carol Gurdal



OCEAN COUNTY SOIL CONSERVATION DISTRICT

714 Lacey Road, Forked River, NJ 08731
Tel 609.971.7002 • Fax 609.971.3391 • www.ocscd.org

REPORT OF COMPLIANCE

TO: CONSTRUCTION CODE OFFICIAL

MUNICIPALITY: BRICK

PROJECT: Home DEPT

SCD NO: 10036

BLOCK NO.(S): 1170

LOT NO.(S): 5

Final Compliance ☒

Conditional Compliance ☐

Block No.	Lot No.	Conditions
		ALL REMAINING AREAS TO BE HAY MULCHES PRIOR TO BLDG. OCCUPANCY
		TOTAL FEES DUE: \$ <u> </u>

This verifies that the soil erosion and sediment control measures for the above designated block and lot numbers are in compliance to the extent indicated above with the soil erosion and sediment control plan as certified by the Ocean County Soil Conservation District and required by Chapter 251, P.L. 1975 as amended, the Soil Erosion and Sediment Control Act, (N.J.S.A. 4:24 - 39 et. seq.).

AGENT RESPONSIBLE FOR PROJECT: RIV

AUTHORIZED DISTRICT SIGNATURE:

DATE: 7/4/69

Distribution: WHITE - Township
CANARY - Applicant
PINK - District



BUILDING SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location 1722 NJ STATE ROUTE 88

Owner in Fee: THE HOME DEPOT

Tel. (732) 226-7626 e-mail buce.talvo@homedepot.com

Address 7096 HAMILTON BLVD., S. PLAINFIELD, NJ 07080

Contractor: ACECO/Contractor Municipality to Tel. (732) 848 307 1838

Address _____ e-mail _____

Contractor License No. or Builder Registration No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: () _____

CONTRACTOR LICENSE NO. OR BUILDER REGISTRATION NO. _____

JOB SUMMARY (Office Use Only)

PLAN REVIEW

INSPECTIONS

DATES (Month/Day)

[] No Plans Required Date Initial Type: Failure Failure Approval Initial

[X] All 1/29/08 RA Footing * 2-13-09 JR

[] Footings/Foundations Footing Bonding

[] Structural/Framework Foundation * 2-13-09 JR

[] Exterior Frame * 6-1-09 G.P.

[X] Interior Truss Sys/Bracing

[] Joint Plan Review Required Barrier-Free

[] Elec. [] Plumb. [] Fire [] Elevator Insulation

SUBCODE APPROVAL for PERMIT

Date: _____

Approved by: _____

SUBCODE APPROVAL for CERTIFICATE

[X] CO [] CCO 8/13/09 CA

Date: _____

Approved by: _____

B. BUILDING CHARACTERISTICS

Use Group Present M Proposed M

No. of Stories (1) ONE Constr. Class Present IIA Proposed IIA

Height of Structure 76 FT If Industrialized Building: _____

Area — Largest Floor 127,025 State Approved _____ HUD _____

New Bldg. Area/All Floors 21,300 sq. ft. Est. Cost of Bldg. Work: _____

Volume of New Structure 240,305 sq. ft. 1. New Bldg. \$ 4,350,000.00

Max. Live Load _____ 2. Rehabilitation \$ 4,350,000.00

Max. Occupancy Load 4,070 PERSONS 3. Total (1+2) \$ 8,700,000.00

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

Signature _____

DATE RECEIVED _____

CONTROL # _____

DATE ISSUED _____

PERMIT # _____

COMMERCIAL

FEE (Office Use Only)

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

09-0158
1-30-09

1 While = Inspector Copy

2 Canary = Office Copy

3 Pink = Office Copy

4 Gold = Applicant Copy

U.C.C. #110
(rev. 12/07)

8/7/09 W= Recommend TCO

OK 1) Elect. Rm. 1 Hr. Rating / Both sides

OK 2) Additional Exit Signage

A) Data Room

B) Appliance Center

C) GC Center Auto Sliding doors

D) House plant enclosure

OK 3) Anchor rack in Garden Center
(End Cap)

4) Cut sheet for HPE or 1" Clearance

OK 5) Knock out directionals at Emergency light display at end of Isle

2-13-09	J.L.	SLAB	COLUMN LINE 9-11	A-F
2-16-09	J.L.	FOOTINGS	LUMBER VESTIBULE / ENTRY-EXIT VESTIBULE	
2-20-09	J.L.	FOOTINGS	GARDEN CENTER	F-B4 0-1
2-24-09	J.L.	FOOTINGS	LOADING DOCK	A-A.8 - 0.1 - 0.7
2-26-09	G.P.	LC	" "	A-0.7A - column 1 - UNDERPINNING
3-6-09	J.L.	PIERS	18 - GARDEN CENTER AREA	
3-10-09	J.L.	PIERS @	LOADING DOCK	
3-11-09	J.L.	SLAB @	LOADING DOCK / PARTIAL	
3-16-09	J.L.	SLAB @	LOADING DOCK / PARTIAL	
3-20-09	J.L.	SLAB @	LOADING DOCK / PARTIAL	
3-24-09	J.L.	PARTIAL FRAME / REAR OF BLDG	PIERS FOR LUMBER ROOF	
4-1-09	J.L.	PARTIAL FRAME /	0.14	
4-14-09	J.L.	SLAB O.K.	GARDEN CENTER	
4-20-09	J.L.	PARTIAL FRAME	REAR OF BLDG	
4-24-09	J.L.	FRAME BALANCE	REAR OF BLDG	
5-21-09	J.L.	SLAB		
5-22-09	J.L.	FRAME VESTIBULES		
6-1-09	G.P.	PAINT SIGN		



BUILDING SUBCODE TECHNICAL SECTION



COMMERCIAL

Date Received 09/30/2008
Control # C-08-004682
Date Issued 01/30/2009
Permit # 09-0158

A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000

Block 1170 Lot 5 Qualification Code

Work Site Location: 1722 ROUTE 88 Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address: 3096 HAMILTON BLVD S PLAINFIELD NJ 07080

Tel. (732) 926-3626

Contractor: CASCO

Address: 1090 KING GEORGE POST RD EDISON NJ 08837

Tel. (732) 661-1400

Fax:

Contractor License No. or, if new home, Bldrs Reg. No.

Federal Employee No.

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Type:	Failure	Dates (Month/Day)	Approval	Initial
☐ No Plan Required				Footings				
☐ All				Footings Bonding				
☐ Footings				Foundation				
☐ Foundation				Slab				
☐ Frame				Frame				
☐ Other				Truss Sys./Bracing				
☐ Joint Plan Review Required				Barrier-Free				
☐ Elec. ☐ Plumb. ☐ Fire ☐ Elevator				Insulation				
				Finishes-Base Layer				
				Finishes-Final				
				Energy				
				Mechanical				
				TCO				
				Other				
				Final				
				Barrier-Free				

B. BUILDING CHARACTERISTICS

Use Group Present Proposed M

Constr. Class Present Type Proposed Type

Number of Stories

Height of Structure Ft.

Area - Largest Floor 21309 Sq. Ft.

New Bldg. Area / All Floors 100 Sq. Ft.

Volume of New Structure 3459 Cu. Ft.

Total Land Area Disturbed Sq. Ft.

Est. Cost of Bldg. Work:

1. New Bldg. \$4,350,000
2. Rehabilitation \$4,350,100
3. Total (1+2) \$4,350,100

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of the record and am authorized to make this application.

Signature

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

ALTERATION - COMMERCIAL. CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

TYPE OF WORK

- ☐ New Building
- ☒ Addition
- ☒ Rehabilitation
- ☐ Roofing
- ☐ Siding
- ☐ Fence Height (exceeds 6')
- ☐ Sign Sq. Ft.
- ☐ Pool
- ☐ Asbestos Abatement Subchapter 8
- ☐ Lead Haz Abatement NJAC 5:17
- ☐ Other
- ☐ Demolition

FEE (Office Use Only)

Administrative Surcharge	
Minimum Fee	
State Permit Surcharge Fee	\$5,881
TOTAL FEE	\$71,824



BUILDING SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location 1722 Route 88 Buick NJ 08724

Owner in Fee: 142 Home Depot

Tel. (732) 926-3626 e-mail Bruce - talvy @home depot.com

Address 3096 Hamilton Blvd, S Fairfield NJ 07080

Contractor: Riv Construction Group Tel. (732) 431-5484

Address 315 Rt 34 Suite 137 e-mail _____

COITS NECK NJ 07733

Contractor License No. or Builder Registration No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. 54-1608072 FAX: (732) 431-5483

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Failure	Failure	Approval	Initial
☐ No Plans Required			Type:				
☐ All			Footings				
☐ Footings/Foundations			Footings Bonding				
☐ Structural/Framework			Foundation				
☐ Exterior			Slab				
☒ Interior Light Poles 8/1/09			Frame				
Joint Plan Review Required:			Truss Sys./Bracing				
☐ Elec. ☐ Plumb. ☐ Fire ☐ Elevator			Barrier-Free				
SUBCODE APPROVAL for PERMIT			Insulation				
Date:			Finishes -Base Layer				
			Finishes -Final				
Approved by:			Energy				
			Mechanical				
SUBCODE APPROVAL for CERTIFICATE			TCO				
☐ CO ☐ CCO			Other				
Date:			Barrier-Free				
Approved by:							

B. BUILDING CHARACTERISTICS

Use Group Present M Proposed M

No. of Stories ONE

Height of Structure 36ft ft.

Area — Largest Floor 127,025 sq. ft.

New Bldg. Area/All Floors 21,309 sq. ft.

Volume of New Structure 240,385 cu. ft.

Max. Live Load _____

Max. Occupancy Load 4,070 persons

Constr. Class Present II B Proposed II B

If Industrialized Building:

State Approved _____ HUD _____

Est. Cost of Bldg. Work: _____

1. New Bldg. _____

2. Rehabilitation _____

3. Total (1 + 2) _____

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

CASCO has issued a change
Bulletin # 1B (Site and Building)
Dated 1-18-09.

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that am the (agent of) owner of
report and am authorized to make this application.

Signature _____

For Home Depot

Date Received
Control #

Date Issued
Permit #

09-0158 fd
009-000746

8-10-09

FEE (Office Use Only)

COMMERCIAL

Administrative Surcharge \$	1200
Minimum Fee \$	85
State Permit Surcharge Fee \$	
TOTAL FEE \$	

1 White = Inspector Copy
2 Canary = Office Copy
3 Pink = Office Copy
4 Gold = Applicant Copy

(rev. 12/07)



PLUMBING SUBCODE TECHNICAL SECTION

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170 Qualification Code 5
 Work Site Location 1722 1st STATE ROUTE 60
 Owner in Fee PRICK, NOT 08724
 Address THE HIVE DEPOT
3096 HAMILTON BLVD.
S. PLAINFIELD, NJ 07080
 Tel (732) 926-3626
 Contractor CAICO/Contractor to follow
 Address _____
 Tel () _____ FAX () _____
 Contractor License No. _____
 Federal Emp. No. _____

B. PLUMBING CHARACTERISTICS

Use Group Present M Proposed M
 Building Sewer Size 8" Public Sewer ✓ Private Septic _____
 Water Service Size 3/4" Public Water ✓ Private Well _____
 Est. Cost of Plumbing Work \$ 109,000.00 \$275,000.00

JOB SUMMARY (Office Use Only)

PLAN REVIEW	INSPECTIONS	Dates (Month/Day)
☐ No Plans Required	Type:	Failure Failure Approval Initial
Joint Plan Review Required:	Slab	02-25-09 PA
☐ Building ☐ Electric	Rough	06-26-09 PA
☐ Fire ☐ Elevator	Water	
☐ Plumbing Plans Approved	Sewer	04-03-09 PA
Date: _____	Gas Equipment	
Approved by: _____	Gas Piping	06-23-09 PA
SUBCODE APPROVAL	TRASH-DRAIN	03-19-09 PA
☐ CO ☐ CCO ☐ CA	Fuel Oil Piping	
Date: <u>2-16-09</u>	Solar	
Approved by: <u>CAICO</u>	TCO	02-01-09 PA
	HAAC	02-01-09 PA

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature
☐ Licensed Plumbing Contractor ☒ Exempt Applicant



D. TECHNICAL SITE DATA (List of all fixtures,)

NO.	FIXTURE/EQUIPMENT	DATE RECEIVED
0	Water Closet	
0	Urinal/Bidet	
0	Bath Tub	
0	Lavatory	
0	Shower	
0	Floor Drain	
0	Sink	
0	Dishwasher	
0	Drinking Fountain	
0	Washing Machine	
0	Hose Bibbs & Hose Reels	
0	Water Heater	
0	Fuel Oil Piping	
0	Gas Piping	
0	LP Gas Tank	
0	Steam Boiler	
0	Hot Water Boiler	
0	Sewer Pump (SINK)	
0	Interceptor/Separator	
0	Backflow Preventer	
0	Greasetrap	
0	Sewer Connection (EXIST)	
0	Water Service Connection (EXIST)	
0	Stacks (VTR)	
0	Other WATER & IRREGULARITIES	
0	Other WIND MACHINE/COPPER	

Administrative Surcharge	\$
Minimum Fee	\$
State Permit Surcharge Fee	\$
TOTAL FEE	\$

COMMERCIAL

Date Received _____
 Control # _____
 Date Issued _____
 Permit # _____

02-02-09 PA

SLAB FOR UNISEX BATH & UTILITY ROOM
+ GARG-BATH ROOMS OK

02-10-09 PA

- ① DEMO + CAP PORTIONS OF EXISTING U/G IS OK. COE WORKS PLAN OK. SEE WORKS PLAN
- ② SEWER FOR DRINKING FOUNDATION BY OLD ENTRANCE IS OK
- ③ SLAB WORK COMPLETE IN BLDG EXCEPT FOR OIL SEPARATOR + FLOOR DRAIN

02-25-09 PA

- ① OIL SEPARATOR / FLOOR DRAIN INSTALLED - SLAB COMPLETE + ROOF DRAINING OK IN BLDG.
- ② TRENCH DRAIN LOADING-DOCK AREA OK!

03-31-09 PA

ROUGH FOR BOTH TOILET ROOMS
AND LOUNGE SINK ONLY - OK

04-03-09 PA

- ① GARDEN CENTER TRENCH DRAINING
+ STORM PIPING UNDERGROUND COMPLETED

06-24-09 PA

- ① DRINKING FOUNDATION NOT READY - OK - 06-26-09 PA - ROUGH COMPLETE

07-01-09 PA

- ① PAINT GAS PIPING ON ROOF AND NUMBER ROOF TOP CHUTE - OK

- ② LADIES ROOM BARRIER FREE WALL @ 38 3/4 HFT - OK

- ④ MEN'S ROOM OK - REST OF BUILDING NOT INSPECTION OK

- ⑤ RECOMMEND TCO - 60 DAYS

07-13-09 PA

- ① FIRE BACKFLOW TEST RESULTS OK - 07-14-09 PA

- ② TOOL MAINTENANCE ROOM SINK NO HOT WATER - OK

- ③ DRINKING FOUNDATION BY GARDEN CENTER NO WATER - OK

PERMIT OUTLEAD
08-26-08 03-19-09 OK PA



PLUMBING SUBCODE
TECHNICAL SECTION



Change of Contractor
12/22/08
Date Received
Control #

69-0158
1-30-09

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION, WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location 1722 Route 88

Owner in Fee: Home Depot

Tel. (____) _____ e-mail _____

Address _____

Contractor: Competitive P&H Inc Tel. (732) 560 3871

Address 137 Ward Ave Middlesex NJ e-mail _____

Contractor License No. 10247 08846 Exp. Date 06/09

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. 02-3470443 FAX: (732) 560-9762

B. PLUMBING CHARACTERISTICS

Use Group Present _____ Proposed _____

Building Sewer Size _____ Public Sewer _____ Private Septic _____

Water Service Size _____ Public Water _____ Private Well _____

Est. Cost of Plumbing Work \$ 0

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☐ No Plans Required

Joint Plan Review Required:

☐ Building ☐ Electric

☐ Fire ☐ Elevator

☐ Plumbing Plans Approved

Date: 12/22/08

Approved by: _____

SUBCODE APPROVAL

☐ CO ☐ CCO ☐ CA

Date: _____

Approved by: _____

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

Licensed Plumbing Contractor ☐ Exempt Applicant

D. TECHNICAL SITE DATA (List of all fixtures.)

NO. _____

FIXTURE/EQUIPMENT

Water Closet

Urinal/Bidet

Bath Tub

Lavatory

Shower

Floor Drain

Sink

Dishwasher

Drinking Fountain

Washing Machine

Hose Bibb

Water Heater

Fuel Oil Piping

Gas Piping

LP Gas Tank

Steam Boiler

Hot Water Boiler

Sewer Pump

Interceptor/Separator

Backflow Preventer

Greasetrap

Sewer Connection

Water Service Connection

Slacks

Other

Other

Other

Other

Other

Other

Other

Other

Other

Other

Other

Other

Other

Other

Other

FEE (Office Use Only)

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____

\$ _____



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Physical Connection Test & Maintenance Report

Date of test 07 / 07 / 09

Certification expires 1 year from date of test.

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 Days of each test and Inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To:

From: (Name of Permit Holder)

Home Depot #0912

Route 70 and Route 88

Brick, NJ

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C.7:10-10.6 and is certified to be in compliance with this regulation.

Description of Valve

Location of Valve

Manufacturer: Watts

Sprinkler Control Room

Model Number: 009M2 ☒ RPZ ☐ DCVA ☐ PVB

Irrigation Main

Serial Number: A56003 Size 2 in.

Tested by:
Pan Metro Services
Edison, NJ 08817
732-393-0100

Comments and Notations:

	PRESSURE TEST			INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE	
	DOUBLE CHECK VALVE			ASSEMBLY	
	1 st Check	2 nd Check	Relief Valve	1 st Check	2 nd Check
Initial Test	Closed Tight ☒ at 10.0 psid	Closed Tight ☒ at ____ psid	Opened at 3.2 psid	OK ☐	OK ☐
Passed ☒	Leaked ☐	Leaked ☐		Failed ☐	Failed ☐
Failed ☐	No. 2 Shut-off Valve Closed Tight ☒ Leaked ☐ By-pass used ☐		Did Not Open ☐		
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐ ____ psid	Closed Tight ☐ ____ psid	Opened at ____ psid	OK ☐	OK ☐

The Results Shown Above are Certified to be True

Witnesses to test and inspection

Certified Testers Name: Clifford Lyle Blevins

Name: _____ Title: _____

Certified Testers Signature: Clifford L. Blevins

Representing: _____

Certifying Authority: New England Water Works Association

Name: _____ Title: _____

Cert. ID#: 3829 Exp. Date: 10-31-09

Representing: _____



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Physical Connection Test & Maintenance Report

Date of test 07 / 07 / 09

Certification expires 1 year from date of test.

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 Days of each test and Inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To:

From: (Name of Permit Holder)

Home Depot #0912

Route 70 and Route 88

Brick, NJ

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C.7:10-10.6 and is certified to be in compliance with this regulation.

Description of Valve

Manufacturer: Watts

Model Number: 009M2 ☒ RPZ ☐ DCVA ☐ PVB

Serial Number: A57389 Size 2 in.

Comments and Notations: _____

Location of Valve

Sprinkler Control Room

Domestic Main

Tested by:
 Pan Metro Services
 Edison, NJ 08817
 732-393-0100

	PRESSURE TEST			INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE ASSEMBLY	
	DOUBLE CHECK VALVE		Relief Valve		
	1 st Check	2 nd Check		1 st Check	2 nd Check
Initial Test	Closed Tight ☒	Closed Tight ☒	Opened at 2.6 psid	OK ☐	OK ☐
Passed ☒	at 8.2 psid	at ____ psid			
Failed ☐	Leaked ☐	Leaked ☐	Did Not Open ☐	Failed ☐	Failed ☐
	No. 2 Shut-off Valve Closed Tight ☒				
	Leaked ☐ By-pass used ☐				
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐	Closed Tight ☐	Opened at ____ psid	OK ☐	OK ☐
	____ psid	____ psid			

The Results Shown Above are Certified to be True

Certified Testers Name: Clifford Lyle Blevins

Certified Testers Signature: Clifford L. Blevins

Certifying Authority: New England Water Works Association

Cert. ID#: 3829 Exp. Date: 10-31-09

Witnesses to test and inspection

Name: _____ Title: _____

Representing: _____

Name: _____ Title: _____

Representing: _____



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Quarterly Physical Connection Test & Maintenance Report

1 st Quarter ☐ 04/01-06/30	2 nd Quarter ☐ 07/01-09/30	3 rd Quarter ☐ 10/01-12/31	4 th Quarter ☐ 01/01-03/31
--	--	--	--

Date of test 7/13/09

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 days of each test and inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To: Home Dept # 0912
1722 Rt 88
Brick NJ, 08724

From: (Name of Permit Holder)
Fire Tech Automatic Sprinkler
121 Blackwood Barnsboro Rd
Sewell NJ 08080
JAMES W Kennedy

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C. 7:10-10.6 and is certified to be in compliance with this regulation.

Description of Valve
 Manufacturer: AMES ☒ RPBZ ☐ DCVA
 Model Number: 400055 Size: 8' in.
 Serial Number: 122636
 Comments and Notations: NEW

Location of Valve
Fire Pump Room

	PRESSURE TEST			INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE ASSEMBLY	
	1 st Check	2 nd Check	Relief Valve	1 st Check	2 nd Check
Initial Test	Closed Tight ☒ at <u>7</u> psid	Closed Tight ☒ at <u>6</u> psid	Opened at <u>2.5</u> psid	OK ☐	OK ☐
Passed ☒	Leaked ☐	Leaked ☐	Did Not Open ☐	Failed ☐	Failed ☐
Failed ☐	No. 2 Shut-off Valve Closed Tight ☒ Leaked ☐	By-pass Used ☐			
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐ psid	Closed Tight ☐ psid	Opened at psid	OK ☐	OK ☐

The Results Shown Above are Certified to be True

Witnesses to test and inspection

Certified Testers Name: JAMES W Kennedy III Name: _____ Title: _____

Certified Testers Signature: [Signature] Representing: _____

Certifying Authority: ASSE Name: _____ Title: _____

Cert. ID #: 9513 Exp. Date: 4/30/2011 Representing: _____



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION, WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location 1722 NJ STATE ROUTE 88

Owner in Fee: THE HOME DEPOT

Tel. (732) 926-3026 e-mail bruce_balgichemedepot.com

Address 3096 HAMILTON BLVD, 3 PLAINFIELD, NJ 07060

Contractor: CASECOI contractor to follow Tel. () e-mail _____

Address _____

Contractor License No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: () _____

B. ELECTRICAL CHARACTERISTICS

Use Group Present M Proposed M

[] Pole/Pad # _____ [] Temporary [] Other

Building Occupied as RETAIL STORE Utility Co. JCP&L

Est. Cost of Elec. Work \$ 1,200,000.00

JOB SUMMARY (Office Use Only)

PLAN REVIEW	INSPECTIONS	Dates (Month/Day)
[] No Plans Required	Type:	Failure, Failure, Approval Initial
[] Partial - Underslab Utilities Approved	Rough	See Back
Date: _____ Approved by: _____	Barrier-Free	
☒ Electric Plans Approved	Trench	
Date: <u>12/15/08</u> Approved by: <u>WNV</u>	Temp. Serv.	
Joint Plan Review Required:	Constr. Serv.	
[] Bldg. [] Plumb. [] Fire. [] Elev.	TCO	<u>60 Day</u> <u>7-8-09</u> <u>DD</u>
SUBCODE APPROVAL FOR PERMIT	Other	
Date: _____	Service	<u>5-19-09</u> <u>AD</u>
Approved by: _____	Final	<u>8-2-09</u> <u>00</u>
SUBCODE APPROVAL FOR PERMIT	Barrier-Free	
Date: _____	Temp. Cut-in-Card Date Issued	<u>5-14-08</u>
Approved by: _____	Final Cut-in-Card Date Issued	
SUBCODE APPROVAL FOR CERTIFICATE	Annual Pool Inspection	
[] CO [] CCO [] CA	Date of Grounding and Bonding	
Date: <u>8-1-08</u>	Certification	
Approved by: <u>X8</u>		

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

[] Licensed Elec. Contractor [] Certifd Landscape Irrigation Contr' [X] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

QTY	SIZE	ITEMS
629		Lighting Fixtures
530		Receptacles
75		Switches
1		Detectors
22		Light Poles
49		Motors—Fract. HP
31		Emergency & Exit Lights
30		Communications Points
		Alarm Devices/F.A.C. Panel
TOTAL NUMBERS		
1		Pool Permit/with UW Lights
1		Storable Pool/Spa/Hot Tub
1		KW Elec. Range/Receptacle
1		KW Oven/Surface Unit
1		KW Elec. Water Heater
2		KW Elec. Dryer/Receptacle
1		KW Dishwasher
1		HP Garbage Disposal
1		KW Central A/C Unit
1		HP/KW Space Heater/Air Handler
1		KW Baseboard Heat
2		HP Motors 1/4 HP
7		KW Transformer/Generator
23		AMP Service
1		AMP Subpanels 100-400A
1		AMP Motor Control Center
1		KW Elec. Sign/Outline Light

Administrative Surcharge \$	
Minimum Fee \$	
State Permit Surcharge Fee \$	
TOTAL FEE \$	

COMMERCIAL

FEE (Office Use Only)

Date Received
Control #
Date Issued
Permit #
09-0158
1-30-09

2-3-9

FRONT BACK AREA INSIDE

2-26-9

WALK THRU W/ BUILDING INSP FOR
SPACES OF 2 FROM
& VOLTAGE DROP FOR EQUIPMENT

3-19-09

BACK WALLS ROUGH

OK
DD

3-31-09

SITE LIGHTS REPAIRS

OK
DD

4-2-09

LOW VOLT WIRE BATHS

OK
DD

4-9-09

SITE LIGHT REPAIRS

OK DD

6-1-09

ABOUT CALLING BACK OFFICES

ABOUT CALLING LOBBY DOOR

OK DD

6-9-09

LIGHTS IN GARDEN CENTER

OK DD

6-10-09

LOADING DOCK AREA

OK
DD

6-25-09

PART FINAL OFFICES & BATHS

OK

DD

6-28-09

CON STARTED IN 10 SEC
ALL EM LIGHTS CAME ON

7-14-09

PART FINAL

LOADING DOCK

CAN'T REACH

BATTERY CHARGERS

ROOF TOPS

OK DD

7-22-09

PART FINAL

CASH REG

8-6-09

PART FINAL

GARDEN CENTER

LIGHTING

KITCHENS



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____
Work Site Location Home Depot

Owner in Fee 1722 Route 88
Address ISM e Route 88 LLC
1260 Stetson Road
Piscataway, NJ 08854

Tel () _____
Contractor Coville Electric Service
Address P.O. Box 546
Saddle Brook, NJ

Tel (201) 843-6566 FAX (201) 843-0828
Contractor License No. 9101
Federal Emp. No. 22-0224481

B. ELECTRICAL CHARACTERISTICS

Use Group Present _____ Proposed _____
☐ Pole/Pad # _____ ☐ Temporary ☐ Other _____
Building Occupied as _____ Utility Co. _____
Est. Cost of Elec. Work \$ _____

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS				
			Type:	Failure	Failure	Approval	Initial
☒ No Plans Required <u>2-11-09</u>							
Joint Plan Review Required:							
☐ Building ☐ Plumbing			Rough				
☐ Fire ☐ Elevator			Barrier-Free				
☐ Elec. Plans Approved			Trench				
			Temp. Serv.				
			Constr. Serv.				
Date: _____			TCO				
			Other				
Approved by: _____			Service				
			Final				
			Barrier-Free				
SUBCODE APPROVAL							
☐ CO ☐ CCO ☐ CA			Temp. Cut-in-Card Date Issued				
Date: <u>2-11-09</u>			Final Cut-in-Card Date Issued				
Approved by: _____			Annual Pool Inspection				
			Date of Grounding and Bonding Certification				

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the agent of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature _____

D. TECHNICAL SITE DATA

QTY. SIZE ITEMS

- Lighting Fixtures
- Receptacles
- Switches
- Detectors
- Light Poles
- Motors—Frac. HP
- Emergency & Exit Lights
- Communications Points
- Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

- Pool Permit with UV Lights
- Storable Pool/Spa/Hot Tub
- KW Elec. Range/Receptacle
- KW Oven/Surface Unit
- KW Elec. Water Heater
- KW Elec. Dryer/Receptacle
- KW Dishwasher
- HP Garbage Disposal
- KW Central A/C Unit
- HP/KW Space Heater/Air Handler
- KW Baseboard Heat
- HP Motors 1/+ HP
- KW Transformer/Generator
- AMP Service
- AMP Subpanels
- AMP Motor Control Center
- KW Elec. Sign/Outline Light

Administrative Surcharge \$ _____

Minimum Fee \$ _____

State Permit Surcharge Fee \$ _____

TOTAL FEE \$ _____

Date Received
Control #

Date Issued
Permit #

3/6/09

09-0381

COMMERCIAL



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of the record and am authorized to make this application and perform the work listed on this application.

Date Received 06/15/2009
Date Issued 6-19-09
Control # 09-002073
Permit # 09-01584E

Block 1170 Lot 5 Qualification Code

Work Site Location: 1722 ROUTE 88, Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address: 3096 HAMILTON BLVD, S PLAINFIELD, NJ 07080

Tel. (732) 926-3626

Contractor: Mason Technologies, Inc.

Address: 33 Ranick Road Hauppauge, NY 11788

Tel. (631) 234-5565

Fax. (631) 234-7826

Lic No.

Federal Employee No. 38-3665918

B. ELECTRICAL CHARACTERISTICS

Use Group Present Proposed M

Pole/Pad # Temporary Other

Building Occupied as Utility Co.

Estimated Cost of Electrical Work \$50,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

No Plan Required Date 8-11-08 Initial J.S.

Joint Plan Review Required

Building Plumbing

Fire Elevator

Electrical Plans Approved

Date:

Approved by:

INSPECTIONS

Type: Rough Barrier-Free

Failure: Failure Approval Initial

Trench Temp. Serv.

Constr. Serv.

TCO

Other

Service

Final

Barrier-Free

Temp. Cut-in-Card Date Issued

Final Cut-in-Card Date Issued

Annual Pool Inspection

Date of Grounding and Bonding

Certification

Applicant's Signature/Contractor's Seal and Signature

Licensed Elec Contr

Certified Landscape Irrigation Contr

Exempt Applicant

TECHNICAL SITE DATA

ITEMS

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles

Motors - Fract. HP

Emergency & Exit Lights

Communication Points

Alarm Devices/F. A.C. Panel

TOTAL NUMBERS

Pool Permit/with UW Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptical

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Recepticle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air

KW Baseboard Heat

HP Motors 1/+ HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

FEE (Office Use Only)

Administrative Surcharge

Minimum Fee

State Permit Surcharge Fee

TOTAL FEE

\$145

\$85

U.O.C. 120 (rev 12/07)

Applicant: When submitting this form to your Local Construction Code Enforcement Office, please provide one original plus three photocopies.



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION WHEN CHANGING CONTRACTORS. NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 3 Qualification Code _____
Work Site Location The Home Depot

Owner in Fee: The Home Depot

Tel. (732) 926-3626 e-mail _____

Address 1722 NJ State Route 28 Brick NJ

Contractor: HomeLand Security & Safety Systems Tel. (201) 955-9110

Address 22 Pershing Place e-mail _____

North Arlington, NJ 07031

Contractor License No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: (_____) _____

Use Group _____ Present _____ Proposed _____

[] Pole/Pad # _____ [] Temporary [] Other _____

Building Occupied as _____ Utility Co. _____

Est. Cost of Elec. Work \$ 3,000.00

JOB SUMMARY (Office Use Only)

PLAN REVIEW

[] No Plans Required 3-12-98 AS

[] Partial -Underslab Utilities Approved

Date: _____ Approved by: _____

[] Electric Plans Approved

Date: _____ Approved by: _____

Joint Plan Review Required:

[] Bldg. [] Plumb. [] Fire. [] Elev.

SUBCODE APPROVAL for PERMIT

Date: _____

Approved by: _____

SUBCODE APPROVAL for CERTIFICATE

[] CO [] CCO [] CA

Date: 3-11-98

Approved by: AS

C. CERTIFICATION IN LIEU OF OATH

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

QTY. SIZE

ITEMS

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles

Motors—Fract. HP

Emergency & Exit Lights

Communications Points

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UW Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptacle

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Receptacle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air Handler

KW Baseboard Heat

HP Motors 1/4 HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

Anti Theft System

Date Received
Control #
Date Issued
Permit #

09-0158 K
3/30/09
109-000642

FEE (Office Use Only)

COMMERCIAL

Administrative Surcharge \$

Minimum Fee \$

State Permit Surcharge Fee \$

TOTAL FEE \$

Brick Township
Building Department (732) 262-1027



DRUR # 318-312-996

MUNICIPALITY Brick Township

CUT-IN-CARD

LOCATION 1722 ROUTE 88

UTILITY CO _____

Brick Township, NJ

BLK 1170

LOT 5

OWNER THE HOME DEPOT

OCCUPANT THE HOME DEPOT

"Installation in the above premises has been inspected and is
in accordance with N.E.C., utility and DCA requirements."

☒ FINAL

☐ TEMPORARY

This approval void after ____ days

DESCRIPTION OF SERVICE 1200 amp

INSTALLED BY CASCO

LICENSE NO _____

DATE 05/19/2009

PERMIT # 09-0158

INSPECTOR Donohue

☐ FAXED IN _____

Lic. No: 8914

U.C.C. Form F350B equiv. 1 WHITE-UTILITY 2 CANARY-OFFICE/FILE 3 PINK-OFFICE/CONTRACTOR

Jersey Central
Power & Light
A FirstEnergy Company

417 New Jersey Avenue
Point Pleasant Beach, NJ 08742

732 262 8954

Date: 05/19/09

To: DOUG DONOHUE
BRICK TOWNSHIP
ELECTRICAL INSPECTOR

Inquire location: HOME DEPOT, 1702

The interrupting duty or fault current for the above location will be:

> under 10,000 Amps

☒ over 10,000 Amps

> If over 10,000 Amps - your interrupting duty for the specific
transformer in question will be 32,250 Amps
(transformer size 1500
(977/480V))

Delord Perry
JC P&L Co

Jersey Central
Power & Light
A FirstEnergy Company

417 New Jersey Avenue
Point Pleasant Beach, NJ 08742

Debbie Rumney
Senior Layout Technician
Point Pleasant Line Dept.

732-714-2830
Fax: 732-892-5828

E-Mail: drumney@gpu.com



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code 08734

Work Site Location 1738 Route 88

Owner in Fee: Stonebrook

Tel. (732) 986-3600 e-mail BLR@NJ08734

Address 3096 Hamulton Blvd. So. Plainfield, NJ

Contractor: 1031 PENNSYLVANIA AVE Tel. (908) 486-6886

Address LINDEN ST 07036 e-mail

Contractor License No. 8346 Exp. Date

Home Improvement Contractor Registration No. or Exemption Reason (if applicable):

Federal Emp. ID No. 22 268 5729 FAX: (908) 486-7497

B. ELECTRICAL CHARACTERISTICS

Use Group Present Proposed

☐ Pole/Pad # ☐ Temporary ☐ Other

Building Occupied as Utility Co. 2800

Est. Cost of Elec. Work \$ 2800

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☐ No Plans Required 4-23-97

☐ Partial - Underslab Utilities Approved

Date: Approved by:

☐ Electric Plans Approved

Date: Approved by:

Joint Plan Review Required:

☐ Bldg. ☐ Plumb. ☐ Fire. ☐ Elev.

SUBCODE APPROVAL FOR PERMIT

Date: Final 8-10-09

Approved by: Barrier-Free

SUBCODE APPROVAL FOR CERTIFICATE

☐ CO ☐ CCO ☐ CA

Date: 8-11-09

Approved by: Date of Grounding and Bonding

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

☒ Licensed Elec. Contractor ☐ Certified Landscape Irrigation Contr ☐ Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Date Received 09-01-09
Control # 009-000746
Date Issued 8-10-09
Permit # 09-01667d

QTY. SIZE ITEMS

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles - RELOCATED

Motors—Fract. HP

Emergency & Exit Lights

Communications Points

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UV Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptacle

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Receptacle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air Handler

KW Baseboard Heat

HP Motors 1/+ HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

VEP 120.0 Phase Box

UNDERGROUND

Administrative Surcharge \$ 46

Minimum Fee \$ 5

State Permit Surcharge Fee \$

TOTAL FEE \$

COMMERCIAL



FIRE PROTECTION SUBCODE TECHNICAL SECTION

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170

Lot 5

Qualification Code

Work Site Location 1722 N STATE ROUTE 86

Owner in Fee THE HOME DEPOT

Address 3096 HAMILTON BLVD.

SOUTH PLAINFIELD, NJ 07080

Tel (192) 926-3626

Contractor CASCO / Contract to follow

Address

FAX ()

Fire Protection Equipment, NJ Div of Fire Safety Permit No.

Fire Protection Equipment, NJ Div of Fire Safety Installer No.

Fire Alarm Contractor No.

Federal Emp. No.

B. FIRE PROTECTION CHARACTERISTICS

Use Group: Present M Proposed M Fire Alarm System: [] New or [] Existing

Constr. Class: Present M Proposed M Location of Panel: [] New or [] Existing

Heating System: [X] New or [] Existing [X] HVAC Fire Suppression/Standpipe System:

Type: [X] Gas [] Oil [] Electric [] Solar [] Other [] Location of Main Control Valve: [] New or [] Existing

Location: [] Other [] Location of Main Control Valve: [] New or [] Existing

Fuel Storage tank: CABINET - 100L RENTAL CENTER

Fuel Type: [] Flammable or [X] Combustible Capacity 50 GAL. GASOLINE

Total Cost of Fire Protection Work \$ 150,000.00

JOB SUMMARY (Office Use Only)

PLAN REVIEW

[X] No Plans Required

[] Joint Plan Review Required:

[] Building [] Plumbing

[] Electric [] Elevator

[] Fire Plans Approved

Date: 11-17-89

Approved by: [Signature]

SUBCODE APPROVAL

[] CO [] CCG [] CA

Date: 7-31-01

Approved by: [Signature]

INSPECTIONS

Type: [] Alarm System [] Failure [] Failure [] Approval [] Initial

[] Suppression Sys. [] Failure [] Failure [] Approval [] Initial

[] Standpipe [] Failure [] Failure [] Approval [] Initial

[] Fire Pump [] Failure [] Failure [] Approval [] Initial

[] Pre-Eng. System [] Failure [] Failure [] Approval [] Initial

[] Mechanical [] Failure [] Failure [] Approval [] Initial

[] Smoke Control [] Failure [] Failure [] Approval [] Initial

[] TCO [] Failure [] Failure [] Approval [] Initial

[] Flammable/Combust Tanks [] Failure [] Failure [] Approval [] Initial

[] Fireplace Venting [] Failure [] Failure [] Approval [] Initial

[] Final [] Failure [] Failure [] Approval [] Initial

[] Other [] Failure [] Failure [] Approval [] Initial



C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the duly authorized representative of the applicant and I have read and understand the provisions of the Fire Protection Subcode and I agree to make this application.

[] Certified Contractor [] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK: GAS PIPING

Water Supply Source APRINKERS TOWER

Method of Alarm/Suppression System Supervision

Flammable/Combustible Tanks

Alarm Systems

[] System

[] 110V Interconnected

[] CO Detectors/110V

Alarm Devices (i.e., smoke, heat, pulls, water/flow)

Supervisory Devices (i.e., tamper, low/high air)

Signaling Devices (i.e., horn/strobes, bells)

Other Devices

TOTAL

Suppression Systems

Fire Pump GPM Type

Dry Pipe/Alarm Valves

Pre-action Valves

Sprinkler Heads (Dry and Wet)

Standpipes

Pre-engineered Systems

Wet Chemical

Dry Chemical

CO₂ Suppression

Foam Suppression

FM200 Suppression

Other

Other Systems

Kitchen Hood Exhaust System

Smoke Control System

Fired Appliances [X] Gas or [] Oil

Fireplace Venting/Metal Chimney

Other

Date Received

Control #

Date Issued

Permit #

09-0158
1-30-09

NUMBER

FEE (Office Use Only)

COMMERCIAL

Administrative Surcharge \$

Minimum Fee \$

State Permit Surcharge Fee \$

TOTAL FEE \$



FIRE SUBCODE TECHNICAL SECTION



COMMERCIAL

A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION WHEN CHANGING CONTRACTORS. NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000
Block 1170 Lot 5 Qualification Code _____

Work Site Location: 1722 ROUTE 88, Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address 3096 HAMILTON BLVD S PLAINFIELD NJ 07080

Tel (732) 926-3626

Contractor: FIRE MATERIALS GROUP

Address 2615 S INDUSTRIAL PARK AVENUE TEMPE AZ 85282

Tel (480) 753-5444

Fax _____

Fire Protection Equipment, NJ Div of Fire Safety Permit No. _____

Fire Protection Equipment, NJ Div of Fire Safety Installer No. _____

Fire Alarm Contractor No. P00164

Federal Employee No. _____

B. FIRE PROTECTION CHARACTERISTICS

Use Group Present _____ Proposed _____ M Fire Alarm System: ☐ New or ☐ Existing

Const. Class Present Type I Proposed Type I Location of Panel: _____

Heating Systems: ☐ New or ☐ Existing ☐ HVAC Fire Suppression/Standpipe System: _____

Type: ☐ Gas ☐ Oil ☐ Electric ☐ Solar ☐ New or ☐ Existing Location of Main Control Valve: _____

Location: _____

Fuel Storage Tank:

Fuel Type: ☐ Flammable or ☐ Combustible Capacity _____

Total Cost of Fire Protection Work \$10,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☐ No Plan Required

☐ Joint Plan Review Required

☐ Building ☐ Plumbing

☐ Electrical ☐ Elevator

☒ Fire Plans Approved

Date: 1-12-09

Approved by: [Signature]

SUBCODE APPROVAL

☐ CO ☐ CCO: ☒ CA 1009

Date: 1-12-09

Approved by: [Signature]

INSPECTIONS

Type: _____ Failure _____ Approval _____ Initial _____

Alarm System _____

Suppression System _____

Standpipe _____

Fire Pump _____

Pre-Eng. System _____

Mechanical _____

Smoke Control _____

TCO _____

Final _____

Other _____

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

Applicant's Signature/Contractor's Seal and Signature

☐ Certified Contractor ☐ Exempt Applicant

D. TECHNICAL SITE DATA
DESCRIPTION OF WORK
FIRE SUPPRESSION ALTERATIONS, ADD/REMOVE/RELOCATE TO
MATCH REMODELED BUILDING.
Water Supply Source _____
Method of Alarm/Suppression System Supervision _____

Flammable/Combustible Tanks

Alarm Systems

☐ System

☐ 110V Interconnected

☐ CO Detectors/110V

Alarm Devices (i.e. smoke, heat, pulls, water/flow)

Supervisory Devices (tamper, low/high air)

Signaling Devices (horn/strobes, bells)

Other Devices _____

TOTAL

Suppression Systems

Fire Pump _____ GPM Type 1500

Dry Pipe/Alarm Valves

Pre-action Valves

Sprinkler Heads (Dry and Wet)

Standpipes

Pre-engineered Systems

Wet Chemical

Dry Chemical

CO2 Suppression

Foam Suppression

FM200 Suppression

Other _____

Other Systems

Kitchen Hood Exhaust System

Smoke Control System

Fire Appliances ☐ Gas ☐ Oil

Fireplace Venting/Metal Chimney

Other _____

Administrative Surcharge

Minimum Fee

State Permit Surcharge Fee

TOTAL FEE

Date Received 01/08/2009
Control # C-08-004682+A
Date Issued 1-30-09
Permit # +A 01-0153614



FIRE SUBCODE TECHNICAL SECTION



A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000
Block 1170 Lot 5 Qualification Code _____

Work Site Location: 1722 ROUTE 88 Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address: 3096 HAMILTON BLVD. S PLAINFIELD NJ 07080

Tel: (732) 926-3626

Contractor: ADI SECURITY

Address: 8607 Roberts Drive Suite 150 Atlanta GA 30350

Tel: (678) 585-5822

Fax: _____

Fire Protection Equipment, NJ Div of Fire Safety Permit No. _____

Fire Protection Equipment, NJ Div of Fire Safety Installer No. _____

Fire Alarm Contractor No. _____

Federal Employee No. 22-5818132104

B. FIRE PROTECTION CHARACTERISTICS

Use Group Present Proposed M Fire Alarm System: ☐ New or ☐ Existing

Constr. Class Present Type I Proposed Type I Location of Panel: _____

Heating Systems: ☐ New or ☐ Existing ☐ HVAC Fire Suppression/Standpipe System:

Type: ☐ Gas ☐ Oil ☐ Electric ☐ Solar ☒ New or ☐ Existing

Location of Main Control Valve: _____

Other: _____

Fuel Storage Tank:

Fuel Type: ☐ Flammable or ☐ Combustible Capacity _____

Total Cost of Fire Protection Work \$50,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☐ No Plan Required

☐ Joint Plan Review Required

☐ Building

☐ Plumbing

☐ Electrical

☐ Elevator

☒ Fire Plans Approved

Date: 2-27-09

Approved by: DB

SUBCODE APPROVAL

☐ CO ☐ CCO ☒ CA

81009

KCS

Approved by: _____

Final

Other

INSPECTIONS

Type: _____

Alarm System

Suppression System

Standpipe

Fire Pump

Pre-Eng. System

Mechanical

Smoke Control

TCO

Final

Other

Dates (Month/Day)

Failure Failure Approval Initial

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

1/24/09 1/24/09 1/24/09 1/24/09

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

☐ Certified Contractor

☐ Exempt Applicant

Applicant's Signature/Contractor's Seal and Signature

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

ALARM SYSTEM (BURGLAR OR FIRE) FIRE ALTERATIONS

CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A

WAREHOUSE FOR "MERCANTILE STORE WITH AN EXTERIOR GARDEN

METHOD OF ALARM/SUPPRESSION SYSTEM SUPERVISION

Flammable/Combustible Tanks

Alarm Systems

☐ System

☐ 110v Interconnected

☐ CO Detectors/110v

Alarm Devices (i.e. smoke, heat, pulls, water/flow)

Supervisory Devices (tamper, low/high air)

Signaling Devices (horn/strobes, bells)

Other Devices _____ annunciator

TOTAL _____

Suppression Systems

Fire Pump _____ GPM Type _____

Dry Pipe/Alarm Valves

Pre-action Valves

Sprinkler Heads (Dry and Wet)

Standpipes

Pre-engineered Systems

Wet Chemical

Dry Chemical

CO2 Suppression

Foam Suppression

FM200 Suppression

Other _____

Other Systems

Kitchen Hood Exhaust System

Smoke Control System

Fire Appliances ☐ Gas ☐ Oil

Fireplace Venting/Metal Chimney

Other _____

NUMBER FEE (Office Use Only)

COMMERCIAL

U.C.C.F-147 (rev. 12/07)

Applicant: When submitting this form to your Local Construction Code Enforcement Office, please provide one original plus three photocopies.

Date Received 2/25/2009
Control # C-09-000458
Date Issued 09-0158+B
Permit # 83-10-09

Administrative Surcharge

Minimum Fee

State Permit Surcharge Fee

TOTAL FEE

\$225

4/11/09

1) weather pipe inspection only - no testing performed

6/25/09

2 hr / 200 psi test for interior only

CONNECT

B 2
1170 5

- 1722
RT
EX

Section Copm

Punch list
for fire

Front
Move Stroke

(Replacing)
Pump Section
2 Tempers Bulflow Door

Fire Lane Scribe (No signs
on side)

Fire Safety Plan

Annunciator pump room

Label all fire alarm devices

FDC Sign

Pump test only

Tross roof sign

Calculation plates Fire Sprinkler

Exterior door signs

- Sprinkler
- Alarm Reports
- Pump

fire ext mounting

HUAC Labeling

Strobes exterior

3 Strobes by
bath - lounge
breakroom

compactor head
to be specified
head


a recirculating system. Fire pumps rated larger than 2,500 gpm usually have flow meters for testing. Smaller pumps might need flow meters as well. Sometimes conditions don't permit full water flow o

Full Unit Inspections

Fire pumps (again, all types) should be inspected (and started) at least weekly to check the general condition of the pump, driver and controller. The inspections should include the pump itself, bearings, stuffing box, supply suction and discharge, strainers, pump running and power off alarms, and fuel/power supply. Gasoline fire pump inspections should also include batteries, oil level, cooling system, belts and hose. The general mechanical condition of the engine. Just like your car or truck, the diesel engine driver for a fire pump needs an annual tune-up and other maintenance specified by the manufacturer. An expert diesel mechanic should do this work.

All functions of the fire pump controller should also be tested at least annually. The controller manufacturer should recommend a local expert to assist with these tests. After the tests are completed, you should get a report describing which tests were conducted and settings of all time delay devices. The report should include results for operation of the pump, driver and controller. A trending comparison of year-by-year results is an early indication of problems before they are really serious.

Acceptance Testing



Directing the water flow back into the water supply source is recommended.

What about a newly installed fire pump? I think (and most insurers and Authorities Having Jurisdiction) that a special fire pump acceptance test is needed for every new fire pump installation. NFPA 20 recommends acceptance tests of new fire pump installations and gives specific criteria in Chapter 11 (of the 1999 edition). The typical "three-point test" of the pump characteristic curve is a basic minimum flow test required by NFPA 20. NFPA 20 recommends as many as five test points be taken on acceptance tests.

The fire pump controller unit is also put through its paces on an acceptance test. NFPA 20 calls for six manual starts and six automatic starts, and a minimum run time of 5 minutes for the pump driver. Electric fire pump controllers must also be tested by measuring the voltages and electrical currents under various flow conditions. The 1999 version of NFPA 20 now requires the use of voltmeters and ammeters on fire pump controllers to allow testing to be conducted safely. Diesel pumps must be started on both sets of batteries. The fire pump must run for not less than 60 minutes (total) during all of these tests.

Fire pump experts, including the manufacturers and installer, typically do acceptance tests. Insurers



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Quarterly Physical Connection Test & Maintenance Report

1 st Quarter ☐ 04/01-06/30	2 nd Quarter ☒ 07/01-09/30	3 rd Quarter ☐ 10/01-12/31	4 th Quarter ☐ 01/01-03/31
--	---	--	--

Date of test 7/13/09

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 days of each test and inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To: Home Dept # 0912
1722 Rt 88
Brick NJ 08724

From: (Name of Permit Holder)
Fire Tech Automatic Sprinkler
121 Blackwood - Barnsboro Rd
Seaside NJ 08080
JAMES W Kennedy

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C. 7:10-10.6 and is certified to be in compliance with this regulation.

Description of Valve
 Manufacturer: Ames ☒ RPZ ☐ DCVA
 Model Number: 400055 Size: 8" in.
 Serial Number: 122636
 Comments and Notations: New

Location of Valve
Fire Pump Room

	PRESSURE TEST		Relief Valve	INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE ASSEMBLY	
	1 st Check	2 nd Check		1 st Check	2 nd Check
Initial Test	Closed Tight ☒ at <u>7</u> psid	Closed Tight ☒ at <u>6</u> psid	Opened at <u>2.5</u> psid	OK ☐	OK ☐
Passed ☒	Leaked ☐	Leaked ☐	Did Not Open ☐	Failed ☐	Failed ☐
Failed ☐	No. 2 Shut-off Valve Closed Tight ☒ Leaked ☐ By-pass Used ☐				
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐ psid	Closed Tight ☐ psid	Opened at _____ psid	OK ☐	OK ☐

The Results Shown Above are Certified to be True

Certified Testers Name: JAMES W Kennedy III

Certified Testers Signature: [Signature]

Certifying Authority: ASSE

Cert. ID #: 9513 Exp. Date: 4/30/2011

Witnesses to test and inspection

Name: _____ Title: _____

Representing: _____

Name: _____ Title: _____

Representing: _____



Fire Sprinkler Hydraulic Data Plate

Project: THD-Brick, NJ Date: 7/20/09
Location: System #3 Sys #: 3
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Wet
Density/Area: .6 gpm/sf over 2000 sq. ft. area
Area/Sprinkler: 96.67 sf/sp. used 100 sq. ft. allowed
Mfg: Tyco Model: K17
Sprinkler Data: _____ orifice 1" k-factor 16.8 degree 256
Spkr's Flowing: 21 spkr. Hose: 500 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 459

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 1457.88 gpm @ 77.195 psi
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Teigan Test Date: 4/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height _____ Minimum Clear _____ ft.
Fig. No (231-C): _____ Curve: _____ Aisle Width _____ ft.
Rack Demand: _____ gpm @ _____ psi @ ref. pt. _____
Backflow Preventer: Mfg. Ames Model 4000ss
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD-Brick, NJ Date: 7/20/09
Location: Entrance Canopy Sys #: 3
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Dry
Density/Area: .2 gpm/sf over 1850 sq. ft. area
Area/Sprinkler: 225 sf/sp. used 320 sq. ft. allowed
Mfg: Tyco Model: SW-20
Sprinkler Data: _____ orifice 3/4" k-factor 11.2 degree 200
Spkr's Flowing: 6 spkr. Hose: 250 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 459

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 419.83 gpm @ 58.68 psi
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Telgian Test Date: 6/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height _____ Minimum Clear _____
Fig. No (231-C): _____ Curve: _____ ft. Aisle Width _____
Rack Demand: _____ gpm @ _____ psi @ ref. pt. _____
Backflow Preventer: Mfg. Anes Model 400055
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD-Brick, NJ Date: 7/20/09
Location: High bay garden center Sys #: 3
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Dry
Density/Area: .5 gpm/sf over 2600 sq. ft. area
Area/Sprinkler: 86.42 sf/sp. used 100 sq. ft. allowed
Mfg: Tyco Model: ELO-231
Sprinkler Data: _____ orifice 3/4" k-factor 11.2 degree 286
Spkr's Flowing: 36 spkr. Hose: 500 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 459

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 1753.3 gpm @ 130.09 psi
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Belgian Test Date: 4/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height 16 ft. Minimum Clear Aisle Width 8 ft.
Fig. No (231-C): _____ Curve: _____ Spkr/Level to Flow: _____
Rack Demand: _____ gpm @ _____ psi @ ref. pt. _____
Backflow Preventer: Mfg. Ames Model 4000SS
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD-Brick, NJ Date: 7/20/09
Location: Low Bay Garden Center Sys #: 3
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Dry
Density/Area: .2 gpm/sf over 1900 sq. ft. area
Area/Sprinkler: 95 sf/sp. used 130 sq. ft. allowed
Mfg: Tyco Model: TY-B
Sprinkler Data: _____ orifice 1/2" k-factor 5.6 degree 286
Spkr's Flowing: 20 spkr. Hose: 250 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 459

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 502.696 gpm @ 64.335
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Belgian Test Date: 6/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height _____ Minimum Clear _____ ft.
Fig. No (231-C): _____ Curve: _____ Spkr/Level to Flow: _____
Rack Demand: _____ gpm @ _____ psi @ ref. pt. _____
Backflow Preventer: Mfg. Anes Model 4000ss
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD - Brick, NJ Date: 7/20/09
Location: Drive Thru Canopy Sys #: 3
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8") _____ OR-2(12") _____ EX-1 _____ EX-2 _____
NFPA Standard: _____ System Type: Dry
Density/Area: .2 gpm/sf over 1950 sq. ft. area
Area/Sprinkler: 113.3 sf/sp. used 130 sq. ft. allowed
Mfg: Tyco Model: TK-13
Sprinkler Data: _____ orifice 1/2" k-factor 5.6 degree 286
Spkr's Flowing: 19 spkr. Hose: _____ gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 459

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 628.86 gpm @ 119.108
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Belgian Test Date: 6/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height _____ Minimum Clear _____ ft.
Fig. No (231-C): _____ Curve: _____ Spkr/Level to Flow: _____
Rack Demand: _____ gpm @ _____ psi @ ref. pt. _____
Backflow Preventer: Mfg. Ames Model 4000SS
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD-Brick, NJ Date: 7/20/09
Location: Tool Rental Center Sys #: 1
Contractor: _____ Zone: _____
Address: 1722 Rt. 88 Area: _____
Brick, NJ
Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Grid
Density/Area: .4 gpm/sf over 2000 sq. ft. area
Area/Sprinkler: 96.67 sf/sp. used 100 sq. ft. allowed
Mfg: Tyco Model: ELO-231
Sprinkler Data: _____ orifice 5/4" k-factor 11.2 degree 286
Spkr's Flowing: 25 spkr. Hose: 500 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: _____

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: 1103.49
TOTAL DEMAND BASE OF RISER: 1103.49 @ 41.56 psi
With Hose: 1503.49 gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Teigian Test Date: 4/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height 14 ft. Minimum Clear _____
Fig. No (231-C): _____ Curve: _____ Aisle Width 4 ft.
Rack Demand: _____ gpm @ _____ psi @ ref. pt.
Backflow Preventer: Mfg. Ames Model 4000ss
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THO-Brick, NJ Date: 7/20/09
Location: Aericals Rack Sys #: 2
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Wet
Density/Area: .6 gpm/sf over 2000 sq. ft. area
Area/Sprinkler: 96.67 sf/sp. used 100 sq. ft. allowed
Mfg: Tyco Model: K17/TK-FRB
Sprinkler Data: _____ orifice 1 1/2" k-factor 6.8/56 degree 286/155
Spkr's Flowing: 33 spkr. Hose: 506 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 422-sys2 80-rack

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 1765.28 gpm @ 78.258 psi
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Belgian Test Date: 4/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height 16 ft. Minimum Clear _____ ft.
Fig. No (231-C): _____ Curve: _____ Spkr/Level to Flow: 6
Rack Demand: 378.97 gpm @ 66.009 psi @ ref. pt. BR4
Backflow Preventer: Mfg. Ames Model 40055
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD- Brick, NJ Date: 7/20/09
Location: Combustibles Rack Sys #: 1
Contractor: _____ Zone: _____
Address: _____ Area: _____

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Wet
Density/Area: .6 gpm/sf over 2000 sq. ft. area
Area/Sprinkler: 96.67 sf/sp. used 100 sq. ft. allowed
Mfg: Tyco Model: K17/TY-FRB
Sprinkler Data: _____ orifice 1 1/4" k-factor 168/5.6 degree 286/155
Spkr's Flowing: 34 spkr. Hose: 500 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 477-system 1 80-racks

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 1875.56 gpm @ 44.428 psi
With Hose: _____ gpm With Rack: _____ gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Belgian Test Date: 4/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: _____ Maximum Height 16 ft. Minimum Clear Aisle Width 8 ft.
Fig. No (231-C): _____ Curve: _____ Spkr/Level to Flow: _____
Rack Demand: _____ gpm @ _____ psi @ ref. pt.
Backflow Preventer: Mfg. Ames Model 9000SS
(If Provided)



Fire Sprinkler Hydraulic Data Plate

Project: THD - Brick, NJ Date: 7/20/09
Location: Polystyrenes Rack Sys #: 1
Contractor: _____ Zone: _____
Address: _____ Area: Polystyrenes

Hazard: LIGHT _____ OR-1(8') _____ OR-2(12') _____ EX-1 _____ EX-2 _____
NFPA Standard: 13 System Type: Grid/wet
Density/Area: .6 gpm/sf over 2000 sq. ft. area
Area/Sprinkler: 96.67 sf/sp. used 100 sq. ft. allowed
Mfg: Tyco Model: K17/TV-FRB
Sprinkler Data: _____ orifice 1 1/2" k-factor 1685.6 degree 286/155
Spkr's Flowing: 29 spkr. Hose: 50 gpm allowance
TOTAL SPRINKLERS ON SYSTEM: 477-Sys 1 80-racks

SUMMARY OF FLOW

End Sprinkler Flow: _____ gpm @ _____ psi
Discharge of Flowing Sprinklers: _____
TOTAL DEMAND BASE OF RISER: 1727.68 gpm @ 44.286 psi
With Hose: 2127.68 gpm With Rack: 216.28 gpm

SUPPLY DATA

Location: Hydrant near NE corner of building
Test By: Teigan Test Date: 4/18/06
City: Static 68 psi; Residual 60 psi; Flow 1862 gpm
Fire Pump Rating: 1500 gpm @ 100 psi; Elec. X Diesel _____

PIPE DATA

C-Factor: Aboveground = 120 Underground = 140
Pipe Type: Sched/40 X Lt. Wall X XL _____ CPVC _____ Copper _____

STORAGE

Commodity Class: High hazard Maximum Height 14 ft. Minimum Clear Aisle Width 8 ft.
Fig. No (231-C): _____ Curve: _____ Spkr/Level to Flow: _____
Rack Demand: _____ gpm @ _____ psi @ ref. pt. _____
Backflow Preventer: Mfg. _____ Model _____
(If Provided)

FIRE ALARM SYSTEM RECORD OF COMPLETION

To be completed by the system installation contractor at the time of system acceptance and approval.

1. PROTECTED PROPERTY INFORMATION

Name of property: Home - Dept
Address: _____
Description of property: Retail - Home Improvement
Occupancy type: _____
Name of property representative: _____
Address: _____
Phone: _____ Fax: _____ E-mail: _____
Authority having jurisdiction over this property: _____
Phone: _____ Fax: _____ E-mail: _____

2. FIRE ALARM SYSTEM INSTALLATION, SERVICE, AND TESTING INFORMATION

Installation contractor for this equipment: Altek Security Systems Group
Address: 161 - Lincoln Highway Edison N.J. 08820
Phone: 732-321-0300 Fax: 732-548-6582 E-mail: _____
Service organization for this equipment: _____
Address: _____
Phone: _____ Fax: _____ E-mail: _____
Location of as-built drawings: Service Company Location of historical test reports: _____
Location of system operation and maintenance manuals: _____
A contract for test and inspection in accordance with NFPA standards is in effect as of _____
Contracted testing company: ADT Security Services
Address: 7895 Browning Rd. Pennsauken N.J. 08109
Phone: 856-661-6113 Fax: 856-661-4455 E-mail: _____
Contract expires: _____ Contract number: _____ Frequency of routine inspections: _____

3. TYPE OF FIRE ALARM SYSTEM OR SERVICE

NFPA 72 Chapter Reference of System Type: _____
Name of organization receiving alarm signals with phone numbers (if applicable):
Alarm: ADT Phone: 888-238-2666
Supervisory: ADT Phone: 888-238-2666
Trouble: ADT Phone: 888-238-2666
Entity to which alarms are retransmitted: _____ Phone: _____
Method of retransmission of alarms to that organization or location: _____

FIGURE 4.5.2.1 Record of Completion.

3. TYPE OF FIRE ALARM SYSTEM OR SERVICE (continued)

If Chapter 8, note the means of transmission from the protected premises to the central station:

☒ Digital alarm communicator ☐ McCulloch ☐ Multiplex ☐ 2-way radio ☐ 1-way radio ☐ N/AIf Chapter 9, note the type of connection: ☐ Local energy ☐ Shunt ☐ N/A**3.1 System Software**

Operating system (executive) software revision level: _____

Site-specific software revision date: _____

Revision completed by: _____

4. SIGNALING LINE CIRCUITS

Characteristics of signaling line circuits connected to this system (see NFPA 72, Table 6.4.1):

Quantity: 1 Style: B Class: _____**5. ALARM-INITIATING DEVICES AND CIRCUITS**

Characteristics of initiating device circuits connected to this system (see NFPA 72, Table 6.5):

Quantity: 1 Style: _____ Class: B**5.1 Manual Initiating Devices****5.1.1 Manual Pull Stations**Number of manual pull stations: 1Type of devices: ☒ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/A**5.2 Automatic Initiating Devices****5.2.1 Area Smoke Detectors**Number of smoke detectors: 1Type of coverage: ☐ Complete area ☒ Partial area ☐ Nonrequired partial area ☐ N/AType of devices: ☒ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/AType of smoke detector sensing technology: ☐ Ionization ☒ Photoelectric**5.2.2 Duct Smoke Detectors**Number of duct smoke detectors: N/A

Type of coverage: _____

Type of devices: ☐ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/AType of smoke detector sensing technology: ☐ Ionization ☐ Photoelectric**5.2.3 Heat Detectors**Number of heat detectors: 2Type of coverage: ☐ Complete area ☒ Partial area ☐ Nonrequired partial area ☐ N/AType of devices: ☒ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/A**5.2.4 Sprinkler Waterflow Detectors**Number of waterflow detectors: 5Type of devices: ☒ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/A**5.2.5 Alarm Verification**Number of devices subject to alarm verification: 0Alarm verification on this system is: ☐ Enabled ☒ Disabled ☐ Set for _____ seconds

FIGURE 4.5.2.1 Continued



6. SUPERVISORY SIGNAL-INITIATING DEVICES AND CIRCUITS**6.1 Sprinkler System**Number of valve supervisory switches: 5Type of devices: ☒ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/A**6.2 Fire Pump**Type of fire pump: ☒ Electric ☐ DieselType of fire pump supervisory devices: ☒ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/A**Fire Pump Functions Supervised**☒ Fire pump power ☒ Fire pump running ☒ Fire pump phase reversal ☒ Selector switch not in auto☐ Engine or control panel trouble ☐ Low fuel

Other: _____

6.3 Engine-Driven GeneratorType of generator supervisory devices: ☐ Addressable ☐ Conventional ☐ Coded ☐ Transmitter ☐ N/A☐ Engine or control panel trouble ☐ Generator running ☐ Selector switch not in auto ☐ Low fuel

Other: _____

7. ANNUNCIATORS**7.1 Annunciator 1** ☒ Local ☐ RemoteType: ☒ Addressable ☐ Directory ☐ Graphic ☐ N/A Location: _____**7.2 Annunciator 2** ☐ Local ☐ RemoteType: ☐ Addressable ☐ Directory ☐ Graphic ☐ N/A Location: _____**7.3 Annunciator 3** ☐ Local ☐ RemoteType: ☐ Addressable ☐ Directory ☐ Graphic ☐ N/A Location: _____**8. ALARM NOTIFICATION DEVICES AND CIRCUITS****8.1 Emergency Voice Alarm Service**

Number of single voice alarm channels: _____

Number of multiple voice alarm channels: _____

Number of speakers: _____

Number of speaker zones: _____

8.2 Telephone Jacks

Number of telephone jacks installed: _____

Number of telephone handsets stored on site: _____

Type of telephone system installed: ☐ Electrically powered ☐ Sound powered ☐ N/A**8.3 Nonvoice Audible System**

Characteristics of notification device circuits connected to this system (see NFPA 72, Table 6.5):

Quantity: 20 Style: V Class: B

FIGURE 4.5.2-1 Continued

8. ALARM NOTIFICATION DEVICES AND CIRCUITS (continued)**8.4 Types and Quantities of Nonvoice Notification Appliances Installed**

Bells: _____ With visual device: _____ Horns: 123 With visual device: 64
 Chimes: _____ With visual device: _____ Bells: _____ With visual device: _____
 Visual devices without audible devices: _____ Other (describe): _____

9. EMERGENCY CONTROL FUNCTIONS ACTIVATED

- ☐ Hold-open door releasing devices ☐ Smoke management or smoke control
☐ Door unlocking ☐ Elevator recall ☐ Other _____

10. SYSTEM POWER SUPPLY**10.1 Primary Power**

Nominal voltage: 120 VAC Amps: 20 Amps
 Overcurrent protection: Type Breaker Amps: 1
 Location (of primary supply panelboard): _____
 Disconnecting means location: _____

10.2 Secondary Power

Location: _____ Type: _____ Nominal voltage: _____ Current rating: _____
 Number of standby batteries: 2 Amp hour rating: 18 amp hr
 Location of emergency generator: _____
 Location of fuel storage: _____
 Calculated capacity of secondary power to drive the system _____
 In standby mode: _____ In alarm mode: _____

11. RECORD OF SYSTEM INSTALLATION

Fill out after all installation is complete and wiring has been checked for opens, shorts, ground faults, and improper branching, but before conducting operational acceptance tests.

The system has been installed in accordance with the following NFPA standards: (Note any or all that apply.)

☒ NFPA 72 ☐ NFPA 70, National Electrical Code, Article 760

☐ Manufacturer's published instructions ☐ Other (please specify): _____

System deviations from referenced NFPA standards: _____

Signed: [Signature] Printed name: Joe Vieira Date: 7-24-09
 Organization: ALTEL Security System Title: President Phone: _____

12. RECORD OF SYSTEM OPERATION

All operational features and functions of this system were tested by or in the presence of the signer shown below, on the date shown below, and were found to be operating properly in accordance with the requirements of:

☐ NFPA 72 ☐ NFPA 70, National Electrical Code, Article 760

☐ Manufacturer's published instructions ☐ Other (please specify): _____

☐ Documentation in accordance with Inspection and Testing Form (Figure 10.6.2.3) is attached

Signed: _____ Printed name: _____ Date: _____
 Organization: _____ Title: _____ Phone: _____

FIGURE 4.6.2.1 (Continued)

13. CERTIFICATIONS AND APPROVALS**13.1 System Installation Contractor**

This system as specified herein has been installed and tested according to all NFPA standards cited herein.

Signed: [Signature] Printed name: Joe Vienna Date: 7-24-09
Organization: Attek Security Title: _____ Phone: 732-351-5300

13.2 System Service Contractor

This system as specified herein has been installed and tested according to all NFPA standards cited herein.

Signed: _____ Printed name: _____ Date: _____
Organization: _____ Title: _____ Phone: _____

13.3 Central Station

This system as specified herein will be monitored according to all NFPA standards cited herein.

Signed: _____ Printed name: _____ Date: _____
Organization: _____ Title: _____ Phone: _____

13.4 Property Representative

I accept this system as having been installed and tested to its specifications and all NFPA standards cited herein.

Signed: _____ Printed name: _____ Date: _____
Organization: _____ Title: _____ Phone: _____

13.5 Authority Having Jurisdiction

I have witnessed a satisfactory acceptance test of this system and find it to be installed and operating properly in accordance with its approved plans and specifications, its approved sequence of operations, and with all NFPA standards cited herein.

Signed: _____ Printed name: _____ Date: _____
Organization: _____ Title: _____ Phone: _____

FIGURE 4.5.2.1 Continued

ALL FIRE ALARM SYSTEM CIRCUIT WIRING MUST ANNUNCIATE A TROUBLE SIGNAL DURING OPEN AND GROUND FAULT CONDITIONS. ADDITIONALLY ALL OUTPUT CIRCUITS ARE REQUIRED TO ANNUNCIATE A TROUBLE SIGNAL DURING A WIRE TO WIRE SHORT CONDITION. THE FIRE ALARM SYSTEM WILL BE TESTED BY THE

Fire Pump Acceptance Report

Property of Home Depot	Acct No.	Index No-A/C
----------------------------------	----------	--------------

City & State Brick, NJ	Insurance Company FMEA D.O.
---------------------------	--------------------------------

Conferred with	Title	Tested by Fire Tech	Date 07/01/09
----------------	-------	------------------------	------------------


PUMP	Shaft Horizontal X Vertical	Manufacturer Armstrong	Approved X Yes No	Shop or Serial No 613819	Model 8x8x15FM
	Rated GPM 1500	Rated Head (PSI) 100	Rated RPM 1780	Suction from Tank	Tank Size

IF VERTICAL TYPE	Vertical Distance Discharge Gauge to Water Level	Static	RIGHT ANGLE GEAR DRIVE	Manufacturer	Shop or Serial No	Approved Yes No
		FT		Model or Type	Performance Smooth Rough	
		Pumping				

DRIVER	Manufacturer Weg	Approved X Yes No	Shop or Serial No 125180P3E40 570	Model or Type ODP	Rated HP 125	Rated RPM 1775
	Electric Motor	Rated Volt 230/460	Operating Volt 480	Rated FL Amps 142	Amps at 150% 154	Phase 3

CONTROLLER	Manufacturer Metron	Approved X Yes No	Start psi 140 Manual	X Press Drop	Stop psi 155 Manual	Jockey Pump X Yes On psi 155
	Shop or Serial No NA09N411611	Model or Type MP435125480C	X Auto	Water Flow	X Auto	No Off psi 170

Speed RPM	Discharge Pressure PSI	Suction Pressure PSI	Net Head PSI	Streams			Gallons Per Minute	Percent of Rated Capacity	Volts	Amps
				No	Size	Pitot Press.				
1792	168	57	111	0	0	Churn	0	0%	473	72
1788	158	49	109	2	1 ¼ "	18 18	772	51%	474	83
1781	135	35	100	3	1 ¼ "	32 32 32	1542	102%	471	133
1778	104	14	90	4	1 ¾ "	38 28 40 42	2206	147%	470	154



Notes:

Fire Pump Acceptance Report

Property of Home Depot	Acct No.	Index No-A/C
----------------------------------	-----------------	---------------------

City & State Brick, NJ	Insurance Company	FMEA D.O.
--------------------------------------	--------------------------	------------------

Conferred with	Title	Tested by Fire Tech	Date 07/01/09
-----------------------	--------------	-------------------------------	-------------------------


PUMP	Shift Horizontal X Vertical	Manufacturer Armstrong	Approved X Yes No	Shop or Serial No 613819	Model 8x8x15FM	
	Rated GPM 1500	Rated Head (PSI) 100	Rated RPM 1780	Suction from Tank	Tank Size	Tank Height

IF VERTICAL TYPE	Vertical Distance Discharge Gauge to Water Level	Static FT	RIGHT ANGLE GEAR DRIVE	Manufacturer	Shop or Serial No	Approved Yes No
		Pumping		Model or Type	Performance Smooth Rough	
		FT				

DRIVER	Manufacturer Weg	Approved X Yes No	Shop or Serial No 125180P3E40 570	Model or Type ODP	Rated HP 125	Rated RPM 1775	
	Electric Motor	Rated Volt 230/460	Operating Volt 480	Rated FL Amps 142	Amps at 150% 154	Phase 3	Cycles 60

CONTROLLER	Manufacturer Metron	Approved X Yes No	Start psi 140 Manual	X Press Drop	Stop psi 155 Manual	Jockey Pump X Yes On psi 155
	Shop or Serial No NA09N411611	Model or Type MP435125480C	X Auto	Water Flow	X Auto	No Off psi 170

Speed RPM	Discharge Pressure PSI	Suction Pressure PSI	Net Head PSI	Streams			Gallons Per Minute	Percent of Rated Capacity	Volts	Amps
				No	Size	Pilot Press.				
1792	168	57	111	0	0	Churn	0	0%	473	72
1788	158	49	109	2	1 3/4"	18 18	772	51%	474	83
1781	135	35	100	3	1 3/4"	32 32 32	1542	102%	471	133
1778	104	14	90	4	1 3/4"	38 28 40 42	2206	147%	470	154



Notes:

KOHLER. POWER SYSTEMS

Startup Notification

Follow the startup checklist on the back of this form. Then complete the form.

This form is required for coverage under the Kohler limited warranty and must be completely filled out at the time of initial startup. Representatives of the distributor/dealer and owner must sign the notification form. **Signing this form represents acceptance of the unit and that all information on the startup form is correct.** Return a copy of the completed form to the Kohler Co. within 60 days of the startup date.

Startup Date

mo. 6 day 4 yr. 09

Telephone	
732 774 1058	
Company Name	
COOPER POWER SYSTEMS	
Address	
1924 HECK AVE	
City	
NEPTUNE	
State	
NJ	
ZIP/Postal Code	
07753	
Country	
USA	

Telephone	
Company Name/Owner	
Home Depot # 912	
Address of Unit Location	
465 RTE 70 W	
City	
BRICK	
State	
NJ	
ZIP/Postal Code	
08723	
Country	
USA	
Round-trip miles from nearest authorized Kohler servicing distributor/dealer to the power system equipment:	
30	

Generator Set and Engine Nameplate Information				
	Generator Set No. 1	Engine No. 1	Generator Set No. 2	Engine No. 2
Serial No.	2147092	06R0969222		
Model No.	250RE0200	600 Series		
Spec No.	G41933 GA2			

Application Information (one item in each column must be checked)		
☒ Industrial	☒ Mobile/Towable/Trailer-Mounted	☐ Prime
☐ Residential/Commercial	☒ Stationary	☐ Rental
		☒ Standby

ATS and Switchgear Information					
	ATS No. 1	ATS No. 2	ATS No. 3	ATS No. 4	Switchgear
Serial No.	K2241073	K2222954			
Spec No.					
Contactor Serial No.	1548837-1	1551240-14			
Model No.					

Kohler Representative's Name (print)	Owner Representative's Name (print)
R. DELAHANTY	RANDY P. L. S.
Kohler Representative's Signature and Date	Owner Representative's Signature and Date
<u>YR. 5</u> mo. <u>6</u> day <u>4</u> yr. <u>09</u>	<u>[Signature]</u> mo. <u>6</u> day <u>4</u> yr. <u>09</u>

Form Distribution:

Mail WHITE copy to:
Warranty Department, MS 072, Kohler Co., Kohler, WI 53044

PINK copy: Distributor

YELLOW copy: Owner's Representative

K-625 (1/07e)

Cooper Power Systems

A Division of Cooper Electric Supply Co.

1924 Heck Avenue
Neptune, NJ 07753
(732) 774-1058 (800) 843-6435
Fax (732) 774-8360

21 PineAire Drive
Bay Shore, NY 11706

EMERGENCY GENERATOR REPAIR ORDER

BILL TO:
NIKON POWER C/O
Home Depot 912
465 RT 70
BRICK NJ

DATE 6 8 09

MILEAGE _____
LABOR _____
TRAVEL _____

W/O _____
RUNNING HOURS 3.8
ANTIFREEZE PROTECTION -40°F

GEN. MFG. <u>KOHIER</u>	MOD. # <u>250RE0200</u>	SPEC. # <u>GM 41935 GA2</u>	SER. # <u>2147092</u>
ENG. MFG. <u>DETROIT</u>	MOD. # <u>6063HW35</u>	SPEC. # _____	SER. # <u>06R0969222</u>
ATS. MFG. <u>KOHIER</u>	KSS DATA <u>00805</u> MOD. # <u>KSS DATA 01501</u>	SPEC. # _____	SER. # <u>K2222954</u> <u>K2241073</u>

BATTERIES:

ACID LEVEL ☐ Full
LOAD CHECK ☐ Fully CHG
CONNECTIONS ☐ TITE
CABLES ☐ CLEAN

COOLING SYSTEM:

LEVEL ☐ Full
ANTIFREEZE ☐ Pmk etc
HOSES ☐ OK
CONN/CLAMPS ☐ All TITE
RADIATOR ☐ CLEAN
PSI TEST ☐ NO LEAKS
BLOCKHEATER ☐ 2500W 208V
FILTERS ☐ _____

LUBE SYSTEM:

LEVEL ☐ Full
OIL CONDITION ☐ CLEAN
FILTER CHANGE ☐ NO
OIL CHANGE ☐ NO

FUEL SYSTEM:

DAY TANK ☐ 450G SUB
LINES ☐ OK
LIFT PUMP ☐ OK
FILTER CHANGE ☐ _____

ENGINE:

BELTS ☐ OK
STARTERS ☐ _____
AIR FILTERS ☐ ↓
BREATHERS ☐ _____

CONTROLS D.C.:

CONNECTIONS ☐ All TITE

CONTROL A.C.:

VOLTAGE REG. ☐ STEADY
WIRING ☐ ↓
CLEANLINESS ☐ _____

GOV. & ACTUATORS:

LINKAGE ☐ DDEC 5
LUBE OIL ☐ ↓
CLEANLINESS ☐ _____

MANUAL OPERATIONAL CHECKS:

OIL PRESSURE ☐ 50
FUEL PRESSURE ☐ _____
WATER TEMP. ☐ 180
OIL TEMP. ☐ 60
FREQUENCY ☐ 277.480
AC VOLTAGE ☐ _____

AUTO SAFETY SHUTDOWNS:

LOW COOLANT ☐ WATER TEMP ☐ _____
OIL PRESSURE ☐ OTHER ☐ _____

LEAKS:

OIL ☐ None
COOLANT ☐ _____
FUEL ☐ ↓
EXHAUST ☐ _____
EXERCISER: DID NOT SET
TIME DELAY ON LINE: 7-8 SEC
TRANSFER OPERATION: Yes
TIME DELAY TO NORMAL: 10M + 1M
TIME DELAY COOL DOWN: 5M AIS
TRANSFERRED ☒ Y ☐ N
LOAD BANK TEST ☐ Y ☒ N

COMMENTS: ON SITE WITH DETROIT DIESEL
THEY REPLACED W/PUMP - I REFILLED WITH
NEW PMX ETC. RAN UNIT WITH/WITHOUT
LOAD. ENG TEMP 180°. NO LEAKS
PRESENT. SIMULATED OUTAGE ALLOWING FULL
CYCLE THRU. UNIT LOCKED OUT ON E STOP
UNTIL FIRE PUMP CONTROLS STARTED

S/C INFO:

CONTACT: _____
PHONE: _____
JOB SITE INFO: _____

PARTS USED:

QTY.	PART #	DESCRIPTION

PARTS NEEDED:

QTY.	PART #	DESCRIPTION

Cooper Power Systems

A Division of Cooper Electric Supply Co.

1924 Heck Avenue
Neptune, NJ 07753
(732) 774-1058 (800) 843-6435
Fax (732) 774-8360

21 PineAire Drive
Bay Shore, NY 11706

EMERGENCY GENERATOR REPAIR ORDER

BILL TO:
NIVON Power Co
Home Depot 912
465 RT 70
BRICK NJ

DATE 6 4 09

MILEAGE _____
LABOR _____
TRAVEL _____

W/O

RUNNING HOURS 1.8

ANTIFREEZE PROTECTION _____

GEN. MFG. KOHLER	MOD. # 250 REOZND	SPEC. # G741935 GA2	SER. # 2147092
ENG. MFG. DETROIT	MOD. # 60 Series	SPEC. #	SER. # 06A0969222
ATS. MFG.	MOD. #	SPEC. #	SER. #

BATTERIES:

ACID LEVEL ☐ OK
LOAD CHECK ☐
CONNECTIONS ☐ 1
CABLES ☐

COOLING SYSTEM:

LEVEL ☐ DRAINED
ANTIFREEZE ☐
HOSES ☐
CONN./CLAMPS ☐
RADIATOR ☐
PSI TEST ☐
BLOCKHEATER ☐
FILTERS ☐

LUBE SYSTEM:

LEVEL ☐ FULL
OIL CONDITION ☐ CLEAN
FILTER CHANGE ☐ OK
OIL CHANGE ☐ OK

FUEL SYSTEM:

DAY TANK ☐ SUB BASE
LINES ☐
LIFT PUMP ☐ ↓
FILTER CHANGE ☐

ENGINE:

BELTS ☐ OK
STARTERS ☐
AIR FILTERS ☐ 1
BREATHERS ☐

CONTROLS D.C.:

CONNECTIONS ☐ OK

CONTROL A.C.:

VOLTAGE REG. ☐ STEADY
WIRING ☐ 1
CLEANLINESS ☐

GOV. & ACTUATORS:

LINKAGE ☐ DISC V
LUBE OIL ☐ 1
CLEANLINESS ☐

MANUAL OPERATIONAL CHECKS:

OIL PRESSURE ☐
FUEL PRESSURE ☐
WATER TEMP. ☐
OIL TEMP. ☐
FREQUENCY ☐ 60
AC VOLTAGE ☐ 277 480

AUTO SAFETY SHUTDOWNS:

LOW COOLANT ☐ WATER TEMP ☐
OIL PRESSURE ☐ OTHER _____

LEAKS:

OIL ☐ NONE
COOLANT ☐
FUEL ☐ ↓
EXHAUST ☐

EXERCISER:

TIME DELAY ON LINE: 7 sec
TRANSFER OPERATION: YES
TIME DELAY TO NORMAL: 10M
TIME DELAY COOL DOWN: 5M ATS
TRANSFERRED ☐ Y ☐ N
LOAD BANK TEST ☐ Y ☐ N

COMMENTS: ON SITE TO PERFORM START-UP
OF EMERGENCY POWER SYSTEM. DURING
LOADED BIDG TEST. COOLANT BEGAN
LEAKING FROM PUMP SEAL THRU
WEEP HOLE. CAPTURED COOLANT INTO
DIRTY CONTAINER. DISCONNECTED BATT
UNTIL REPAIR IS MADE

S/C INFO:

CONTACT: _____
PHONE: _____
JOB SITE INFO: _____

PARTS USED:

QTY.	PART #	DESCRIPTION

PARTS NEEDED:

QTY.	PART #	DESCRIPTION
1	DETROIT	WATER PUMP

7/27/2009 10:00 am

Event History Report

Page 1 of 3

CS# H765107396

Dates 07/27/2009 00:00 to 07/27/2009 23:59

Corp Account# All
Affiliation All
On Test? B
In Service? Y

Site# All

Event Class All
Reporting Group All

Open/Close? N

Date	Zone	Operator	Event	Description	Zone Comment	Additional Info	User	Comment	Alt#
CS# H765107396				Site Name HOME DEPOT 0912	Address 1722 ROUTE 88	BRICK, NJ 08724			
7/27/2009 12:57:43 pm	23		7570	IN-ZONE BYPASS	riser#3				
7/27/2009 12:57:41 pm	23		842	SU-FIRE SYS TRBL	riser#3				
7/27/2009 12:57:38 pm	23		CIR113	RE-RESTORE WATERFL	riser#3				
7/27/2009 12:54:24 pm	E571		7570	IN-ZONE BYPASS					
7/27/2009 12:50:15 pm	23		7894	FA-FIRE-WATERFLOW	riser#3				
7/27/2009 12:46:46 pm	46		CIR203	RE-GATE VALVE SENS	pump discharge				
7/27/2009 11:07:30 am	127		CIR110	RE-RESTORE FA	ABV FACP				
7/27/2009 11:07:28 am	22		CIR113	RE-RESTORE WATERFL	riser#2				
7/27/2009 11:07:25 am	E320		CIE320	TR-SNDR/RELAY TRBL					
7/27/2009 11:07:23 am	R320		CIR320	RE-SNDR/RELAY TRBL					
7/27/2009 11:00:45 am	R320		CIR320	RE-SNDR/RELAY TRBL					
7/27/2009 10:58:20 am	E320		CIE320	TR-SNDR/RELAY TRBL					
7/27/2009 10:55:10 am	32		CIR203	RE-GATE VALVE SENS	riser #2				
7/27/2009 10:51:50 am	E320		CIE320	TR-SNDR/RELAY TRBL					
7/27/2009 10:51:47 am	R320		CIR320	RE-SNDR/RELAY TRBL					
7/27/2009 10:51:40 am	127		54	FA-FIRE-SMOKE DET	ABV FACP				
7/27/2009 10:50:48 am	E320		CIE320	TR-SNDR/RELAY TRBL					
7/27/2009 10:50:44 am	R320		CIR320	RE-SNDR/RELAY TRBL					
7/27/2009 10:48:09 am	22		63	FA-FIRE-WATERFLOW	riser#2				
7/27/2009 10:43:41 am	59		849	SU-SUPERVISORY	fire pump auto				
7/27/2009 10:43:37 am	46		58	SU-TAMPER (FA)	pump discharge				
7/27/2009 10:43:34 am	33		58	SU-TAMPER (FA)	riser #3				
7/27/2009 10:43:30 am	32		58	SU-TAMPER (FA)	riser #2				
7/27/2009 10:42:17 am	E320		CIE320	TR-SNDR/RELAY TRBL					
7/27/2009 10:42:14 am	E305		CIE305	RE-SYSTEM RESET					
7/27/2009 10:42:10 am	E628		CIE628	IN-END PRGRM MODE					
7/27/2009 10:40:30 am	E627		CIE627	IN-START PRGRM MOD					
7/27/2009 10:23:27 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:22:49 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:22:47 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:22:42 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:22:40 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:22:37 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:22:33 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:22:31 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:22:28 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:21:51 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:21:48 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:21:44 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:21:42 am	R333		CIR333	RE-EXP MODULE FAIL					
CS# H765107396									

User# 0
User# 0

CS# H765107396

CS# H765107396
Site# AllDates 07/27/2009 00:00 to 07/27/2009 23:59
Event Class All Reporting Group AllCorp Account# All
Affiliation AllOn Test? B
In Service? Y

Open/Close? N

Date	Zone	Operator	Event	Description	Zone Comment	Additional Info	User	Comment	Alt#
CS# H765107396		Site Name	HOME DEPOT 0912	Address	1722 ROUTE 88	BRICK, NJ	08724		
7/27/2009 10:21:40 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:21:36 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:21:33 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:21:30 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:21:26 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:21:24 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:21:20 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:21:17 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:20:34 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:20:32 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:20:29 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:20:27 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:20:23 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:20:20 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:20:18 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:20:14 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:20:11 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:20:09 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:20:06 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:20:02 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:19:59 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:19:55 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:19:53 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:19:50 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:19:11 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:19:07 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:19:05 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:19:02 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:18:58 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:55 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:18:51 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:48 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:46 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:44 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:18:40 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:35 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:18:33 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:18:31 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:28 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:18:24 am	E333		CIE333	TR-EXP MODULE FAIL					

CS# H765107396

Event History Report

CS# H765107396

Site# All

Dates 07/27/2009 00:00 to 07/27/2009 23:59

Event Class All

Reporting Group All

Corp Account# All
Affiliation All
On Test? B
In Service? Y

Open/Close? N

Date	Zone	Operator	Event	Description	Zone Comment	Additional Info	User	Comment	Alt#
CS# H765107396		Site Name	HOME DEPOT 0912	Address	1722 ROUTE 88	BRICK, NJ 08724			
7/27/2009 10:18:22 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:18:20 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:17:44 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:17:40 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:17:37 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:17:35 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:17:30 am	R333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:17:28 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 10:17:26 am	E333		CIR333	RE-EXP MODULE FAIL					
7/27/2009 10:17:22 am	R333		CIR333	TR-EXP MODULE FAIL					
7/27/2009 10:17:19 am	E333		CIE333	RE-EXP MODULE FAIL					
7/27/2009 10:17:15 am	R333		CIR333	TR-EXP MODULE FAIL					
7/27/2009 10:17:13 am	E333		CIE333	TR-EXP MODULE FAIL					
7/27/2009 9:47:26 am	264		ONTEST	OA-Place on Test				Michael Smith	Cat 3 Expires: 07/27/2009 17:47:00 All Zones
7/27/2009 9:43:51 am	46		58	SU-TAMPER (FA)	pump discharge				
7/27/2009 9:07:27 am	32		58	SU-TAMPER (FA)	riser #2				
7/27/2009 9:03:26 am	33		58	SU-TAMPER (FA)	riser #3				
7/27/2009 9:03:23 am	59		849	SU-SUPERVISORY	fire pump auto				
7/27/2009 8:39:44 am	ARN		ONTEST	OA-Place on Test				JON BODI	Cat 1 ROB SMITH, JON BODI Expires: 07/27/2009 16:00:00 Zones: 21, 22, 23, 24, 25, 31, 32, 33, 34, 35, 40, 41, 42, 43, 44, 45, 46, 47, 56, 57, 58, 59
7/27/2009 8:36:35 am	ARN		1999	OA-PIC HOLDER				JON BODI	per inst
7/27/2009 7:34:03 am	HSR		FC	OA-** Full Clear **					Confirmation
7/27/2009 7:33:17 am	HSR		AA	OA-Acd Access RE:Si					
7/27/2009 7:31:16 am	R320		CIR320	RE-SNDR/RELAY TRBL					
7/27/2009 7:31:13 am	E320		CIE320	TR-SNDR/RELAY TRBL					
7/27/2009 2:16:58 am	E608		CIE608	IN-TIMER TEST W/TRBL				User# 0	

CONTRACTOR'S MATERIAL & TEST CERTIFICATE FOR **A**BOVEGROUND PIPING

PROCEDURE

Upon completion of work, inspection and test shall be made by the contractor's representative and witnessed by an owner's representative. All defects shall be corrected and system left in service before contractor's personnel finally leave the job.

A certificate shall be filled out and signed by both representatives. Copies shall be prepared for approving authorities, owners, and contractor. It is understood the owner's representative's signature in no way prejudices any claim against contractor for faulty material, poor workmanship, or failure to comply with approving authority's requirements or local ordinances.

PROPERTY NAME	Home Depot					DATE	7/27/09					
PROPERTY ADDRESS	RT 88 & RT 77, Brick NJ											
PLANS	ACCEPTED BY APPROVING AUTHORITIES (NAME)											
	Brick Township											
	ADDRESS											
	500 Herbertsville Rd, Brick NJ											
	INSTALLATION CONFORMS TO ACCEPTED PLANS											
	EQUIPMENT USED IS APPROVED ☒ YES ☐ NO											
	IF NO, EXPLAIN DEVIATIONS ☒ YES ☐ NO											
INSTRUCTIONS	HAS PERSON IN CHARGE OF FIRE EQUIPMENT BEEN INSTRUCTED AS TO LOCATION OF CONTROL VALVES AND CARE AND MAINTENANCE OF THIS NEW EQUIPMENT? ☒ YES ☐ NO											
	IF NO, EXPLAIN											
	HAVE COPIES OF THE FOLLOWING BEEN LEFT ON THE PREMISES:											
	1. SYSTEM COMPONENTS INSTRUCTIONS ☒ YES ☐ NO											
	2. CARE AND MAINTENANCE INSTRUCTIONS ☒ YES ☐ NO											
	3. NFPA 13A ☒ YES ☐ NO											
LOCATION OF SYSTEM	SUPPLIES BUILDINGS Pump Room, Rear of Store											
SPRINKLERS	MAKE	MODEL	YEAR OF MANUFACTURE	ORIFICE SIZE	QUANTITY	TEMPERATURE RATING						
	Tyco	K17-231	2009	3/4"	1122	286						
	Tyco	E10-231	2009	3/4"	110	286						
	Tyco	Tytrb	2009	3/4"	80	1550						
	Tyco	Ty-B	2009	3/4"	70	286						
	Tyco	Tytrb	2009	1/2"	32	155						
PIPE AND FITTINGS	Type of Pipe Black Steel											
	Type of Fittings Cast Iron											
ALARM VALVE OR FLOW INDICATOR	TYPE		ALARM DEVICE		MAXIMUM TIME TO OPERATE THROUGH TEST CONNECTION							
	WES		Potter		MODEL		SEC.					
					MIN.		45					
DRY PIPE OPERATING TEST	MAKE		MODEL		SERIAL NO.		MAKE		MODEL		SERIAL NO.	
	Tyco		DPV-1				Tyco		Acc1			
	TIME TO TRIP THRU TEST CONNECTION		WATER PRESSURE		AIR PRESSURE		TRIP POINT AIR PRESSURE		TIME WATER REACHED TEST OUTLET		ALARM OPERATED PROPERLY	
	MIN. SEC.		PSI		PSI		PSI		MIN. SEC.		YES NO	
	Without O.O.D.											
	With O.O.D.		0 15		150 40		26 0 40				✓	
	IF NO, EXPLAIN											

MEASURED FROM TIME INSPECTOR'S TEST CONNECTION IS OPENED.
ISA (10-88) PRINTED W.U.S.A.

(OVER)

Figure 8-1(a).

SYSTEM ACCEPTANCE

13-07

DELUGE & PREACTION VALVES	OPERATION		☐ PNEUMATIC ☐ ELECTRIC ☐ HYDRAULIC PIPING SUPERVISED ☐ YES ☐ NO DETECTING MEDIA SUPERVISED ☐ YES ☐ NO DOES VALVE OPERATE FROM THE MANUAL TRIP AND/OR REMOTE CONTROL STATIONS ☐ YES ☐ NO IS THERE AN ACCESSIBLE FACILITY IN EACH CIRCUIT FOR TESTING IF NO, EXPLAIN				
	☐ YES ☐ NO						
	MAKE	MODEL	DOES EACH CIRCUIT OPERATE SUPERVISION LOSS ALARM	DOES EACH CIRCUIT OPERATE VALVE RELEASE	MAXIMUM TIME TO OPERATE RELEASE		
NA		YES	NO	YES	NO	MIN.	SEC.
200 PSI	HYDROSTATIC: Hydrostatic tests shall be made at not less than 200 psi (13.8 bars) for two hours or 50 psi (3.4 bars) above static pressure in excess of 150 psi (10.3 bars) for two hours. Differential dry-side valve clappers shall be left open during test to prevent damage. All aboveground piping leakage shall be stopped. PNEUMATIC: Establish 40 psi (2.7 bars) air pressure and measure drop which shall not exceed 1-1/2 psi (0.1 bars) in 24 hours. Test pressure shall be at normal water level and air pressure and measure air pressure drop which shall not exceed 1-1/2 psi (0.1 bars) in 24 hours.						
TESTS	ALL PIPING HYDROSTATICALLY TESTED AT <u>200</u> PSI FOR <u>2</u> HRS. IF NO, STATE REASON DRY PIPING PNEUMATICALLY TESTED ☐ YES ☐ NO EQUIPMENT OPERATES PROPERLY ☐ YES ☐ NO DO YOU CERTIFY AS THE SPRINKLER CONTRACTOR THAT ADDITIVES AND CORROSIVE CHEMICALS SODIUM SILICATE OR DERIVATIVES OF SODIUM SILICATE, BRINE, OR OTHER CORROSIVE CHEMICALS WERE NOT USED FOR TESTING SYSTEMS OR STOPPING LEAKS? ☒ YES ☐ NO						
	DRAIN TEST	READING OF GAGE LOCATED NEAR WATER SUPPLY TEST CONNECTION: <u>50</u> PSI		RESIDUAL PRESSURE WITH VALVE IN TEST CONNECTION OPEN WIDE: <u>45</u> PSI			
	UNDERGROUND MAINS AND LEAD-IN CONNECTIONS TO SYSTEM RISERS FLUSHED BEFORE CONNECTION MADE TO SPRINKLER PIPING VERIFIED BY COPY OF THE U FORM NO. 858 ☒ YES ☐ NO OTHER EXPLAIN FLUSHED BY INSTALLER OF UNDERGROUND SPRINKLER PIPING ☒ YES ☐ NO						
BLANK TESTING GASKETS	NUMBER USED	LOCATIONS					NUMBER REMOVED
	<u>0</u>						
	WELDED PIPING ☒ YES ☐ NO IF YES...						
	DO YOU CERTIFY AS THE SPRINKLER CONTRACTOR THAT WELDING PROCEDURES COMPLY WITH THE REQUIREMENTS OF AT LEAST AWS D10.9, LEVEL A-3 ☒ YES ☐ NO DO YOU CERTIFY THAT THE WELDING WAS PERFORMED BY WELDERS QUALIFIED IN COMPLIANCE WITH THE REQUIREMENTS OF AT LEAST AWS D10.9, LEVEL A-3 ☒ YES ☐ NO DO YOU CERTIFY THAT WELDING WAS CARRIED OUT IN COMPLIANCE WITH A DOCUMENTED QUALITY CONTROL PROCEDURE TO INSURE THAT ALL DISCS ARE RETRIEVED, THAT OPENINGS IN PIPING ARE SMOOTH, THAT SLAG AND OTHER WELDING RESIDUE ARE REMOVED, AND THAT THE INTERNAL DIAMETERS OF PIPING ARE NOT PENETRATED ☒ YES ☐ NO						
CUTOUTS (DISCS)	DO YOU CERTIFY THAT YOU HAVE A CONTROL FEATURE TO ENSURE THAT ALL CUTOUTS (DISCS) ARE RETRIEVED? ☒ YES ☐ NO						
HYDRAULIC DATA NAMEPLATE	NAME PLATE PROVIDED		IF NO, EXPLAIN				
	☒ YES ☐ NO						
REMARKS	DATE LEFT IN SERVICE WITH ALL CONTROL VALVES OPEN:						
SIGNATURES	NAME OF SPRINKLER CONTRACTOR <u>Fire Tech Automatic Sprinkler, Inc</u> TESTS WITNESSED BY FOR PROPERTY OWNER (SIGNED) TITLE <u>Superintendent</u> DATE <u>7/8/09</u> FOR SPRINKLER CONTRACTOR (SIGNED) TITLE <u>President</u> DATE <u>7/8/09</u>						
ADDITIONAL EXPLANATION AND NOTES							

13A BACK

Figure 8-1(a) (cont.).

13-0808

Fire Pump Acceptance Report

Property of Home Depot	Acct No.	Index No-A/C
----------------------------------	-----------------	---------------------

City & State Brick, NJ	Insurance Company FMEA D.O.
--------------------------------------	---------------------------------------

Conferred with	Title	Tested by Fire Tech	Date 07/01/09
-----------------------	--------------	-------------------------------	-------------------------


PUMP	Shaft Horizontal ☒ Vertical	Manufacturer Armstrong	Approved ☒ Yes ☐ No	Shop or Serial No 613819	Model 8x8x15FM	
	Rated GPM 1500	Rated Head (PSI) 100	Rated RPM 1780	Suction from Tank	Tank Size	Tank Height

IF VERTICAL TYPE	Vertical Distance Discharge Gauge to Water Level	Static	RIGHT ANGLE GEAR DRIVE	Manufacturer	Shop or Serial No	Approved Yes No
		FT				
	Pumping			Model or Type	Performance Smooth Rough	

DRIVER	Manufacturer Weg	Approved ☒ Yes ☐ No	Shop or Serial No 12518OP3E40570	Model or Type ODP	Rated HP 125	Rated RPM 1775	
	Electric Motor	Rated Volt 230/460	Operating Volt 480	Rated FL Amps 142	Amps at 150% 154	Phase 3	Cycles 60

CONTROLLER	Manufacturer Metron	Approved ☒ Yes ☐ No	Start psi 140 Manual ☒ Auto	Stop psi 155 Manual ☒ Auto	Jockey Pump ☒ Yes ☐ No	psi 155 Manual ☒ Auto
	Shop or Serial No NA09N411611	Model or Type MP435125480C	X Press Drop Water Flow		No Off psi 170	

Speed RPM	Discharge Pressure PSI	Suction Pressure PSI	Net Head PSI	Streams			Gallons Per Minute	Percent of Rated Capacity	Volts	Amps
				No	Size	Pitot Press.				
1792	168	57	111	0	0	Churn	0	0%	473	72
1788	158	49	109	2	1 3/4"	18 18	772	51%	474	83
1781	135	35	100	3	1 3/4"	32 32 32	1542	102%	471	133
1778	104	14	90	4	1 3/4"	38 28 40 42	2206	147%	470	154



Percent Rated Capacity

Notes:



APPLICATION FOR CERTIFICATE

Date Received 09/30/2008
Date Permit Issued 01/30/2009
Control # C-08-004682
Permit # 09-0158
Date Issued

IDENTIFICATION

Block 1170 Lot 5 Qualifier _____
Work Site Location 1722 ROUTE 88 Brick Township, NJ Contractor CASCO
Address 1090 KING GEORGE POST RD EDISON NJ 08837
Owner in Fee THE HOME DEPOT Telephone (732) 661-1400
3096 HAMILTON BLVD S PLAINFIELD NJ 07080 Lic. No. or Bldrs. Reg. No. _____
Telephone (732) 926-3626 Federal Employee No. _____

ACTION

- ☒ CERTIFICATE OF OCCUPANCY
☐ CERTIFICATE OF CONTINUED OCCUPANCY
☐ LEAD HAZARD ABATEMENT CERTIFICATE OF CLEARANCE
☐ TEMPORARY CERTIFICATE OF OCCUPANCY

USE GROUP _____ Previous _____ M _____ Current _____

FINAL COST OF CONSTRUCTION: \$ 5975100

(Include value of any new structure, all on-site improvements, built-in furnishings and fixtures and all the integral equipment exclusive of process or manufacturing equipment.)

A set of "As Built" or amended drawings is required if the building or structure deviates from the approved plans filed with the construction permit. Use space below to describe any deviations from approved plans:

If you are requesting a Temporary Certificate of Occupancy, please explain why in the space below.

DESCRIPTION OF WORK/USE:

Addition/Alteration ALTERATION - -COMMERCIAL CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A "HOME DEPOT" MERCANTILE STORE WITH AN EXTERIOR GARDEN CENTER.

I hereby attest, that to the best of my knowledge, all work has been completed in accordance with the approved plans, permit, and regulations. Incomplete items listed on a Temporary Certificate of Occupancy will be completed by the date on the Certificate.

SIGNED _____

Owner/Agent

RIV CONSTRUCTION Group

☐ OWNER

☒ AGENT *PM*



BUILDING SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1173 Lot 5 Qualification Code _____

Work Site Location 1762 2nd St 08724

Owner in Fee: 1762 2nd St 08724

Tel. (973) 926-3676 e-mail Bruce - 1 My Office 255 134

Address 1762 2nd St 08724 1080

Contractor: 1500 1st St 08724 1080 1080

Address 1500 1st St 08724 1080 1080

Contractor License No. or Builder Registration No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. 235 54-1623072 FAX: (973) 401 5453

JOB SUMMARY (Office Use Only)

PLAN REVIEW	Date	Initial	INSPECTIONS	Type	Failure	Dates (Month/Day)	Approval	Initial
☐ No Plans Required			☐ All	Footings				
☐ Footings/Foundations			☐ Structural/Framework	Foundation				
☐ Exterior			☐ Interior	Slab				
☐ Joint Plan Review Required:			☐ Truss Sys./Bracing	Frame				
☐ Elec. ☐ Plumb. ☐ Fire ☐ Elevator			☐ Barrier-Free	Truss Sys./Bracing				
SUBCODE APPROVAL FOR PERMIT			☐ Insulation	Barrier-Free				
Date:			☐ Finishes -Base Layer	Barrier-Free				
Approved by:			☐ Finishes -Final	Barrier-Free				
SUBCODE APPROVAL FOR CERTIFICATE			☐ Energy	Barrier-Free				
☐ CO ☐ CCO ☐ CA			☐ Mechanical	Barrier-Free				
Date:			☐ TCO	Barrier-Free				
Approved by:			☐ Other	Barrier-Free				
			☐ Final	Barrier-Free				
			☐ Barrier-Free	Barrier-Free				

B. BUILDING CHARACTERISTICS

Use Group Present 101 Proposed 101

No. of Stories 2 Proposed 2

Height of Structure 27 ft. 25 ft.

Area — Largest Floor 21,309 sq. ft.

New Bldg. Area/All Floors 24,309 sq. ft.

Volume of New Structure 24,309 cu. ft.

Max. Live Load 4 7 2 1 2 5

Max. Occupancy Load 4 7 2 1 2 5

Constr. Class Present III Proposed III

If Industrialized Building: State Approved _____ HUD _____

Est. Cost of Bldg. Work: \$ 1,100,000

1. New Bldg. \$ 1,100,000

2. Rehabilitation \$ 1,100,000

3. Total (1+2) \$ 2,200,000

1 White = Inspector Copy
2 Canary = Office Copy
3 Pink = Office Copy
4 Gold = Applicant Copy

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

Signature Bruce - 1 My Office 255 134 Date Issued 8-10-01

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

1762 2nd St 08724 1080 1080

TYPE OF WORK:

- ☐ New Building
- ☐ Addition
- ☒ Rehabilitation
- ☐ Roofing
- ☐ Siding
- ☐ Fence
- ☐ Sign
- ☐ Pool
- ☐ Retaining Wall
- ☐ Asbestos Abatement Subchapter 8
- ☐ Lead Haz. Abatement NJAC 5:17
- ☐ Radon Remediation
- ☐ Other
- ☐ Demolition

FEE (Office Use Only)

Administrative Surcharge \$	
Minimum Fee \$	
State Permit Surcharge Fee \$	
TOTAL FEE \$	



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170 Lot 5 Qualification Code 1758

Work Site Location 1758 Route 88

Owner in Fee Home Depot

Tel. (734) 946-3616 e-mail

Address 3096 Marleton Blvd. E. Plainfield, NJ

Contractor 1031 PENNSYLVANIA AVE Tel. (908) 486-6886

Address Linden NJ 07036 e-mail

Contractor License No. 8346 Exp. Date

Home Improvement Contractor Registration No. or Exemption Reason (if applicable):

Federal Emp. ID No. 22 268 5729 FAX: (908) 486-7497

B. ELECTRICAL CHARACTERISTICS

Use Group Present Proposed

[] Pole/Pad # [] Temporary [] Other

Building Occupied as Utility Co. 8800

Est. Cost of Elec. Work \$ 2800

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☒ No Plans Required 4-23-94

[] Partial - Under/Slab Utilities Approved

Date: Approved by:

[] Electric Plans Approved

Date: Approved by:

Joint Plan Review Required:

[] Bldg. [] Plumb. [] Fire. [] Elev.

Other

SUBCODE APPROVAL FOR PERMIT

Date: Barrier-Free

Approved by:

SUBCODE APPROVAL for CERTIFICATE

[] CO [] CCO [] CA

Date: Annual Pool Inspection

Approved by: Date of Grounding and Bonding Certification

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

☒ Licensed Elec. Contractor [] Certif'd Landscape Irrigation Contr' [] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Date Received 04/10/94
Control # 047-000746
Date Issued 8-10-09
Permit # 09-115571

QTY. SIZE ITEMS

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles - RELOCATED

Motors—Fract. HP

Emergency & Exit Lights

Communications Points

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permit/with UW Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptacle

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Receptacle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air Handler

KW Baseboard Heat

HP Motors 1/4 HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

VERIZON PHONE BOX

UNDERGROUND

Administrative Surcharge \$ 45

Minimum Fee \$ 2

State Permit Surcharge Fee \$

TOTAL FEE \$



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1110 Lot 5 Qualification Code 1785 ACUTE SR

Work Site Location 14114 ACUTE ST ORANGE

Owner in Fee: HAAC GROUP

Tel. (725) 946-4666 e-mail haac@haacgroup.com

Address 2096 Manhattan Blvd. c. 7th floor, NJ

Contractor: ALL PHASE ELECTRIC municipality ZIP CODE 08860

Address 1031 DENNY ROAD AVE e-mail allphase@allphase.com

Contractor License No. 9346 Exp. Date 4/1/2010

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): 4

Federal Emp. ID No. 22 268 5729 FAX: (201) 986-7997

B. ELECTRICAL CHARACTERISTICS

Use Group Present: 1 Temporary 1 Other 1

Building Occupied as 1 Utility Co. 1

Est. Cost of Elec. Work \$ 2800

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☒ No Plans Required 1-23-97

INSPECTIONS
Type: 1 Rough 1 Failure 1 Failure 1 Approval 1 Initial 1

☐ Partial - Under-slab Utilities Approved

Date: 1-23-97 Approved by: 1 Barrier-Free 1

☐ Electric Plans Approved

Date: 1-23-97 Approved by: 1 Temp. Serv. 1 Const. Serv. 1 TCO 1

Joint Plan Review Required:

☐ Bldg. ☐ Plumb. ☐ Fire. ☐ Elev. ☐ Other 1

SUBCODE APPROVAL FOR PERMIT

Date: 1-23-97 Approved by: 1 Barrier-Free 1

SUBCODE APPROVAL FOR CERTIFICATE

☐ CO ☐ CCO ☐ CA

Date: 1-23-97 Temp. Cut-in-Card Date Issued 1

Approved by: 1 Annual Pool Inspection 1 Date of Grounding and Bonding 1

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature

☒ Licensed Elec. Contractor ☐ Certif'd Landscape Irrigation Contr ☐ Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

QTY.	SIZE	ITEMS	FEE (Office Use Only)
		Lighting Fixtures	
		Receptacles	
		Switches	
		Detectors	
		Light Poles - <u>221</u>	
		Motors—Fract. HP	
		Emergency & Exit Lights	
		Communications Points	
		Alarm Devices/F.A.C. Panel	
		TOTAL NUMBERS	
		Pool Permit/with UW Lights	
		Storable Pool/Spa/Hot Tub	
		KW Elec. Range/Receptacle	
		KW Oven/Surface Unit	
		KW Elec. Water Heater	
		KW Elec. Dryer/Receptacle	
		KW Dishwasher	
		HP Garbage Disposal	
		KW Central A/C Unit	
		HP/KW Space Heater/Air Handler	
		KW Baseboard Heat	
		HP Motors 1/4 HP	
		KW Transformer/Generator	
		AMP Service	
		AMP Subpanels	
		AMP Motor Control Center	
		KW Elec. Sign/Outline Light	
		UNDERGROUND	

Date Received 08-10-09
Control # 8-10-09

Date Issued 8-10-09
Permit # 8-10-09

Administrative Surcharge \$ 1

Minimum Fee \$ 1

State Permit Surcharge Fee \$ 1

TOTAL FEE \$ 1



FIRE SUBCODE TECHNICAL SECTION



A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION WHEN CHANGING CONTRACTORS. NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000
Block 1170 Lot 5 Qualification Code
Work Site Location: 1722 ROUTE 88, Brick Township, NJ

Owner in Fee: THE HOME DEPOT
Address 3096 HAMILTON BLVD. S. PLAINFIELD, NJ 07080

Tel. (732) 926-3626
Contractor: ADI SECURITY
Address 8607 Roberts Drive Suite 150 Atlanta GA 30350

Tel. (678) 585-5822 Fax
Fire Protection Equipment, NJ Div of Fire Safety Permit No.
Fire Protection Equipment, NJ Div of Fire Safety Installer No.

Fire Alarm Contractor No.
Federal Employee No. 22-5818132104

B. FIRE PROTECTION CHARACTERISTICS
Use Group Present Proposed M Fire Alarm System: ☐ New or ☐ Existing
Constr. Class Present Type I Proposed Type I Location of Panel:
Heating Systems: ☐ New or ☐ Existing ☐ HVAC Fire Suppression/Standpipe System:
Type: ☐ Gas ☐ Oil ☐ Electric ☐ Solar ☒ New or ☐ Existing
☐ Other Location of Main Control Valve:
Location:

Fuel Storage Tank:
Fuel Type: ☐ Flammable or ☐ Combustible Capacity
Total Cost of Fire Protection Work \$50,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW		INSPECTIONS		Dates (Month/Day)	
Type	Failure	Failure	Approval	Initial	
☐ No Plan Required					
☐ Joint Plan Review Required					
☐ Building ☐ Plumbing					
☐ Electrical ☐ Elevator					
☒ Fire Plans Approved					
Date: 2/27/09					
Approved by: [Signature]					
SUBCODE APPROVAL		Smoke Control			
☐ CO ☐ CCO ☐ CA		TCO			
Date:		Final			
Approved by:		Other			

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

Applicant's Signature/Contractor's Seal and Signature
☐ Certified Contractor ☐ Exempt Applicant

D. TECHNICAL SITE DATA
DESCRIPTION OF WORK
ALARM SYSTEM (BURGLAR OR FIRE) FIRE ALTERATIONS,
CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A
WAREHOUSE FOR MERCANTILE STORE WITH AN EXTERIOR GARDEN-
CENTERED Alarm/Suppression System Supervision

Flammable/Combustible Tanks	NUMBER	FEE (Office Use Only)
Alarm Systems		
☐ System		
☐ 110v Interconnected		
☐ CO Detectors/110v		
Alarm Devices (i.e. smoke, heat, pulls, water/flow)	9	
Supervisory Devices (tamper, low/high air)	13	
Signaling Devices (horn/strobes, bells)	125	
Other Devices	1	
TOTAL	148	\$225.00
Suppression Systems		
Fire Pump GPM Type		
Dry Pipe/Alarm Valves		
Pre-action Valves		
Sprinkler Heads (Dry and Wet)		
Standpipes		
Pre-engineered Systems		
Wet Chemical		
Dry Chemical		
CO2 Suppression		
Foam Suppression		
FM200 Suppression		
Other		
Other Systems		
Kitchen Hood Exhaust System		
Smoke Control System		
Fire Appliances ☐ Gas ☐ Oil		
Fireplace Venting/Metal Chimney		
Other		
Administrative Surcharge		
Minimum Fee		
State Permit Surcharge Fee		
TOTAL FEE		\$225

COMMERCIAL



FIRE SUBCODE TECHNICAL SECTION



A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000
Block 1170 Lot 5 Qualification Code _____
Work Site Location: 1722 ROUTE 88 Brick Township, NJ

Date Received 2/25/2009
Control # C-09-000458
Date Issued _____
Permit # 09-0158+B

Applicant's Signature/Contractor's Seal and Signature
☐ Certified Contractor ☐ Exempt Applicant

Owner in Fee: THE HOME DEPOT
Address 3096 HAMILTON BLVD. S. PLAINFIELD NJ 07080

Tel. (732) 926-3626

Contractor: ADI SECURITY

Address 8607 Roberts Drive Suite 150 Atlanta GA 30350

Tel. (678) 585-5822 Fax _____

Fire Protection Equipment, NJ Div of Fire Safety Permit No. _____

Fire Protection Equipment, NJ Div of Fire Safety Installer No. _____

Fire Alarm Contractor No. _____

Federal Employee No. 22-5818132104

B. FIRE PROTECTION CHARACTERISTICS

Use Group Present Proposed M Fire Alarm System: ☐ New or ☐ Existing
Constr. Class Present Type I Proposed Type I Location of Panel: _____
Heating Systems: ☐ New or ☐ Existing ☐ HVAC Fire Suppression/Standpipe System:
Type: ☐ Gas ☐ Oil ☐ Electric ☐ Solar ☒ New or ☐ Existing
☐ Other _____ Location of Main Control Valve: _____
Location: _____

Fuel Storage Tank:

Fuel Type: ☐ Flammable or ☐ Combustible Capacity _____
Total Cost of Fire Protection Work \$50,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☐ No Plan Required
☐ Joint Plan Review Required
☐ Building ☐ Plumbing
☐ Electrical ☐ Elevator

Date: 2/25/09 Fire Plans Approved
Approved by: OC

SUBCODE APPROVAL
☐ CO ☐ CCO ☐ CA

Date: _____
Approved by: _____
Final _____
Other _____

INSPECTIONS

Type: _____ Failure _____ Approval _____ Initial _____
Alarm System _____
Suppression System _____
Standpipe _____
Fire Pump _____
Pre-Eng. System _____
Mechanical _____
Smoke Control _____
TCO _____
Final _____
Other _____

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK
ALARM SYSTEM (BURGLAR OR FIRE), FIRE ALTERATIONS,
CONVERT AN EXISTING "COSTCO" MERCANTILE BUILDING INTO A
WAREHOUSE FOR MERCANTILE STORE WITH AN EXTERIOR GARDEN-
MOUNTED FIRE Alarm/Suppression System Supervision

Flammable/Combustible Tanks

Alarm Systems

☐ System
☐ 110V Interconnected
☐ CO Detectors/110V
Alarm Devices (i.e. smoke, heat, pulls,
waterflow)

Supervisory Devices (tamper, low/high air) 13

Signaling Devices (horn/strobes, bells) 125

Other Devices annunciator 1

TOTAL 148 \$225.00

Suppression Systems

Fire Pump _____ GPM Type _____

Dry Pipe/Alarm Valves _____

Pre-action Valves _____

Sprinkler Heads (Dry and Wet) _____

Standpipes _____

Pre-engineered Systems

Wet Chemical _____

Dry Chemical _____

CO2 Suppression _____

Foam Suppression _____

FM200 Suppression _____

Other _____

Other Systems

Kitchen Hood Exhaust System _____

Smoke Control System _____

Fire Appliances ☐ Gas ☐ Oil

Fireplace Venting/Metal Chimney _____

Other _____

Administrative Surcharge _____
Minimum Fee _____
State Permit Surcharge Fee _____
TOTAL FEE \$225

COMMERCIAL



BOHLER

ENGINEERING

35 Technology Drive
Warren, NJ 07059
PHONE 908.668.8300
FAX 908.754.4401

August 5, 2009

Via Federal Express

Township of Brick Building Department
401 Chambers Bridge Road
Brick, NJ 08723

Attention: Ken Anderson

RECD AUG 06 2009

RE: Proposed Home Depot Facility #912
Route 70 and Route 88
Township of Brick
Ocean County, NJ
BENJ File No. 050251

Dear Mr. Anderson:


As requested, enclosed please find one (1) signed and sealed Detail Sheet in regard to the above referenced project. The enclosed sheet contains a detail for the light pole foundation which corresponds to the light pole foundation calculations which were previously submitted.

Should you have any questions or require any additional information, please contact our office.

Sincerely,

BOHLER ENGINEERING


Michael A. Albanese


Laurence G. Murphy, P.E.

MA/LGM/an/J:\Home Depot\2005\050251 - Home Depot (Brick)\Letters\tpbldngdept(anderson)01.doc

RECD AUG 05 2009

OTHER OFFICE LOCATIONS:

- | | | | | | |
|------------------------------------|------------------------------|------------------------------------|----------------------------------|-------------------------------------|---------------------------------------|
| • Southborough, MA
508.480.9900 | • Albany, NY
518.438.9900 | • White Plains, NY
914.286.2700 | • Ronkonkoma, NY
631.738.1200 | • Center Valley, PA
610.709.9971 | • Chalfont, PA
215.996.9100 |
| • Philadelphia, PA
215.996.9100 | • Towson, MD
410.821.7900 | • Sterling, VA
703.709.9500 | • Warrenton, VA
540.349.4500 | • Bowie, MD
301.809.4500 | • Fort Lauderdale, FL
954.202.7000 |

CIVIL AND CONSULTING ENGINEERS • SURVEYORS • PROJECT MANAGERS • ENVIRONMENTAL CONSULTANTS • LANDSCAPE ARCHITECTS

www.BohlerEngineering.com

RIV

FAX TRANSMITTAL

CONSTRUCTION GROUP

DATE:

8/5/09

PAGES

5

(including cover sheet)

PROJECT:

Brick NJ

Home Depot

TO:

Allison

FAX#:

732-262-8954

COMPANY:

Brick Township

PHONE:

CC:

FROM:

Tony Conro


RE:

Site Pole Struc. Calculations

COMMENTS:

Allison,

See Attached. Please let me know
when you received.



Office

41 Rt. 34 South Colts Neck, NJ 07722 (732) 431-5484 Fax (732) 431-5483

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
TELEPHONE: (908) 668-8300
FAX: (908) 754-4401

JOB TITLE **THE HOME DEPOT - BRICK**
PROPOSED LIGHT POLE FOUNDATION
JOB NO. J050251 SHEET NO. 1
CALCULATED BY TXL DATE 7/6/2009
CHECKED BY _____ DATE _____

STRUCTURAL CALCULATIONS

FOR

THE HOME DEPOT

1722 NEW JERSEY STATE HIGHWAY ROUTE 88; BLOCK 1170, LOT 5
TOWNSHIP OF BRICK
OCEAN COUNTY, NEW JERSEY

K.B. CAHILL, P.E.
NEW JERSEY LICENSE NO.: 42004

Kath B Cahill

www.StruWare.com

BOHLER ENGINEERING
 35 TECHNOLOGY DRIVE
 WARREN, NEW JERSEY 07059
 TELEPHONE: (908) 668-8300
 FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK

PROPOSED LIGHT POLE FOUNDATION

JOB NO. J050251 SHEET NO.

CALCULATED BY TXL

DATE 7/6/09

CHECKED BY

DATE

Code Search

I. Code: International Building Code 2006

II. Occupancy:

Occupancy Group = U Utility & Miscellaneous

III. Type of Construction:

Fire Rating:

Roof = 0.0 hr
 Floor = 0.0 hr

IV. Live Loads:

Roof angle (θ) 0.00 / 12 0.0 deg
 Roof 0 to 200 sf: 20 psf
 200 to 600 sf: 24 - 0.02 Area
 over 600 sf: 12 psf
 Floor N/A
 Stairs & Exitways 0 psf
 Balcony N/A
 Mechanical N/A
 Partitions N/A



V. Wind Loads: ASCE 7 - 02

Importance Factor 1.00
 Wind speed 113 mph
 Directionality (K_d) 0.85
 Mean Roof Ht (h) 32.0 ft
 Parapet ht above grd 0.0 ft
 Exposure C
 Enclosure Classif. Open Building
 Internal pressure ± 0.00
 Building length (L) 7.5 ft
 Least width (B) 2.3 ft
 K_h case 1 0.996
 K_h case 2 0.996

Topographic Factor (K_{zt})

Topography Flat
 Hill Height (H) 0.0 ft
 Half Hill Length (L_h) 0.0 ft
 Actual H/L_h = 0.00
 Use H/L_h = 0.00
 Modified L_h = 0.0 ft
 From top of crest: x = 0.0 ft
 Bldg up/down wind? downwind
 $H/L_h = 0.00$ $K_1 = 0.000$
 $x/L_h = 0.00$ $K_2 = 0.000$
 $z/L_h = 0.00$ $K_3 = 1.000$
 At Mean Roof Ht:
 $K_{zt} = (1 + K_1 K_2 K_3)^{1/2} = 1.00$

$H < 15 \text{ ft} \times \text{exp } C$
 $\therefore K_{zt} = 1.0$



2D RIDGE or 3D AXISYMMETRICAL HILL

BOHLER ENGINEERING
 35 TECHNOLOGY DRIVE
 WARREN, NEW JERSEY 07059
 TELEPHONE: (908) 668-8300
 FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK
PROPOSED LIGHT POLE FOUNDATION
 JOB NO. J050251 SHEET NO. _____
 CALCULATED BY TXL DATE 7/6/09
 CHECKED BY _____ DATE _____

V. Wind Loads - Other Structures:

Importance Factor	1.00	Wind Speed	113 mph
Height to evaluate pressure (z)	32.0 ft	Exposure	C
Gust Effect Factor (G)	0.85	Kzt	1.00
Kz (case 2)	0.996	Base pressure (qz) =	32.55 Kd psf

A. Solid Freestanding Walls & Solid Signs (& open signs with less than 30% open)

Height	32.0 ft	M =	32.0 ft
Width	7.5 ft	N =	7.5 ft
Dist above ground		M/N =	4.267
to bottom edge	32.0 ft	Cf =	1.20
Directionality (Kd)	0.85		

$F = q_z G C_f A_f = 28.2 \text{ Af}$

$A_f = 7.8 \text{ sf}$
 $F = 220 \text{ lbs}$

Horizontal design eccentricity for signs = 0 to 0.2 times sign width.

Use 30 ft in design

B. Open Signs & Lattice Frameworks (openings 30% or more of gross area)

Width (zero if round)	0.0 ft	Error	
Diameter (zero if rect)	0.0 ft		
Percent of open area		=	0
to gross area	0.0%	Cf =	0.8
Directionality (Kd)	0.85		

$F = q_z G C_f A_f = 0.0 \text{ Af}$

Solid Area: $A_f = 0.0 \text{ sf}$
 $F = 0 \text{ lbs}$

Design sign as solid sign

C. Chimneys, Tanks & Similar Structures

Cross-Section	Round
Directionality (Kd)	0.95
Height (h)	0.0 ft
Width (D)	0.0 ft
Type of Surface	Moderately smooth

$h/D = \#DIV/0!$

$D(qz)^{1.5} = 0.00$

D = diameter or least horizontal dimension of square, hexagonal or octangular at elevation under consideration.
 D' = depth of protruding elements such as ribs and spoilers (in feet) for round structures only.

Round

$C_f = \#DIV/0!$

$F = q_z G C_f A_f = \#DIV/0! \text{ Af}$

$A_f = 0.0 \text{ sf}$

$F = \#DIV/0! \text{ lbs}$

D. Trussed Towers

$\epsilon = 0.27$ (Ratio of solid area to gross area of the tower face under consideration)

Tower Cross Section	square
Member Shape	flat
Directionality (Kd)	1.00

Diagonal wind factor = 1.2

Round member factor = 1.000

Square (wind along tower diagonal)

$C_f = 3.24$

$F = q_z G C_f A_f = 89.6 \text{ Af}$

Solid Area: $A_f = 10.0 \text{ sf}$

$F = 896 \text{ lbs}$

Square (wind normal to face)

$C_f = 2.70$

$F = q_z G C_f A_f = 74.7 \text{ Af}$

Solid Area: $A_f = 0.0 \text{ sf}$

$F = 0 \text{ lbs}$

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
T: (908) 668-8300
F: (908) 754-4401

Title: LIGHT POLE FOUNDATION Job # J050251
Design: TUNG-TO LAM Date: 3:41PM, 6 JUL 09
Description: THE HOME DEPOT
1722 NEW JERSEY STATE HIGHWAY ROUTE 88
Scope: LIGHT POLE FOUNDATION

Rev: 580186
User: KYI-0801434, Ver 5.6.1, 25-Oct-2002
(c)1985-2002 ENERCALC Engineering Software

Pole Embedment in Soil

Page 1

g:\home depot\2006\J050251\structural\J050251

Description Circular pole with Point & Uniform Loads (Two Fixtures @180 degrees)

General Information

Allow Passive	180.00 pcf	Applied Loads...
Max Passive	1,500.00 psf	Point Load
Load duration factor	1.333	distance from base
Pole is Circular		
Diameter	36.000 in	Distributed Load
No Surface Restraint		distance to top
		distance to bottom

234.00 lbs
32.000 ft

23.60 #/ft
32.000 ft
0.000 ft

Summary

Moments @ Surface...		
Point load	7,488.00 ft-#	Total Moment
Distributed load	11,520.00	Total Lateral
		19,008.00 ft-#
Without Surface Restraint...		954.00 lbs
Required Depth	6.383 ft	
Press @ 1/3 Embed...		
Actual	513.20 psf	
Allowable	510.53 psf	

7 ft embedment

7.8 cf EPA

9" pole

RIV

FAX TRANSMITTAL

CONSTRUCTION GROUP

DATE: 8-5-09 # PAGES 5
PROJECT: HOME DEPOT (including cover sheet)
Brick, NJ
TO: Allison FAX#: _____
COMPANY: Brick Twp. PHONE: _____
CC: _____
FROM: Carmine Caruso
RE: Light Pole Calculations

COMMENTS:

Please see calculations for proposed light poles.

Thanks!

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
TELEPHONE: (908) 668-8300
FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK	
PROPOSED LIGHT POLE FOUNDATION	
JOB NO. J050251	SHEET NO. 1
CALCULATED BY TXL	DATE 7/6/2009
CHECKED BY	DATE

STRUCTURAL CALCULATIONS

FOR

THE HOME DEPOT

1722 NEW JERSEY STATE HIGHWAY ROUTE 88; BLOCK 1170, LOT 5
TOWNSHIP OF BRICK
OCEAN COUNTY, NEW JERSEY

K.B. CAHILL, P.E.
NEW JERSEY LICENSE NO.: 42004



BOHLER ENGINEERING

35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
TELEPHONE: (908) 663-8300
FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK

PROPOSED LIGHT POLE FOUNDATION

JOB NO. J050251 SHEET NO.

CALCULATED BY TXL

DATE 7/6/09

CHECKED BY

DATE

Code Search

I. Code: International Building Code 2006

II. Occupancy:

Occupancy Group = U Utility & Miscellaneous

III. Type of Construction:

Fire Rating:

Roof = 0.0 hr
Floor = 0.0 hr

IV. Live Loads:

Roof angle (θ) 0.00 / 12 0.0 deg
Roof 0 to 200 sf: 20 psf
200 to 600 sf: 24 - 0.02 Area
over 600 sf: 12 psf

Floor N/A
Stairs & Exitways 0 psf
Balcony N/A
Mechanical N/A
Partitions N/A

V. Wind Loads: ASCE 7 - 02

Importance Factor 1.00
Wind speed 113 mph
Directionality (K_d) 0.85
Mean Roof Ht (h) 32.0 ft
Parapet ht above grd 0.0 ft
Exposure C
Enclosure Classif. Open Building
Internal pressure ± 0.00
Building length (L) 7.5 ft
Least width (B) 2.3 ft
 K_h case 1 0.996
 K_h case 2 0.996

Topographic Factor (K_{zt})



Topography Flat
Hill Height (H) 0.0 ft
Half Hill Length (L_h) 0.0 ft
Actual $H/L_h = 0.00$
Use $H/L_h = 0.00$
Modified $L_h = 0.0$ ft
From top of crest: $x = 0.0$ ft
Bldg up/down wind? downwind

$H/L_h = 0.00$ $K_1 = 0.000$
 $x/L_h = 0.00$ $K_2 = 0.000$
 $z/L_h = 0.00$ $K_3 = 1.000$

At Mean Roof Ht:

 $K_{zt} = (1 + K_1 K_2 K_3)^2 = 1.00$

$H < 15$ ft; exp C
 $\therefore K_{zt} = 1.0$

**ESCARPMENT****2D RIDGE or 3D AXISYMMETRICAL HILL**

BOHLER ENGINEERING
 35 TECHNOLOGY DRIVE
 WARREN, NEW JERSEY 07059
 TELEPHONE: (908) 668-8300
 FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK
PROPOSED LIGHT POLE FOUNDATION
 JOB NO. J050251 SHEET NO.
 CALCULATED BY TXL DATE 7/6/09
 CHECKED BY DATE

V. Wind Loads - Other Structures:

Importance Factor	1.00	Wind Speed	113 mph
Height to evaluate pressure (z)	32.0 ft	Exposure	C
Gust Effect Factor (G)	0.85	K _z	1.00
K _z (case 2)	0.996	Base pressure (q _z) =	32.55 Kd psf

A. Solid Freestanding Walls & Solid Signs (& open signs with less than 30% open)

Height	32.0 ft	M =	32.0 ft
Width	7.5 ft	N =	7.5 ft
Dist above ground		M/N =	4.267
to bottom edge	32.0 ft	C _f =	1.20
Directionality (K _d)	0.85		

$$F = q_z G C_f A_f = 28.2 \text{ Af}$$

A_f = 7.8 sf
 F = 220 lbs

Horizontal design eccentricity for
 signs = 0 to 0.2 times sign width.

Use 30 ft
 in design

B. Open Signs & Lattice Frameworks (openings 30% or more of gross area)

Width (zero if round)	0.0 ft	Error	
Diameter (zero if rect)	0.0 ft		
Percent of open area		e =	0
to gross area	0.0%	C _f =	0.8
Directionality (K _d)	0.85		

$$F = q_z G C_f A_f = 0.0 \text{ Af}$$

Solid Area: A_f = 0.0 sf
 F = 0 lbs

Design sign as solid sign

C. Chimneys, Tanks & Similar Structures

Cross-Section	Round
Directionality (K _d)	0.95
Height (h)	0.0 ft
Width (D)	0.0 ft
Type of Surface	Moderately smooth

$$h/D = \#DIV/0!$$

$$D(qz)^{0.5} = 0.00$$

D = diameter or least horizontal dimension of square, hexagonal or octagonal at elevation under consideration.
 D' = depth of protruding elements such as ribs and spoilers (in feet) for round structures only.

Round

$$C_f = \#DIV/0!$$

$$F = q_z G C_f A_f = \#DIV/0! \text{ Af}$$

$$A_f = 0.0 \text{ sf}$$

$$F = \#DIV/0! \text{ lbs}$$

D. Trussed Towers

$$e = 0.27 \quad (\text{Ratio of solid area to gross area of the tower face under consideration})$$

Tower Cross Section	square
Member Shape	flat
Directionality (K _d)	1.00

$$\text{Diagonal wind factor} = 1.2$$

$$\text{Round member factor} = 1.000$$

Square (wind along tower diagonal)

$$C_f = 3.24$$

$$F = q_z G C_f A_f = 89.6 \text{ Af}$$

$$\text{Solid Area: } A_f = 10.0 \text{ sf}$$

$$F = 896 \text{ lbs}$$

Square (wind normal to face)

$$C_f = 2.70$$

$$F = q_z G C_f A_f = 74.7 \text{ Af}$$

$$\text{Solid Area: } A_f = 0.0 \text{ sf}$$

$$F = 0 \text{ lbs}$$

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
T: (908) 668-8300
F: (908) 754-4401

Title: LIGHT POLE FOUNDATION **Job # J060251**
Design: TUNG-TO LAM **Date: 3:41PM, 6 JUL 08**
Description: THE HOME DEPOT
1722 NEW JERSEY STATE HIGHWAY ROUTE 68
Scope: LIGHT POLE FOUNDATION

Rev: 380700
 User: KW-0901434, Ver 5.6.1, 25-Oct-2002
 (c)1989-2002 ENERCALC Engineering Software

Pole Embedment in Soil

Page 1

g:\home depot\2005\050251\structure\J060251

Description Circular pole with Point & Uniform Loads (Two Fixtures @180 degrees)

General Information

Allow Passive	180.00 pcf	Applied Loads...
Max Passive	1,500.00 psf	Point Load
Load duration factor	1.333	distance from base
Pole is Circular		
Diameter	36.000 in	Distributed Load
No Surface Restraint		distance to top
		distance to bottom

234.00 lbf
 32.000 ft

02.50 k/ft
 32.000 ft
 0.000 ft

Summary

Moments @ Surface...		
Point load	7,488.00 ft-lb	Total Moment
Distributed load	11,520.00	Total Lateral
		19,008.00 ft-lb
Without Surface Restraint...		
Required Depth	6.383 ft	
Press @ 1/3 Embed...		
Actual	513.20 psf	
Allowable	510.53 psf	

7.8 sf EPA

7 ft embedment

9" pole

RIV

FAX TRANSMITTAL

CONSTRUCTION GROUP

DATE: 8-5-09 # PAGES 5
PROJECT: Home Depot (including cover sheet)
Brick, NJ
TO: Allison FAX#: _____
COMPANY: Brick Twp. PHONE: _____
CC: _____
FROM: Carmine Caruso
RE: Light Pole Calculations

COMMENTS:

Please see calculations for proposed light poles.

Thanks!

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
TELEPHONE: (908) 668-8300
FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK	
PROPOSED LIGHT POLE FOUNDATION	
JOB NO. J050251	SHEET NO. 1
CALCULATED BY TXL	DATE 7/6/2009
CHECKED BY	DATE

STRUCTURAL CALCULATIONS

FOR

THE HOME DEPOT

1722 NEW JERSEY STATE HIGHWAY ROUTE 88; BLOCK 1170, LOT 5
TOWNSHIP OF BRICK
OCEAN COUNTY, NEW JERSEY

K.B. CAHILL, P.E.
NEW JERSEY LICENSE NO.: 42004



BOHLER ENGINEERING
 35 TECHNOLOGY DRIVE
 WARREN, NEW JERSEY 07059
 TELEPHONE: (908) 668-8300
 FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK

PROPOSED LIGHT POLE FOUNDATION

JOB NO. J050251 SHEET NO. _____
 CALCULATED BY TXL DATE 7/6/09
 CHECKED BY _____ DATE _____

Code Search

I. Code: International Building Code 2006

II. Occupancy:

Occupancy Group = U Utility & Miscellaneous

III. Type of Construction:

Fire Rating:

Roof = 0.0 hr
 Floor = 0.0 hr

IV. Live Loads:

Roof angle (θ) 0.00 / 12 0.0 deg
 Roof 0 to 200 sf: 20 psf
 200 to 600 sf: 24 - 0.02 Area
 over 600 sf: 12 psf
 Floor N/A
 Stairs & Exitways 0 psf
 Balcony N/A
 Mechanical N/A
 Partitions N/A



V. Wind Loads: ASCE 7 - 02

Importance Factor 1.00
 Wind speed 113 mph
 Directionality (K_d) 0.85
 Mean Roof Ht (h) 32.0 ft
 Parapet ht above grd 0.0 ft
 Exposure C
 Enclosure Classif. Open Building
 Internal pressure +/-0.00
 Building length (L) 7.5 ft
 Least width (B) 2.3 ft
 K_h case 1 0.996
 K_h case 2 0.996

Topographic Factor (K_{zt})

Topography Flat
 Hill Height (H) 0.0 ft
 Half Hill Length (L_h) 0.0 ft
 Actual H/L_h = 0.00
 Use H/L_h = 0.00
 Modified L_h = 0.0 ft
 From top of crest: x = 0.0 ft
 Bldg up/down wind? downwind
 $H/L_h = 0.00$ $K_1 = 0.000$
 $x/L_h = 0.00$ $K_2 = 0.000$
 $z/L_h = 0.00$ $K_3 = 1.000$
 At Mean Roof Ht:
 $K_{zt} = (1 + K_1 K_2 K_3)^{1/2} = 1.00$

$H < 15 \text{ ft} \times \text{exp C}$
 $\therefore K_{zt} = 1.0$

**ESCARPMENT****2D RIDGE or 3D AXISYMMETRICAL HILL**

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
TELEPHONE: (908) 668-8300
FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK
PROPOSED LIGHT POLE FOUNDATION
JOB NO. 1050251 SHEET NO.
CALCULATED BY TXL DATE 7/6/09
CHECKED BY DATE

V. Wind Loads - Other Structures:

Importance Factor	1.00	Wind Speed	113 mph
Height to evaluate pressure (z)	32.0 ft	Exposure	C
Gust Effect Factor (G)	0.85	Kzt	1.00
Kz (case 2)	0.996	Base pressure (qz) =	32.55 Kd psf

A. Solid Freestanding Walls & Solid Signs (& open signs with less than 30% open)

Height	32.0 ft	M =	32.0 ft
Width	7.5 ft	N =	7.5 ft
Dist above ground		M/N =	4.267
to bottom edge	32.0 ft	C _r =	1.20
Directionality (Kd)	0.85		

$$F = q_z G C_r A_r = 282 \text{ Af}$$

A_r = 7.8 sf
F = 220 lbs

Horizontal design eccentricity for signs = 0 to 0.2 times sign width

Use 30 ft in design

B. Open Signs & Lattice Frameworks (openings 30% or more of gross area)

Width (zero if round)	0.0 ft	Error	
Diameter (zero if rect)	0.0 ft		
Percent of open area		e =	0
to gross area	0.0%	C _r =	0.8
Directionality (Kd)	0.85		

$$F = q_z G C_r A_r = 0.0 \text{ Af}$$

Solid Area: A_r = 0.0 sf
F = 0 lbs

Design sign as solid sign

C. Chimneys, Tanks & Similar Structures

Cross-Section	Round
Directionality (Kd)	0.95
Height (h)	0.0 ft
Width (D)	0.0 ft
Type of Surface	Moderately smooth

$$h/D = \#DIV/0!$$

$$D(qz)^{0.5} = 0.00$$

D = diameter or least horizontal dimension of square, hexagonal or octagonal at elevation under consideration.
D' = depth of protruding elements such as ribs and spoilers (in feet) for round structures only.

Round

$$C_r = \#DIV/0!$$

$$F = q_z G C_r A_r = \#DIV/0! \text{ Af}$$

A_r = 0.0 sf

F = #DIV/0! lbs

D. Trussed Towers

$$e = 0.27 \quad (\text{Ratio of solid area to gross area of the tower face under consideration})$$

Tower Cross Section	square
Member Shape	flat
Directionality (Kd)	1.00

$$\text{Diagonal wind factor} = 1.2$$

$$\text{Round member factor} = 1.000$$

Square (wind along tower diagonal)

$$C_r = 3.24$$

$$F = q_z G C_r A_r = 89.6 \text{ Af}$$

Solid Area: A_r = 10.0 sf

F = 896 lbs

Square (wind normal to face)

$$C_r = 2.70$$

$$F = q_z G C_r A_r = 74.7 \text{ Af}$$

Solid Area: A_r = 0.0 sf

F = 0 lbs

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
T: (908) 666-8300
F: (908) 754-4401

Title : LIGHT POLE FOUNDATION Job # J050261
Dagmr: TUNG-TO LAM Date: 3:41PM, 6 JUL 08
Description : THE HOME DEPOT
 1722 NEW JERSEY STATE HIGHWAY ROUTE 88
Scope : LIGHT POLE FOUNDATION

Rev: 580100
 User: RIV-0601494, Ver 5.8.1, 25-Oct-2002
 (C)1983-2002 ENERCALC Engineering Software

Pole Embedment in Soil

Page 1

g:\home depot\2005\050261\structure\050261

Description Circular pole with Point & Uniform Loads (Two Fixtures @180 degrees)

General Information

Allow Passive 180.00 pcf
 Max Passive 1,500.00 psf
 Load duration factor 1.333
 Pole is Circular
 Diameter 36.000 in
 No Surface Restraint

Applied Loads...

Point Load
 distance from base

234.00 lbs
 32.000 ft

Distributed Load
 distance to top
 distance to bottom

82.60 #/ft
 32.000 ft
 0.000 ft

Summary

Moments @ Surface...

Point load 7,488.00 ft-#
 Distributed load 11,520.00

Total Moment 19,008.00 ft-#
 Total Lateral 954.00 lbs

Without Surface Restraint...

Required Depth 6.363 ft
 Press @ 1/3 Embed...
 Actual 513.20 pcf
 Allowable 510.53 pcf

7 ft embedment

7.8 of EPA

9" pole

RIV

FAX TRANSMITTAL

CONSTRUCTION GROUP

DATE:

8/5/09

PAGES

5

(including cover sheet)

PROJECT:

Brick NJ

Home Depot

TO:

Allison

FAX#:

732-262-8954

COMPANY:

Brick Township

PHONE:

CC:

FROM:

Tony Conro


RE:

Site Pole Struc. Calculations

COMMENTS:

Allison,

See Attached. Please let me know
when you received.



Office

41 Rt. 34 South Colts Neck, NJ 07722 (732) 431-5484 Fax (732) 431-5485

BOHLER ENGINEERING
35 TECHNOLOGY DRIVE
WARREN, NEW JERSEY 07059
TELEPHONE: (908) 668-8300
FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK	
PROPOSED LIGHT POLE FOUNDATION	
JOB NO. J050251	SHEET NO. 1
CALCULATED BY TXL	DATE 7/6/2009
CHECKED BY	DATE

STRUCTURAL CALCULATIONS

FOR

THE HOME DEPOT

1722 NEW JERSEY STATE HIGHWAY ROUTE 88; BLOCK 1170, LOT 5
TOWNSHIP OF BRICK
OCEAN COUNTY, NEW JERSEY

K.B. CAHILL, P.E.
NEW JERSEY LICENSE NO.: 42004



www.StruWare.com

BOHLER ENGINEERING
 35 TECHNOLOGY DRIVE
 WARREN, NEW JERSEY 07059
 TELEPHONE: (908) 668-8300
 FAX: (908) 754-4401

JOB TITLE THE HOME DEPOT - BRICK
PROPOSED LIGHT POLE FOUNDATION
 JOB NO. J050251 SHEET NO. _____
 CALCULATED BY TXL DATE 7/6/09
 CHECKED BY _____ DATE _____

Code Search



- I. **Code:** International Building Code 2006
- II. **Occupancy:**
 Occupancy Group = U Utility & Miscellaneous
- III. **Type of Construction:**
 Fire Rating:
 Roof = 0.0 hr
 Floor = 0.0 hr
- IV. **Live Loads:**
 Roof angle (θ) 0.00 / 12 0.0 deg
 Roof 0 to 200 sf: 20 psf
 200 to 600 sf: 24 - 0.02 Area
 over 600 sf: 12 psf
 Floor N/A
 Stairs & Exitways 0 psf
 Balcony N/A
 Mechanical N/A
 Partitions N/A
- V. **Wind Loads : ASCE 7 - 02**

Importance Factor 1.00
 Wind speed 113 mph
 Directionality (K_d) 0.85
 Mean Roof Ht (h) 32.0 ft
 Parapet ht above grd 0.0 ft
 Exposure C
 Enclosure Classif. Open Building
 Internal pressure +/-0.00
 Building length (L) 7.5 ft
 Least width (B) 2.3 ft
 K_h case 1 0.996
 K_h case 2 0.996

Topographic Factor (K_{zt})

Topography Flat
 Hill Height (H) 0.0 ft
 Half Hill Length (L_h) 0.0 ft
 Actual H/L_h = 0.00
 Use H/L_h = 0.00
 Modified L_h = 0.0 ft
 From top of crest: x = 0.0 ft
 Bldg up/down wind? downwind
 H/L_h = 0.00 K₁ = 0.000
 x/L_h = 0.00 K₂ = 0.000
 z/L_h = 0.00 K₃ = 1.000
 At Mean Roof Ht:
 $K_{zt} = (1 + K_1 K_2 K_3)^2 = 1.00$

H < 15 ft; exp C
 $\therefore K_{zt} = 1.0$



BOHLER ENGINEERING
 35 TECHNOLOGY DRIVE
 WARREN, NEW JERSEY 07059
 TELEPHONE: (908) 668-8300
 FAX: (908) 754-4401

JOB TITLE **THE HOME DEPOT - BRICK**
PROPOSED LIGHT POLE FOUNDATION
 JOB NO. **J050251** SHEET NO. _____
 CALCULATED BY **TXL** DATE **7/6/09**
 CHECKED BY _____ DATE _____

V. Wind Loads - Other Structures:

Importance Factor	1.00	Wind Speed	113 mph
Height to evaluate pressure (z)	32.0 ft	Exposure	C
Gust Effect Factor (G)	0.85	Kzt	1.00
Kz (case 2)	0.996	Base pressure (qz) =	32.55 Kd psf

A. Solid Freestanding Walls & Solid Signs (& open signs with less than 30% open)

Height	32.0 ft	M =	32.0 ft
Width	7.5 ft	N =	7.5 ft
Dist above ground		M/N =	4.267
to bottom edge	32.0 ft	Cf =	1.20
Directionality (Kd)	0.85		

$F = q_z G C_f A_f =$ **282 Af**
 $A_f =$ 7.8 sf
 $F =$ 220 lbs
 Horizontal design eccentricity for signs = 0 to 0.2 times sign width.

Use 30 ft in design

B. Open Signs & Lattice Frameworks (openings 30% or more of gross area)

Width (zero if round)	0.0 ft	Error	
Diameter (zero if rect)	0.0 ft		
Percent of open area		$\epsilon =$	0
to gross area	0.0%	$C_f =$	0.8
Directionality (Kd)	0.85		

$F = q_z G C_f A_f =$ **0.0 Af**
 Solid Area: $A_f =$ 0.0 sf
 $F =$ 0 lbs
 Design sign as solid sign

C. Chimneys, Tanks & Similar Structures

Cross-Section	Round
Directionality (Kd)	0.95
Height (h)	0.0 ft
Width (D)	0.0 ft
Type of Surface	Moderately smooth

D = diameter or least horizontal dimension of square, hexagonal or octangular at elevation under consideration.
 D' = depth of protruding elements such as ribs and spoilers (in feet) for round structures only.

$h/D = \#DIV/0!$
 $D(qz)^{0.5} = 0.00$

Round

$C_f = \#DIV/0!$
 $F = q_z G C_f A_f = \#DIV/0! Af$
 $A_f =$ 0.0 sf
 $F = \#DIV/0! lbs$

D. Trussed Towers

$\epsilon =$ 0.27	(Ratio of solid area to gross area of the tower face under consideration)
Tower Cross Section	square
Member Shape	flat
Directionality (Kd)	1.00

Diagonal wind factor = 1.2
 Round member factor = 1.000

Square (wind along tower diagonal)

$C_f =$ 3.24
 $F = q_z G C_f A_f =$ **89.6 Af**
 Solid Area: $A_f =$ 10.0 sf
 $F =$ 896 lbs

Square (wind normal to face)

$C_f =$ 2.70
 $F = q_z G C_f A_f =$ **74.7 Af**
 Solid Area: $A_f =$ 0.0 sf
 $F =$ 0 lbs



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723
(732) 262-1027

Subcode Official Review

To: 3096 HAMILTON BLVD S PLAINFIELD, NJ 07080 CC:

RE: Building Subcode
Block: 1170 Lot: 5 Qual:
1722 ROUTE 88

Permit Number: 09-0158+D Control Number: C-09-000746
Last Submit Date: Wednesday, April 29, 2009

Date: Wednesday, April 29, 2009

Dear THE HOME DEPOT,

The following comments were made during the Plan Review process:

Submit 2 sealed sets of plans for footing design. Wind speed design 115mph. Wind load/pressure calcs to be on plan.

4/29/09 2 sets of plans showing footing design requested above, not provided.

Sincerely,

4/29/09

Kenneth Anderson, Subcode Official

05-15-09
Called
732-431-
5484

732-
431-
5483

04-29-09

fax #

732-926-

292

Attn: Bruce

TAMy

Bldg

Elect

Fire

Plumbing

(Please mark subcode)

CONTROL NUMBER 000-000-746

TOWNSHIP OF BRICK
APPLICATION REVIEW PROCESS

ADDRESS OF APPLICATION:

1733 Route 88 - Homestead

DATE REVIEWED:

08-05-19

REVIEWED BY:

QJP

CONTACT CALLED/FAXED:

QJP

733-81-3464 Riv Construction - update + d - failed plan

848-207-1838 Tony call #

Called Tony - left message on machine to call me

Needs to be issued before final Bldg inspection can be assigned

08-05-19
2020 - Architect
2020 - engineer
Plans were submitted
to me - will be re-filing
claims to my attention
then over to my attention

ALLISON,
UPDATE WAS FOR
4 PARKING LOT
LIGHTS. PLAN FOR
FOOTINGS NEVER
PROVIDED. PLANS MUST
HAVE INFO REQUESTED
4/24/09 - ORIGINAL
REVIEW. ~~KA~~



Brick Township
401 Chambersbridge Rd
Brick, NJ 08723
(732) 262-1027

Subcode Official Review

To: 3096 HAMILTON BLVD S PLAINFIELD, NJ 07080 CC:

RE: Building Subcode
Block: 1170 Lot: 5 Qual:
~~1722 ROUTE 88~~
Permit Number: 09-0158+D Control Number: C-09-000746
Last Submit Date: Monday, June 22, 2009

Date: Wednesday, June 24, 2009

Dear THE HOME DEPOT,

The following comments were made during the Plan Review process:


Submit 2 sealed sets of plans for footing design. Wind speed design 115mph. Wind load/pressure calcs to be on plan.

4/29/09 2 sets of plans showing footing design requested above, not provided.

★ ***6/24/09*** Thank you for revised pages and calcs.
This update include parking lot lighting. Request above was for parking lot lighting footing design/calcs.
Please provide 2 sealed sets of same.

Plans submitted with Casco bulletin #6 dated 6/18/09 require plumbing update for roof drain piping revisions. No building subcode review required for Casco bulletin #6.

Sincerely,

 6/24/09

Kenneth Anderson, Subcode Official

06-25-09
fax # 732-431-5483
Contract #

QPCTMR



Physical Connection Permit No:

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Physical Connection Test & Maintenance Report

Date of test 07 / 07 / 09

Certification expires 1 year from date of test.

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 Days of each test and Inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To:

From: (Name of Permit Holder)

Home Depot #0912

Route 70 and Route 88

Brick, NJ

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C.7:10-10.6 and is certified to be in compliance with this regulation.

Description of Valve

Location of Valve

Manufacturer: Watts

Sprinkler Control Room

Model Number: 009M2 ☒ RPZ ☐ DCVA ☐ PVB

Irrigation Main

Serial Number: A56003 Size 2 in.

Tested by:
Pan Metro Services
Edison, NJ 08817
732-393-0100

Comments and Notations:

	PRESSURE TEST			INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE ASSEMBLY	
	DOUBLE CHECK VALVE				
	1 st Check	2 nd Check	Relief Valve	1 st Check	2 nd Check
Initial Test	Closed Tight ☒ at <u>10.0</u> psid	Closed Tight ☒ at ____ psid	Opened at <u>3.2</u> psid	OK ☐	OK ☐
Passed ☒	Leaked ☐	Leaked ☐	Did Not Open ☐	Failed ☐	Failed ☐
Failed ☐	No. 2 Shut-off Valve Closed Tight ☒ Leaked ☐ By-pass used ☐				
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐ ____ psid	Closed Tight ☐ ____ psid	Opened at ____ psid	OK ☐	OK ☐

The Results Shown Above are Certified to be True

Witnesses to test and inspection

Certified Testers Name: Clifford Lyle Blevins

Name: _____ Title: _____

Certified Testers Signature: Clifford L. Blevins

Representing: _____

Certifying Authority: New England Water Works Association

Name: _____ Title: _____

Cert. ID#: 3829 Exp. Date: 10-31-09

Representing: _____

Ken -

Home Depot scheduled
for final Bldg on Friday ~~10/1~~

8/7- but update is
pending (in reject drawer)

-so what's the deal here?

is this update still
needed?

Allison

10 MAXham 09.0566

~~44~~ ~~rough~~ ~~f~~

~~44~~ ~~Shore~~ ~~Cherry~~

~~Linda 732 239 8416~~

Linda Barber ↑

~~20-5823~~ 13 Hilly 606 12.01

QPCTMR



Physical Connection Permit No:

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Physical Connection Test & Maintenance Report

Date of test 07 / 07 / 09

Certification expires 1 year from date of test.

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 Days of each test and Inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To:

From: (Name of Permit Holder)

Home Depot #0912

Route 70 and Route 88

Brick, NJ

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C.7:10-10.6 and is certified to be in compliance with this regulation.

Description of ValveManufacturer: WattsModel Number: 009M2 ☒ RPZ ☐ DCVA ☐ PVBSerial Number: A57389 Size 2 in.

Comments and Notations: _____

Location of Valve

Sprinkler Control Room

Domestic Main

Tested by:
Pan Metro Services
Edison, NJ 08817
732-393-0100

	PRESSURE TEST			INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE ASSEMBLY	
	DOUBLE CHECK VALVE		Relief Valve	1 st Check	2 nd Check
	1 st Check	2 nd Check			
Initial Test	Closed Tight ☒ at 8.2 psid	Closed Tight ☒ at ____ psid	Opened at 2.6 psid	OK ☐	OK ☐
Passed ☒	Leaked ☐	Leaked ☐	Did Not Open ☐	Failed ☐	Failed ☐
Failed ☐	No. 2 Shut-off Valve Closed Tight ☒ Leaked ☐ By-pass used ☐				
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐ ____ psid	Closed Tight ☐ ____ psid	Opened at ____ psid	OK ☐	OK ☐

The Results Shown Above are Certified to be TrueWitnesses to test and inspectionCertified Testers Name: Clifford Lyle Blevins

Name: _____ Title: _____

Certified Testers Signature: Clifford L. Blevins

Representing: _____

Certifying Authority: New England Water Works Association

Name: _____ Title: _____

Cert. ID#: 3829 Exp. Date: 10-31-09

Representing: _____

QPCTMR



Physical Connection Permit No:

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION

Physical Connection Test & Maintenance Report

Date of test 07 / 07 / 09

Certification expires 1 year from date of test.

Instructions: This form is to be completed for each test of each approved valve. It is to be mailed to the Supplier of Water and Local Administrative Authority within 5 Days of each test and Inspection performed by a Certified Tester. These forms shall be kept at the facility and be exhibited upon request, and are to be submitted with the Physical Connection Renewal Application.

To:

From: (Name of Permit Holder)

Home Depot #0912

Route 70 and Route 88

Brick, NJ

The backflow prevention device identified below has been tested and inspected as required by N.J.A.C.7:10-10.6 and is certified to be in compliance with this regulation.

Description of Valve

Location of Valve

Manufacturer: Watts

Model Number: 009M2 ☒ RPZ ☐ DCVA ☐ PVB

Serial Number: A56003 Size 2 in.

Comments and Notations:

Sprinkler Control Room

Irrigation Main

Tested by:
Pan Metro Services
Edison, NJ 08817
732-393-0100

	PRESSURE TEST			INTERNAL INSPECTION	
	REDUCED PRESSURE ZONE ASSEMBLY			DOUBLE CHECK VALVE ASSEMBLY	
	DOUBLE CHECK VALVE		Relief Valve		
	1 st Check	2 nd Check		1 st Check	2 nd Check
Initial Test	Closed Tight ☒ at 10.0 psid	Closed Tight ☒ at ____ psid	Opened at 3.2 psid	OK ☐	OK ☐
Passed ☒	Leaked ☐	Leaked ☐			
Failed ☐	No. 2 Shut-off Valve Closed Tight ☒ Leaked ☐	By-pass used ☐	Did Not Open ☐	Failed ☐	Failed ☐
Repairs & Materials Used					
Test After Repair & Assembly	Closed Tight ☐ ____ psid	Closed Tight ☐ ____ psid	Opened at ____ psid	OK ☐	OK ☐

The Results Shown Above are Certified to be True

Witnesses to test and inspection

Certified Testers Name: Clifford Lyle Blevins

Name: _____ Title: _____

Certified Testers Signature: Clifford L. Blevins

Representing: _____

Certifying Authority: New England Water Works Association

Name: _____ Title: _____

Cert. ID#: 3829 Exp. Date: 10-31-09

Representing: _____

Date: Thursday, June 27, 2009

Dear THE HOME DEPOT,

The following comments were made during the Plan Review process:

Submit 2 sealed sets of plans for footing design. Wind speed design 115mph. Wind load/pressure calcs to be on plan.

4/29/09 2 sets of plans showing footing design requested above, not provided.



6/24/09 Thank you for revised pages and calcs.

This update include parking lot lighting. Request above was for parking lot lighting footing design/calcs. Please provide 2 sealed sets of same.

Plans submitted with Casco bulletin #6 dated 6/18/09 require plumbing update for roof drain piping revisions. No building subcode review required for Casco bulletin #6.

Sincerely,

Kenneth Anderson 6/24/09

Kenneth Anderson, Subcode Official

06-25-09
fax # 732-431-5483
Contract #

Page 1

7324315483	NORMAL	25, 9:51	0'25"	1	* O K	
Telephone Number	Mode	Start	Time	Page	Result	Note

P.1 Jun 25 2009 9:52

** Transmit Conf. Report **

Land Use/ Bldg Dept Fax: 732-262-8954



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000

Block 1170 Lot 5 Qualification Code

Work Site Location: 1722 ROUTE 88, Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address: 3096 HAMILTON BLVD, S. PLAINFIELD, NJ 07080

Tel: (732) 926-3626

Contractor: Mason Technologies, Inc.

Address: 33 Ranick Road, Hauppauge, NY 11788

Tel: (631) 234-6565

Fax: (631) 234-7826

Lic No.

Federal Employee No. 38-3665918

B. ELECTRICAL CHARACTERISTICS

Use Group Present Proposed M

Pole/Pad # Temporary Other

Building Occupied as Utility Co.

Estimated Cost of Electrical Work \$50,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

No Plan Required 6/16/09

Joint Plan Review Required

Building Plumbing

Fire Elevator

Electrical Plans Approved

Date:

Approved by:

SUBCODE APPROVAL

CO CCO CA

Date:

Approved by:

INSPECTIONS

Type: Rough Barrier-Free

Trench

Temp. Serv.

Constr. Serv.

TCO

Other

Service

Final

Barrier-Free

Temp. Cut-in-Card Date Issued

Final Cut-in-Card Date Issued

Annual Pool Inspection

Date of Grounding and Bonding Certification

Applicant's Signature/Contractor's Seal and Signature

Licensed Elec Contr' Cert'd Landscape Irrigation Contr' Exempt Applicant

QTY. SIZE

ITEMS

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles

Motors - Fract. HP

Emergency & Exit Lights

Communication Points

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

\$60

Pool Permit/with U/W Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptical

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Recepticle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air

KW Baseboard Heat

HP Motors 1/+ HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

Administrative Surcharge

Minimum Fee

State Permit Surcharge Fee

TOTAL FEE

Date Received 06/15/2009
Date Issued 6/19/09
Control # C-09-002073
Permit # 09-0158+E

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the (agent of) owner of the record and am authorized to make this application and perform the work listed on this application.



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of the record and am authorized to make this application and perform the work listed on this application.

Date Received 06/15/2009
Date Issued 6/15/09
Control # C-09-002073
Permit # 09-0158+E

Block 1170 Lot 5 Qualification Code _____

Work Site Location: 1722 ROUTE 88, Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address: 3096 HAMILTON BLVD S PLAINFIELD NJ 07080

Tel. (732) 926-3626

Contractor: Mason Technologies, Inc.

Address: 33 Ranick Road, Hauppauge NJ 11788

Tel. (631) 234-6565

Fax: (631) 234-7826

Lic No. _____

Federal Employee No. 38-3665918

B. ELECTRICAL CHARACTERISTICS

Use Group Present _____ Proposed _____ M _____

☐ Pole/Pad # _____ ☐ Temporary ☐ Other _____

Building Occupied as _____ Utility Co. _____

Estimated Cost of Electrical Work \$50,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☒ No Plan Required 6-16-09 J.S.

Date _____ Initial _____

INSPECTIONS

Type: _____ Failure _____ Failure _____ Approval _____ Initial _____

Rough _____

Barrier-Free _____

Trench _____

Temp. Serv. _____

Constr. Serv. _____

TCO _____

Other _____

Service _____

Final _____

Barrier-Free _____

Temp. Cut-in-Card Date Issued _____

Final Cut-in-Card Date Issued _____

Annual Pool Inspection _____

Date of Grounding and Bonding _____

SUBCODE APPROVAL
☐ CO ☐ CCO ☐ CA

Date: _____

Approved by: _____

Applicant's Signature/Contractor's Seal and Signature
☐ Licensed Elec Contr ☐ Certifd Landscape Irrigation Contr ☒ Exempt Applicant
D. TECHNICAL SITE DATA

QTY SIZE

ITEMS

FEE (Office Use Only)

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles

Motors - Fract. HP

Emergency & Exit Lights

Communication Points

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

\$60

Pool Permit with UW Lights

Storable Pool/Spa/Hot Tub

KW Elec. Range/Receptacle

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Receptacle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air

KW Baseboard Heat

HP Motors 1/4 HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

Administrative Surcharge

Minimum Fee


State Permit Surcharge Fee

TOTAL FEE

\$145



ELECTRICAL SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITIES: 1-800-272-1000.

Block 1178 Lot 5 Qualification Code _____
Work Site Location 1722 Route 88

Owner in Fee: The Home Depot

Tel: (732) 926-3626 email bruce-Talky@HomeDepot.com

Address 1722 Route 88 Back 45 08923

Contractor: Mason Technologies Inc Municipality 29 Tel: (631) 234-6565

Address 33 Beach Rd Hightstown NJ 08520 e-mail _____

Contractor License No. 1491 Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable) _____

Federal Emp. ID No. 38-3665918 FAX: (631) 234-7826

B. ELECTRICAL CHARACTERISTICS

Use Group Present _____ Proposed _____

☐ Pole/Pad # _____ ☐ Temporary ☐ Other _____

Building Occupied as _____ Utility Co. _____

Est. Cost of Elec. Work \$ 50,000

JOBS SUMMARY (Office Use Only)

☒ No Plans Required 6-16-98

☐ Partial Under-slab Utilities Approved

Date: _____ Approved by: _____

☐ Electric Plans Approved

Date: _____ Approved by: _____

Joint Plan Review Required: ☐ Bldg. ☐ Plumb. ☐ Fire. ☐ Elev.

SUBCODE APPROVAL FOR PERMIT

Date: _____ Approved by: _____

SUBCODE APPROVAL FOR CERTIFICATE

☐ CO ☐ CCCO ☐ CA

Date: _____ Approved by: _____

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the agent of owner of record and am authorized to make this application and perform the work listed on this application.

Applicant's Signature/Contractor's Seal and Signature _____

☐ Licensed Elec. Contractor ☐ Certified Landscape Irrigation Contr' ☐ Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

Voice & Data

Date Received _____
Control # _____

Date Issued _____
Permit # _____

QTY	SIZE	ITEMS	FEE (Office Use Only)
-----	------	-------	-----------------------

Lighting Fixtures

Receptacles

Switches

Detectors

Light Poles

Motors—Fract. HP

Emergency & Exit Lights

Communications Points

Alarm Devices/F.A.C. Panel

TOTAL NUMBERS

Pool Permits/with UV Lights

Storable Pool/Spa/Hot Tub

KW Elec. Ranges/Receptacle

KW Oven/Surface Unit

KW Elec. Water Heater

KW Elec. Dryer/Receptacle

KW Dishwasher

HP Garbage Disposal

KW Central A/C Unit

HP/KW Space Heater/Air Handler

KW Baseboard Heat

HP Motors 1/4 HP

KW Transformer/Generator

AMP Service

AMP Subpanels

AMP Motor Control Center

KW Elec. Sign/Outline Light

Administrative Surcharge \$ _____

Minimum Fee \$ _____

State Permit Surcharge Fee \$ _____

TOTAL FEE \$ _____


update

09-0158 HE

STATE OF NEW JERSEY
DEPARTMENT OF TREASURY
CERTIFICATE OF AUTHORITY

MASON TECHNOLOGIES INC.
0100966700

*I, the Treasurer of the State of New Jersey,
do hereby certify that the above-named
Foreign Profit Corporation organized under
the laws of New York, has complied with all
the requirements of Title 14A of the New
Jersey Statutes, and that the business or
activity of said Foreign Profit Corporation
to be carried on within the State of New Jersey
is such as may be lawfully carried on by a
Foreign Profit Corporation filed under the
laws of this State for similar business or activity.
The Certificate of Authority was duly filed
August 9th, 2006.*



IN TESTIMONY WHEREOF, I have
hereunto set my hand and
affixed my Official Seal
at Trenton, this
10th day of August, 2006

Bradley Abelson

Bradley Abelson
State Treasurer

New Jersey Office of the Attorney General
Division of Consumer Affairs
Board of Examiners of Electrical Contractors



TELECOMMUNICATIONS

Limited Wiring Exemption*

Issued to:

Mason Technologies, Inc.
33 Ranick Road
Haddonfield, NJ 08033

1491

[Signature]
Signature of holder

Exemption No.

CERTIFICATION IN LIEU OF OATH

I. OWNER SECTION (to be completed if the applicant is the owner in fee)

I hereby certify that I am the owner in fee of the property listed on Page 1.

Mark the following applicable boxes:

- A. ☐ I further certify that a new home (private residence) will be constructed on this property for my own use and occupancy. This dwelling is to be occupied by myself and is not to be used for any purpose other than single family residential use. I attest that all construction, plumbing, or electrical work will be done, in whole or in part, by me or by subcontractors under my supervision, in accordance with all applicable laws; and, I further acknowledge that said new home is not covered under the New Home Warranty and Builders Registration Act (N.J.S.A. 46:3B-1 et seq.) and that such fact shall be disclosed to any person purchasing this property within ten years of the date of issuance of a certificate of occupancy.

I UNDERSTAND THAT IN MARKING BOX A, I ACKNOWLEDGE THAT I AM ASSUMING RESPONSIBILITY FOR THE WORK DONE ON SAID PROPERTY, THE CONDITION OF THE PROPERTY PRIOR TO, DURING, AND AFTER ANY WORK PERFORMED, AND FOR THE PERFORMANCE OF THE SUBCONTRACTORS I HIRE, EMPLOY, OR OTHERWISE CONTRACT OR WITH WHOM I MAKE AGREEMENTS TO PERFORM WORK. I AM VOLUNTARILY AND KNOWINGLY ASSUMING THIS RESPONSIBILITY.

- B. ☐ I further certify the following as required by the New Jersey Uniform Construction Code, N.J.A.C. 5:23-2.15(e)1.ix:

I personally prepared the plans submitted for: 1) the new home referred to in A.; or, 2) an addition, alteration, renovation, or repair to an existing single family residence owned and occupied by myself and located on the property listed on Page 1; or, 3) a new structure that will be physically separate from, but that will be deemed part of, an existing single family residence that is owned and occupied by myself and located on the property listed on Page 1.

- C. ☐ I further certify that I will perform or supervise the following work:

C.1. ☐ Building

C.2. ☐ Fire Protection

I further certify that I will perform the following work:

C.3. ☐ Electrical

C.4. ☐ Plumbing

- D. ☐ I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I understand that if any of the above statements are willfully false, I am subject to punishment.

Signature _____ Date _____

II. AGENT SECTION (to be completed if the applicant is not the owner in fee)

I hereby certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(d): the proposed work is authorized by the owner in fee; and I have been authorized by the owner in fee to make this application as his agent.

I further certify the following as required by the Uniform Construction Code, N.J.A.C. 5:23-2.15(a)5: All required State, county, and local prior approvals have been given, including such certification as the construction official may require.

I agree to advise all contractors on this project that they are required to be registered with the New Jersey Division of Taxation and to comply with all New Jersey tax laws.

I understand that if any of the above statements are willfully false, I am subject to punishment.

☒ Check if contractor.

Agent Name Paul L. Lamontagne

Address 33 Ranick Rd. Hauppauge NY 11788

Telephone (917) 216-2300

Signature Paul Lamontagne

III. ☐ LEAD HAZARD ABATEMENT: Include Homeowner or Building Owner Affidavit as per N.J.A.C. 5:17.

BLOCK 1170 LOT 5 QUALIFICATION CODE ADDRESS (SITE)

PERMIT NO.



CONSTRUCTION PERMIT APPLICATION

Applicant Completes: Sections I, II, III (optional), IV, VI, and VII

I. IDENTIFICATION

1. Proposed Work Site at: 1722 Route 88

2. Name of Owner in Fee: The Home Depot

Tel. (232) 924-3626 e-mail bruce-taluy@homedepot.com

Address 1722 Route 88 Boek NJ 08723

3. Ownership in Fee: Public Private Municipality zip code

4. Principal Contractor: Mason Technologies Inc Tel. (631) 234-6565

Address 33 Remick Rd Hightstown NJ 08520 e-mail

plasma@ymail.com Mason 247.com

License No. OR, if new home, Builder Reg. No. 1491 Exp. Date

Home Improvement Contractor Registration No. or Exemption Reason (if applicable):

Federal Emp. ID No. 38-3665918 FAX: (631) 234-7826

5. Architected or Engineer Paul Lemonfyne Contact

Address Paul Lemonfyne FAX: (631) 234-7826

Tel. (917) 216-2300 FAX: (631) 234-7826

6. Responsible Person in Charge once Work has Begun Paul Lemonfyne

Tel. (917) 216-2300 FAX: (631) 234-7826

IIa. PROPOSED WORK

☐ Minor Work

☐ Repair

☐ Asbestos Abat. - Subch. 8

☐ Lead Hazard Abatement

☐ Addition

☐ Renovation

☐ Demolition

☐ Reconstruction

☐ Annual Permit

☐ Radon Remediation

☐ Building

☐ Electrical

☐ Plumbing

☐ Fire Protection

☐ Elevator

TOTAL COST

IIb. SUBCODES

(Check all that apply)

☐ Building

☐ Electrical

☐ Plumbing

☐ Fire Protection

☐ Elevator

TOTAL COST

III. PLAN REVIEW (optional)

DO YOU WANT:

1. ☐ Partial Releases

2. ☐ Prototype Processing

IV. DOES OR WILL YOUR BUILDING CONTAIN ANY OF THE FOLLOWING?

1. ☐ Elevators/Escalators/Lifts

2. ☐ Dumbbells/Moving Walks

3. ☐ High Pressure Boilers

4. ☐ Pressure Vessels

5. ☐ Refrigeration Systems

6. ☐ Cross-Connections/Backflow Preventers

7. ☐ Hazardous Uses/Places of Assembly

8. ☐ Sprinklers

9. ☐ Smoke Control Systems in Open Wells

10. ☐ Underground Storage Tanks

11. ☐ Swimming Pools, Spas and Hot Tubs

12. ☐ LPGas Tanks

VI. BUILDING/SITE CHARACTERISTICS

1. Number of Stories: _____

2. Height of Structure: _____ ft.

3. Area - Largest Floor: _____ sq. ft.

4. New Building Area: _____ sq. ft.

5. Volume of New Structure: _____ cu. ft.

6. Max. Live Load: _____

7. Max. Occupancy Load: _____

8. If Industrialized Building: State Approved _____ HUD _____

9. Total Land Area Disturbed: _____ sq. ft.

10. Flood Hazard Zone: _____

11. Base Flood Elevation: _____ ft.

12. Wetlands: yes _____ no _____

(office use only)

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

Update

09-0158 + E

REC'D JUN 05 2009



BOHLER

ENGINEERING

35 Technology Drive
Warren, NJ 07059
PHONE 908.668.8300
FAX 908.754.4401

April 9, 2009

Via Federal Express

Township of Brick
Planning Board
401 Chambers Bridge Road
Brick, NJ 08723

Attention: Elissa Commins, P.E.

**RE: Proposed Home Depot Facility #912
Route 70 and Route 88
Township of Brick
Ocean County, NJ
BENJ File No. 050251**

Dear Ms. Commins:

As discussed at our April 9, 2009 meeting, enclosed please find two (2) signed and sealed Lighting Plans in regard to the above referenced project.

Should you have any questions or require any additional information, please do not hesitate to contact the undersigned.

Sincerely,

BOHLER ENGINEERING

Michael A. Albanese

MA/ an/J:\Home Depot\2005\050251 - Home Depot (Brick)\Letters\tsppb16.doc

OTHER OFFICE LOCATIONS:

- | | | | | | |
|------------------------------------|------------------------------|------------------------------------|----------------------------------|-------------------------------------|---------------------------------------|
| • Southborough, MA
508.480.9900 | • Albany, NY
518.438.9900 | • White Plains, NY
914.286.2700 | • Ronkonkoma, NY
631.738.1200 | • Center Valley, PA
610.709.9971 | • Chalfont, PA
215.996.9100 |
| • Philadelphia, PA
215.996.9100 | • Towson, MD
410.821.7900 | • Sterling, VA
703.709.9500 | • Warrenton, VA
540.349.4500 | • Bowie, MD
301.809.4500 | • Fort Lauderdale, FL
954.202.7000 |

CIVIL AND CONSULTING ENGINEERS • SURVEYORS • PROJECT MANAGERS • ENVIRONMENTAL CONSULTANTS • LANDSCAPE ARCHITECTS

www.BohlerEngineering.com

TOWNSHIP OF BRICK

OCEAN COUNTY, NEW JERSEY

401 CHAMBERS BRIDGE ROAD, BRICK, N.J. 08723

Stephen C. Acropolis, Mayor

Township Council:

Ruthanne Scaturro - President
Joseph Sangiovanni - Vice President
Brian DeLuca
Anthony Matthews
Kathy M. Russell
Michael A. Thulen, Sr.
Dan Toth



Department of Community Development & Land Use
Division of Engineering

Office of the Municipal Engineer
732-262-1040
Fax: 732-262-8954
www.twp.brick.nj.us

Date: 3-23-09


ENGINEERING PLOT PLAN EXEMPT FORM

Block: 1170 Lot: 5

Property Address: 1722 Route 88

I, Tony Corso (name) of 315 Rt. 34 Suite 137 (address)

request to be exempt from the plot plan requirement for an addition, fence, shed, deck, pool, retaining wall, etc. as outlined in the Brick Land Use Book, Chapter 190.31, Part B.


Applicant's Signature

Colts Neck, NJ 07733
COMMERCIAL

The following shall be submitted with this request:

1. Submit surveys locating existing dwelling and proposed addition. Dimensions of the addition should be included.
2. Proof that the property is not located in a Flood Hazard Area.

Note: Prior to approval a site inspection by the Engineering Department will be performed to verify that the proposed addition will not create a drainage problem.

FOR OFFICE USE ONLY

Approved on: 4/21/09 Signed: KSP

Rejected on: _____ Signed: _____

Comments:

Lighting changes "only" ok ecc 4/9/09 on jacket



**Township of Brick
Zoning Permit**

Approved: Monday, April 20, 2009 **Number:** 2009-229

Block 1170 **Lot** 5 **Zone:** B-3 Highway Dev.

Property Address: 1722 Route 88

Applicant: Tony Corso - RIV Construction

Property Owner: JSM@Brick, LLC


Existing Use: Former Costco Warehouse


Proposed Use: Home Depot Warehouse Sales

Proposed Construction: Construct light poles and fixtures in existing parking area.

Conditions: The installation of the light poles and fixtures shall be in accordance with Planning Board Resolution R-14-06 dated February 8, 2006. Maps signed July 24, 2008. Revised Lighting Plan, Sheet 7 of 12 approved by the Township Engineer.

This permit shall be null, void and of no effect if any of the facts contained in the application upon the basis that this permit was granted are false or untrue in any material respect. This permit shall expire one (1) year after the date of issuance if the use or substantial construction has not been commenced.


Michael P. Fowler, AICP/PP
Administrative Officer


Michael Fowler
Zoning Reviewer

update 09-0158

TOWNSHIP OF BRICK ZONING PERMIT APPLICATION

(Please Type or Print Neatly in Ink, Not Pencil)

Applications missing any of the following information
will delay processing and may be returned to you.

BLOCK 1170 LOT 5 QUALIFIER -

PROPERTY ADDRESS 1722 Route 88

PERSONAL NAME OF APPLICANT Tony Corso

BUSINESS NAME OF APPLICANT RIV Construction

MAILING ADDRESS OF APPLICANT 315 Rt. 34 Suite 137 Colts Neck NJ

PROPERTY OWNER'S FULL NAME JSM 07733

PRESENT USE OF PROPERTY (check all that apply)

☐ Vacant Lot ☐ Single-family dwelling ☐ Multi-family dwelling
☒ Commercial (please describe) Costco Warehouse

PROPOSED USE OF PROPERTY (check all that apply)

☐ Vacant Lot ☐ Single-family dwelling ☐ Multi-dwelling
☒ Commercial (please describe) Home Depot

PROPOSED CONSTRUCTION (check all that apply)

☐ New Building (please describe) _____ Height _____
☐ Addition - Height _____
☐ Alteration _____
☐ Porch or deck - Height _____
☐ Shed - Height _____
☐ Fence - Type _____ Height _____
☐ Swimming Pool ☐ in-ground ☐ above-ground
☒ Other (please describe) light poles

CHECKLIST

- ☐ All information completed above
- ☐ Two (2) copies of a plot plan containing:
- ☐ All existing and proposed structures
- ☐ All dimensions of the lot and structures
- ☐ All setbacks from the structures to the property lines
- ☐ All adjacent streets and waterways
- ☐ If applicable, include a copy of the Zoning Board of Adjustment Resolution, the date that the map was signed, and/or the date that the subdivision map was filed with the Ocean County Clerk, along with the file map and number.

Note: No partial, taped, faxed,
reduced or enlarged copies
can be accepted.

Resubmit
4/20/09

The applicant certifies that all statements and information made and provided as part of this application are true to the best of the applicant's knowledge, information and belief. The applicant further states that the applicant will comply with all other Municipal approvals and ordinances, and all County, State, and Federal Regulations.

SIGNATURE OF APPLICANT [Signature] Date 3/23/09

Reviewed by Zoning Office [Signature] Date 4/20/09 ☒ Approved () Denied

March 2003-----

[Signature]



FIRE SUBCODE TECHNICAL SECTION



COMMERCIAL

Date Received 01/08/2009
Control # C-08-00488-09
Date Issued 04-01-08
Permit # +A

A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000
Block 1170 Lot 5 Qualification Code

Work Site Location: 1722 ROUTE 88 Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address 3096 HAMILTON BLVD S PLAINFIELD NJ 07080

Tel. (732) 926-3626

Contractor: FIRE MATERIALS GROUP

Address 2615 S INDUSTRIAL PARK AVENUE TEMPE AZ 85282

Tel. (480) 753-5444

Fax:

Fire Protection Equipment, NJ Div of Fire Safety Permit No.

Fire Protection Equipment, NJ Div of Fire Safety Installer No.

Fire Alarm Contractor No. P00164

Federal Employee No.

B. FIRE PROTECTION CHARACTERISTICS

Use Group Present Proposed M Fire Alarm System: New or Existing

Constr. Class Present Type I Proposed Type I Location of Panel:

Heating Systems: New or Existing HVAC Fire Suppression/Standpipe System:

Type: Gas Oil Electric Solar New or Existing

Other Location of Main Control Valve:

Location:

Fuel Storage Tank:

Fuel Type: Flammable or Combustible Capacity

Total Cost of Fire Protection Work \$10,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

No Plan Required

Joint Plan Review Required

Building Plumbing

Electrical Elevator

Fire Plans Approved

Date: 1-12-09

Approved by:

SUBCODE APPROVAL

CO COO CA

Date:

Approved by:

INSPECTIONS

Type:

Alarm System

Suppression System

Standpipe

Fire Pump

Pre-Eng. System

Mechanical

Smoke Control

TCO

Final

Other

Dates (Month/Day)

Failure Failure Approval Initial

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

Certified Contractor

Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK

FIRE SUPPRESSION ALTERATIONS, ADD/REMOVE/RELOCATE TO

MATCH REMODELED BUILDING.

Water Supply Source

Method of Alarm/Suppression System Supervision

Alarm Systems

System

110v Interconnected

CO Detectors/110v

Alarm Devices (i.e. smoke, heat, pulls, water/flow)

Supervisory Devices (tamper, low/high air)

Signaling Devices (horn/strobes, bells)

Other Devices

TOTAL

Suppression Systems

Fire Pump GPM Type 1500

Dry Pipe/Alarm Valves

Pre-action Valves

Sprinkler Heads (Dry and Wet)

Standpipes

Pre-engineered Systems

Wet Chemical

Dry Chemical

CO2 Suppression

Foam Suppression

FM200 Suppression

Other

Other Systems

Kitchen Hood Exhaust System

Smoke Control System

Fire Appliances Gas Oil

Fireplace Venting/Metal Chimney

Other

Administrative Surcharge

Minimum Fee

State Permit Surcharge Fee

TOTAL FEE



FIRE SUBCODE TECHNICAL SECTION



COMMERCIAL

Date Received 01/08/2009
Control # C-08-0046627A-C9
Date Issued 09-09-14
Permit # +A

A. IDENTIFICATION - APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000
Block 1170 Lot 5 Qualification Code

Work Site Location: 1722 ROUTE 88 Brick Township, NJ

Owner in Fee: THE HOME DEPOT

Address 3096 HAMILTON BLVD S PLAINFIELD NJ 07080

Tel (732) 926-3626

Contractor: FIRE MATERIALS GROUP

Address 2615 S INDUSTRIAL PARK AVENUE TEMPE AZ 85282

Tel (480) 753-5444

Fax

Fire Protection Equipment, NJ Div of Fire Safety Permit No.

Fire Protection Equipment, NJ Div of Fire Safety Installer No.

Fire Alarm Contractor No. P00164

Federal Employee No.

B. FIRE PROTECTION CHARACTERISTICS

Use Group Present Proposed M Fire Alarm System: ☐ New or ☐ Existing

Const. Class Present Type I Proposed Type I Location of Panel:

Heating Systems: ☐ New or ☐ Existing ☐ HVAC Fire Suppression/Standpipe System:

Type: ☐ Gas ☐ Oil ☐ Electric ☐ Solar ☐ New or ☐ Existing

☐ Other Location of Main Control Valve:

Location:

Fuel Storage Tank:

Fuel Type: ☐ Flammable or ☐ Combustible Capacity

Total Cost of Fire Protection Work \$10,000

JOB SUMMARY (Office Use Only)

PLAN REVIEW

☐ No Plan Required

☐ Joint Plan Review Required

☐ Building ☐ Plumbing

☐ Electrical ☐ Elevator

☒ Fire Plans Approved

Date: 1-12-08

Approved by: [Signature]

SUBCODE APPROVAL

☐ CO ☐ CCO ☐ CA

Date: #

Approved by:

INSPECTIONS

Type: Failure Failure Approval Initial

Alarm System

Suppression System

Standpipe

Fire Pump

Pre-Eng. System

Mechanical

Smoke Control

TCO

Final

Other

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the (agent of) owner of record and am authorized to make this application.

☐ Certified Contractor

Applicant's Signature/Contractor's Seal and Signature

☐ Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK ALTERATIONS, ADD/REMOVE/RELOCATE TO

MATCH REMODELED BUILDING

Water Supply Source

Method of Alarm/Suppression System Supervision

Flammable/Combustible Tanks

Alarm Systems

☐ System

☐ 110V Interconnected

☐ CO Detectors/110V

Alarm Devices (i.e. smoke, heat, pulls, water/flow)

Supervisory Devices (tamper, low/high air)

Signaling Devices (horn/strobes, bells)

Other Devices

TOTAL

Suppression Systems

Fire Pump GPM Type 1500

Dry Pipe/Alarm Valves

Pre-action Valves

Sprinkler Heads (Dry and Wet)

Standpipes

Pre-engineered Systems

Wet Chemical

Dry Chemical

CO2 Suppression

Foam Suppression

FM200 Suppression

Other

Other Systems

Kitchen Hood Exhaust System

Smoke Control System

Fire Appliances ☐ Gas ☐ Oil

Fireplace Venting/Metal Chimney

Other

Administrative Surcharge

Minimum Fee

State Permit Surcharge Fee

NUMBER FEE (Office Use Only)

TOTAL FEE \$779



FIRE PROTECTION SUBCODE TECHNICAL SECTION



COMMERCIAL

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location Home Depot #912
1722 Rt. 88 Brick, NJ 08724

Owner in Fee: The Home Depot

Tel. (233) 752-1700 e-mail Jay-anthracite@hotmail.com

Address 3096 Hamilton Blvd. South Plainfield, NJ 07080

Contractor: Fire Materials Group Tel. (980) 753-5444
2615 S. Industrial Park Ave. Temple Hill

Fire Protection Equipment, NJ Div of Fire Safety Permit No. 85283 PO0164

Fire Protection Equipment, NJ Div of Fire Safety Installer No. _____

Fire Alarm Contractor No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: (_____) _____

B. FIRE PROTECTION CHARACTERISTICS

Use Group: Present _____ Proposed M Fire Alarm System: 1 New or 1 Existing

Const. Class: Present _____ Proposed V-N Location of Panel: _____

Heating System: 1 New or 1 Existing 1 HVAC Fire Suppression/Standpipe System:

Type: 1 Gas 1 Oil 1 Electric 1 Solar X New or X Existing

Location: _____ Location of Main Control Valve: Riser room

Fuel Storage Tank:

Fuel Type: 1 Flammable or 1 Combustible Capacity _____

Total Cost of Fire Protection Work \$ 170

JOB SUMMARY (Office Use Only)

PLAN REVIEW _____ INSPECTIONS _____ Dates (Month/Day) _____

1 No Plans Required _____ Alarm System _____ Failure _____ Approval _____ Initial _____

1 Joint Plan Review Required _____ Suppression Sys _____ Failure _____ Approval _____ Initial _____

1 Building _____ Plumbing _____ Standpipe _____ Failure _____ Approval _____ Initial _____

1 Electric _____ Elevator _____ Fire Pump _____ Failure _____ Approval _____ Initial _____

1 Fire Plans Approved _____ Pre-Eng. System _____ Failure _____ Approval _____ Initial _____

Date: _____ Mechanical _____ Smoke Control _____ Failure _____ Approval _____ Initial _____

Approved by _____ TCO _____ Failure _____ Approval _____ Initial _____

SUBCODE APPROVAL _____ _____ Failure _____ Approval _____ Initial _____

1 CO 1 CCO 1 CA _____ Failure _____ Approval _____ Initial _____

Date: _____ Fireplace Venting _____ Failure _____ Approval _____ Initial _____

Approved by _____ Other _____ Failure _____ Approval _____ Initial _____

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the owner of record and am authorized to make this application. _____

X Certified Contractor _____ Applicant's Signature/Contractor's Signature

[] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK: Add/remove/relocate to match remodeled building

Water Supply Source 8" main behind building

Method of Alarm/Suppression System Supervision _____

NUMBER _____ FEE (Office Use Only) _____

Flammable/Combustible Tanks _____

Alarm Systems _____

[] System _____

[] 110V Interconnected _____

[] CO Detectors/110V _____

Alarm Devices (i.e., smoke, heat, pulls, water/flow) _____

Supervisory Devices (i.e., tamper, low/high air) _____

Signaling Devices (i.e., horns/strobes, bells) _____

Other Devices _____

TOTAL _____

Suppression Systems _____

Fire Pump 1500GPM Type Elec. VIL _____

Dry Pipe Alarm Valves _____

Pre-action Valves _____

Sprinkler Heads (Dry and Wet) _____

Standpipes _____

Pre-engineered Systems _____

Wet Chemical _____

Dry Chemical _____

CO₂ Suppression _____

Foam Suppression _____

FM200 Suppression _____

Other _____

Other Systems _____

Kitchen Hood Exhaust System _____

Smoke Control System _____

Fired Appliances [] Gas or [] Oil _____

Fireplace Venting/Metal Chimney _____

Other _____

Date Received _____

Control # _____

Date Issued _____

Permit # _____

1008-0649682A



FIRE PROTECTION SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location Home Depot #912 Brick, NJ 08724

Owner in Fee: The Home Depot

Tel. (233) 752-1700 e-mail Jay-anthony@charcopt.com

Address 3096 Hamilton Blvd. South Plainfield, NJ 07080

Contractor: Fire Materials Group Municipality South Plainfield Tel. (980) 753-5444

Address 2615 S. Industrial Park Ave. Jersey City, NJ 07310 ZIP code 07310

Fire Protection Equipment, NJ Div of Fire Safety Permit No. P00164

Fire Alarm Contractor No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: (_____) _____

B. FIRE PROTECTION CHARACTERISTICS

Use Group: Present _____ Proposed M Fire Alarm System: [] New or [] Existing

Const. Class: Present _____ Proposed V-N Location of Panel: _____

Heating System: [] New or [] Existing [] HVAC Fire Suppression/Standpipe System: _____

Type: [] Gas [] Oil [] Electric [] Solar [X] New or [X] Existing

Location: _____ Location of Main Control Valve: Riser room

Fuel Storage Tank: _____

Fuel Type: [] Flammable or [] Combustible Capacity _____

Total Cost of Fire Protection Work \$ 1500

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the agent of owner and am authorized to make this application. _____

Applicant's Signature/Contractor's Signature _____

[X] Certified Contractor [] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK: Add/remove/relocate to match remodeled building

Water Supply Source 8" main behind building

Method of Alarm/Suppression System Supervision _____

Flammable/Combustible Tanks _____

Alarm Systems _____

[] System _____

[] 110V Interconnected _____

[] CO Detectors/110V _____

Alarm Devices (i.e., smoke, heat, pull, water/flow) _____

Supervisory Devices (i.e., tamper, low/high air) _____

Signaling Devices (i.e., horn/strobes, bells) _____

Other Devices _____

TOTAL _____

Suppression Systems _____

Fire Pump 1500 GPM Type Etc. V14 _____

Dry Pipe Alarm Valves _____

Pre-action Valves _____

Sprinkler Heads (Dry and Wet) _____

Standpipes _____

Pre-engineered Systems _____

Wet Chemical _____

Dry Chemical _____

CO₂ Suppression _____

Foam Suppression _____

FM200 Suppression _____

Other _____

Kitchen Hood Exhaust System _____

Smoke Control System _____

Fired Appliances [] Gas or [] Oil _____

Fireplace Venting/Metal Chimney _____

Other _____

Administrative Surcharge \$ _____

Minimum Fee \$ _____

State Permit Surcharge Fee \$ _____

TOTAL FEE \$ _____

U.C.C. F-140 (rev. 1006) Applicant: When submitting this form to your local Construction Code Enforcement Office, please provide one original plus three photocopies.



FIRE PROTECTION SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code 5

Work Site Location Home Depot #912
1722 Rt. 88 Brick, NJ 08724

Owner in Fee: The Home Depot

Tel. (732) 752-1700 e-mail jay@mriscia@home depot.com

Address 3096 Hamilton Blvd. South Plainfield, NJ 07080

Contractor: Fire Materials Group Municipality South Plainfield, NJ Tel. (980) 753-5444

Address 2615 S. Industrial Park Ave. Toms River, NJ 08052 Tel. (732) 852-8282

Fire Protection Equipment, NJ Div of Fire Safety Permit No. POD164

Fire Alarm Contractor No. POD164 Exp. Date POD164

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): POD164

Federal Emp. ID No. POD164 FAX: (POD164) POD164

B. FIRE PROTECTION CHARACTERISTICS

Use Group: Present M Proposed V-N Fire Alarm System: [] New or [] Existing

Constr. Class: Present V-N Location of Panel: POD164

Heating System: [] New or [] Existing [] HVAC Fire Suppression/Standpipe System: POD164

Type: [] Gas [] Oil [] Electric [] Solar [X] New or [X] Existing Location of Main Control Valve: Riser room

Location: POD164

Fuel Storage Tank:

Fuel Type: [] Flammable or [] Combustible Capacity POD164

Total Cost of Fire Protection Work \$ POD164

JOBS SUMMARY (Office Use Only)

PLAN REVIEW POD164 INSPECTIONS POD164 Dates (Month/Day) POD164 Initial POD164

[] No Plans Required POD164 Alarm System POD164 Failure POD164 Approval POD164

Joint Plan Review Required POD164 Suppression Sys POD164 Failure POD164 Approval POD164

[] Building [] Plumbing POD164 Standpipe POD164 Failure POD164 Approval POD164

[] Electric [] Elevator POD164 Fire Pump POD164 Failure POD164 Approval POD164

[] Fire Plans Approved POD164 Pre-Eng. System POD164 Failure POD164 Approval POD164

Date POD164 Mechanical POD164 Failure POD164 Approval POD164

Approved by POD164 Smoke Control POD164 Failure POD164 Approval POD164

SUBCODE APPROVAL POD164 TCO POD164 Failure POD164 Approval POD164

[] CG [] CCO [] CA POD164 Flammable Tanks POD164 Failure POD164 Approval POD164

Date POD164 Fireplace Venting POD164 Failure POD164 Approval POD164

Approved by POD164 Other POD164 Failure POD164 Approval POD164

Date Received POD164
Control # POD164
Date Issued POD164
Permit # POD164

C. CERTIFICATION IN LIEU OF OATH
I hereby certify that I am the owner of the project and am authorized to make this application. Signature

[X] Certified Contractor Signature [] Exempt Applicant Signature

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK: Add/remove/relocate to match remodeled building

Water Supply Source 8" main behind building

Method of Alarm/Suppression System Supervision POD164

Flammable/Combustible Tanks POD164

Alarm Systems POD164

[] System POD164

[] 110V Interconnected POD164

[] CO Detectors/110V POD164

Alarm Devices (i.e., smoke, heat, pulls, water/flow) POD164

Supervisory Devices (i.e., tamper, low/high air) POD164

Signaling Devices (i.e., horns/strobes, bells) POD164

Other Devices POD164

TOTAL POD164

Suppression Systems POD164

Fire Pump 1500GPM Type Eke. V12

Dry Pipe Alarm Valves POD164

Pre-action Valves POD164

Sprinkler Heads (Dry and Wet) POD164

Standpipes POD164

Pre-engineered Systems POD164

Wet Chemical POD164

Dry Chemical POD164

CO₂ Suppression POD164

Foam Suppression POD164

FM200 Suppression POD164

Other POD164

Kitchen Hood Exhaust System POD164

Smoke Control System POD164

Fired Appliances [] Gas or [] Oil POD164

Fireplace Venting/Metal Chimney POD164

Other POD164

Administrative Surcharge \$ POD164

Minimum Fee \$ POD164

State Permit Surcharge Fee \$ POD164

TOTAL FEE \$ POD164



FIRE PROTECTION SUBCODE TECHNICAL SECTION



A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO: 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location Home Depot #912 Brick, NJ 08724

Owner in Fee: The Home Depot

Tel. (733) 752-1700 e-mail Jay-anthony@home depot.com

Address 3096 Hamilton Blvd. South Plainfield, NJ 07080

Contractor: Fire Materials Group Tel. (480) 753-5444

Address 2615 S. Industrial Park Ave. Toms River, NJ 08052

Fire Protection Equipment, NJ Div of Fire Safety Permit No. P00164

Fire Alarm Contractor No. _____ Exp. Date _____

Home Improvement Contractor Registration No. or Exemption Reason (if applicable): _____

Federal Emp. ID No. _____ FAX: (_____) _____

B. FIRE PROTECTION CHARACTERISTICS

Use Group: Present _____ Proposed M Fire Alarm System: [] New or [] Existing

Const. Class: Present _____ Proposed V-N Location of Panel: _____

Heating System: [] New or [] Existing [] HVAC Fire Suppression/Standpipe System: _____

Type: [] Gas [] Oil [] Electric [] Solar [X] New or [X] Existing

Location: _____ Location of Main Control Valve: Riser Room

Fuel Storage Tank: _____

Fuel Type: [] Flammable or [] Combustible Capacity _____

Total Cost of Fire Protection Work \$ 170

JOBS SUMMARY (Office Use Only)

PLAN REVIEW _____ INSPECTIONS _____

[] No Plans Required _____

[] Joint Plan Review Required _____

[] Building [] Plumbing _____

[] Electric [] Elevator _____

[] Fire Plans Approved _____

Date: _____

Approved by: _____

SUBCODE APPROVAL _____

[] CO [] CCO [] CA _____

Date: _____

Approved by: _____

C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the owner of the property and am authorized to make this application. _____

[X] Certified Contractor [] Exempt Applicant

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK: Add/remove/relocate to match remodeled building

Water Supply Source 8" main behind building

Method of Alarm/Suppression System Supervision _____

Flammable/Combustible Tanks _____

Alarm Systems _____

[] System _____

[] 110V Interconnected _____

[] CO Detectors/110V _____

Alarm Devices (i.e., smoke, heat, pull, water/flow) _____

Supervisory Devices (i.e., tamper, low/high air) _____

Signaling Devices (i.e., horns/strobes, bells) _____

Other Devices _____

TOTAL _____

Suppression Systems _____

Fire Pump 1500 GPM Type Eke. VIL _____

[X] Dry Pipe Alarm Valves _____

Pre-action Valves _____

Sprinkler Heads (Dry and Wet) _____

Standpipes _____

Pre-engineered Systems _____

Wet Chemical _____

Dry Chemical _____

CO₂ Suppression _____

Foam Suppression _____

FM200 Suppression _____

Other _____

Other Systems _____

Kitchen Hood Exhaust System _____

Smoke Control System _____

Fired Appliances [] Gas or [] Oil _____

Fireplace Venting/Metal Chimney _____

Other _____

Date Received _____

Control # _____

Date Issued _____

Permit # _____

Applicant's Signature/Contractor's Signature _____

[] Exempt Applicant

NUMBER _____ FEE (Office Use Only) _____

Administrative Surcharge \$ _____
Minimum Fee \$ _____
State Permit Surcharge Fee \$ _____
TOTAL FEE \$ _____



FIRE PROTECTION SUBCODE TECHNICAL SECTION

A. IDENTIFICATION—APPLICANT: COMPLETE ALL APPLICABLE INFORMATION. WHEN CHANGING CONTRACTORS, NOTIFY THIS OFFICE. CALL UTILITY DIG NO. 1-800-272-1000.

Block 1170 Lot 5 Qualification Code _____

Work Site Location 1722 N. STATE ROUTE 88

BLACK, NJ 08724

Owner in Fee THE HOME DEPOT

Address 3696 HAMILTON BLVD.

SOUTH PLAINFIELD, NJ 07080

Tel (732) 366-3666

Contractor CASCO / Contractor to follow

Address _____

Tel (____) _____ FAX (____) _____

Fire Protection Equipment, NJ Div of Fire Safety Permit No. _____

Fire Protection Equipment, NJ Div of Fire Safety Installer No. _____

Fire Alarm Contractor No. _____

Federal Emp. No. _____

B. FIRE PROTECTION CHARACTERISTICS

Use Group: Present M Proposed M Fire Alarm System: [] New or [] Existing

Constr. Class: Present _____ Proposed _____ Location of Panel: _____

Heating System: [X] New or [] Existing [X] HVAC Fire Suppression/Standpipe System: _____

Type: [X] Gas [] Oil [] Electric [] Solar [] New or [] Existing

Location: [] Other _____ Location of Main Control Valve: _____

Fuel Storage tank: CABINET - TCC RENTAL CENTER

Fuel Type: [] Flammable or [X] Combustible Capacity 50 GAL. GASOLINE

Total Cost of Fire Protection Work \$ 159,000.00



C. CERTIFICATION IN LIEU OF OATH

I hereby certify that I am the Agent, duly sworn, and am authorized to make this application.

Applicant's Signature/Contractor's Signature _____

[X] Exempt Applicant _____

D. TECHNICAL SITE DATA

DESCRIPTION OF WORK: GAS PIPING SPRINKLERS TO FOLLOW

Water Supply Source _____

Method of Alarm/Suppression System Supervision _____

Date Received _____

Control # _____

Date Issued _____

Permit # _____

Administrative Surcharge \$ _____

Minimum Fee \$ _____

State Permit Surcharge Fee \$ _____

TOTAL FEE \$ _____



April 30, 2009

Plans Examiner
Township of Brick Building Department
401 Chambers Street
Brick Township, NJ 08723

Re: The Home Depot #912
Fire Pump Room Piping Revision

Plans Examiner:

This letter is to document Telgian's review and recommendations for the above referenced issue.

Issue: New location for fire pump controller poses obstruction to fire pump discharge piping

Solution: Reroute fire pump discharge and bypass piping to provide required clearance for fire pump controller

As shown on the accompanying plan, approximately 6 ft of new pipe, various fittings, and one check valve have been added to the original plan. Some existing piping will require field modification.

We thank you for your review of this change. If you have questions or comments please contact me at (678) 402-0523

Sincerely,
Doug Kilgore
Fire Suppression Designer
Telgian Corporation



TRANSMITTAL

Project: The Home Depot #912
Brick, NJ

Job No. NJ00522/P1400

Date: 12-16-08

By: Andrea Thoms

Regarding: Sprinkler & Fire Alarm Submittal

To: Plan Reviewer
Municipal Building
401 Chambers Bridge Road
Brick Twp, NJ 08723
732-262-1027

We are sending you the following information:

Enclosed are (3) sets of fire alarm drawings for your review along with the product data sheets. Also enclosed are (3) sets of sprinkler drawings. The calcs and material data for those will be sent separately from our Atlanta office.

Once reviewed and approved, please notify me at the number below so I may contact the contractor(s) to come and pick up the plans.

If you have any questions, please call.

Thanks,

Andrea Thoms
athoms@telgian.com
734-781-9851

☐ SEPARATE COVER

☐ FACSIMILE

NO.

PAGES (INCLUDES COVER)

☐ U.S. POSTAL SERVICE

☐ PRIORITY AIR

☐ NEXT DAY AIR

☐ 2ND DAY AIR

☒ EXPRESS SAVER

☐ MESSENGER

☐ SENT VIA BBS / E-MAIL

☐ PRINT

☐ ORIGINAL

☐ REPRODUCIBLE

☐ HYDRAULIC CALCULATIONS

☐ SHOP DRAWINGS

☐ SPECIFICATIONS

☐ CORRESPONDENCE

☐ CADD DISC

☐ .DXF FORMAT

☐ .FCD FORMAT

☐ .DWG FORMAT

☐ MATERIAL LIST

☐ PHOTOGRAPH

☐ SAMPLE



FIRE ALARM SUBMITTAL
HOME DEPOT
BRICK, NJ



IntelliKnight® 5808 Single Loop Addressable Fire Alarm Control System



The convenience of an addressable fire alarm control panel in a cost-effective easy to use package.

IntelliKnight Model 5808 is a 127 point class leading single loop addressable fire alarm control/communicator system. 5808 provides you with the revolutionary value and performance of addressable sensing technology combined with exclusive, built-in digital communication,

distributed intelligent power, easy to use interface. Powerful features such as drift compensation and maintenance alert are delivered in this powerful FACP from Silent Knight.

For more information about the IntelliKnight system, or to locate your nearest source, please call 1-800-446-6444, or in Minnesota, call 763-493-6435.

Description

5808 performs drift compensation and calibration checks on each of the sensors in the system.

The basic 5808 system can be enhanced by adding modules such as 5860 remote annunciator, 5824 serial/parallel printer interface module (for printing system reports), and 5496 intelligent power module. 5808 also features a powerful built-in dual line fire communicator that allows for reporting of all system activity to a remote monitoring location.

Features

- Up to 127 addressable points
- Up to 125 zones and 125 output groups
- Uses standard wire—no shielded or twisted pair required
- Built-in digital communicator
- Central station reporting by point or by zone
- Supports Class B (Style 4) and Class A (Style 6 or 7) configuration for SLC
- Distributed, intelligent power
- Drift compensation
- 13 pre-programmed output cadences, (including ANSI-3.41), and 4 programmable outputs
- Notification circuits can be configured as 2 Class A (Style Z) or 4 Class B (Style Y), or auxiliary power for resettable, constant, or door holder power
- Built-in annunciator with 80-character LCD display
- RS-485 bus provides communication to system accessories
- Built-in RS-232 and USB interface for programming via a PC
- Upload or download programming, event history, or detector status via remote or direct connection
- Improvements in SKSS deliver five times faster upload/downloads

- Built-in synchronization for appliances from AMSECO, Gentex®, Faraday, System Sensor®, and Wheelock®
- One Form C trouble relay rated at 2.5A at 27.4 VDC and two Form C programmable relays rated at 2.5A at 27.4 VDC
- Programmable date setting for Daylight Saving Time
- Plex-2 door option combines a dead front cabinet door with a clear window, limiting access to the panel while providing single button operation of the reset and silence functions

Electrical Specifications

Primary AC: 120 VRMS at 50/60 Hz, 2.75A

Total Accessory Load: 6A @ 27.4 VDC

Notification Power: 6A @ 27.4 VDC, power-limited

Standby Current: 170 mA

Alarm Current: 325 mA

Notification & Auxiliary Circuits:

3A @ 27.4 VDC per circuit, power-limited

Battery Charging Capacity: 7.0-35.0 AH

Battery Size: 18 AH max. allowed in FACP. Larger capacity batteries can be housed in an RBB accessory cabinet

Mechanical Specifications

Flush Mount Dimensions:

14.5" W x 24.75" H x 3.5" D
(36.8 W x 62.9 H x 8.73 D cm)


Overall Dimensions:

16" W x 26.4" H x 4.65" D
(40.6 W x 67 H x 11.8 D cm)

Weight: 28 lbs. (12.8 kg)

Color: Red

Telephone Requirements:



Model 5808

FCC Part 15 and Part 68 approved
Type of Jack: RJ31X (two required)

Approvals

NFPA 13, NFPA 15, NFPA 16, NFPA 70, & NFPA 72: Central Station; Remote Signalling; Local Protective Signalling Systems; Auxiliary Protected Premises Unit; & Water Deluge Releasing Service. Suitable for automatic, manual, waterflow, sprinkler supervisory (DACT non-coded) signalling services.

Other Approvals: UL Listed;
CSFM 7170-0559: 142;
MEA 429-92-E Vol. XIV



**SILENT
KNIGHT**

by Honeywell

SLC Detectors

SD505-APS

Addressable photoelectric smoke detector.

SD505-AIS

Addressable ionization smoke detector.

SD505-AHS

Absolute temperature heat detector that goes into alarm immediately if the temperature exceeds the programmable trip point. Trip point range from 135°F–150°F (0°C–37°C).

SD505-6AB

Six inch base for use with detector heads SD505-APS, SD505-AIS and SD505-AHS.

SD505-4AB

Four inch base for use with detector heads SD505-APS, SD505-AIS, and SD505-AHS.

SD505-6SB

Six-inch sounder base for use with existing sensor and base. Operates in single and multi-station modes and/or as a system sounder. Requires 2 additional wires for power.

SD505-6IB

Short circuit isolator base for SD505-APS, SD505-AIS, and SD505-AHS detectors.

SD505-6RB

Six-inch relay base for use with existing sensor and base. Provides one Form C contact.

SD505-ADH

Duct housing that detects smoke in HVAC ducts.

SD505-ADHR

Duct detector base with relay. Provides Form C alarm contact. For use with SD505-APS and SD505-AIS sensors. Compatible with SD505-DTS remote test switch.

SD500-PS/SD500-PSDA

SD500-PS is a single action pull station and SD500-PSDA is a dual action pull station.

SLC Modules

Model SD500-AIM

Dry contact input module for use with normally open, dry contacts. It features an indicator LED to show alarm status.

SD500-MIM

Mini dry contact input module is a small version of the SD500-AIM. For use with pull stations and other normally open dry contact inputs.

SD500-ANM

Addressable notification module providing a single Class A or Class B notification circuit on the SLC.

SD500-ARM

Addressable relay module that features two Form C output relays. Provides indicator LED to show output status.

SD500-SDM

Two-wire detector input module. Allows for the connection of conventional 2-wire detectors on the SLC loop. Requires two additional wires for power.

SD500-LIM

A short circuit isolator module for SLC devices. When a short occurs on the SLC loop, it is detected as a trouble, but all SLC devices protected by the isolator module continue to operate.

SD500-LED

An LED driver capable of driving 80 LEDs through the SLC loop. Up to 40 SD500-LEDs can be used per system.

S-BUS Accessories

5860/R Remote Fire Annunciator

Features the same 80 character backlit LCD display keypad and firefighter's key switch as the 5808. 5860 is gray and 5860R is red.

5496 Intelligent Power Module

A 6 amp notification power expander that provides four additional power-limited notification appliance circuit outputs.

5880 LED/IO Module

Features 40 LED outputs, 8 normally open dry contact inputs and one piezo output.



5865-3 and 5865-4 Remote LED Annunciator

Features 30 programmable LED (15 red and 15 yellow) outputs and a piezo sounder. The 5865-4 adds a silence and reset switch to the package.

5883 Relay Board

Features 10 general purpose Form C relays. Used with 5880 module.

5824 Serial/Parallel Printer Interface Module

Provides one parallel and one RS-232 serial port for connecting a printer to 5808. Use to print a real-time log of system events, detector status reports, and event history.

Miscellaneous Accessories

5660 Silent Knight Software Suite

PC-base software for FACP programming. Upload and view panel account information, event history, and detector status.

5670 Silent Knight Software Suite

End-user facility management software allows viewing of detector status and event history via modem or direct connection.

Plex-2 Door


Dead front cabinet door with clear window to limit access to the FACP.

RBB

Remote Battery Box Accessory Cabinet. Use if backup batteries are too large to fit into FACP cabinet. Dimensions: 16" W x 10" H x 6" D (406 mm W x 254 mm H x 152 mm D)

SD505-DTS

Remote test switch that provides remote key operated test function and annunciation of detector alarm with SD505-ADHR.



by Honeywell

This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice. For more information, contact Silent Knight: 7550 Meridian Circle Suite 100, Maple Grove, Mn 55369-4927. Phone: (800) 328-0103, Fax: (763) 493-6475.



IntelliKnight & JumpStart are Registered Trademarks of Silent Knight
Flexput is a Trademark of Silent Knight

MADE IN AMERICA

FORM# 350386 Rev. D 04/06

Copyright © 2006 Silent Knight

5860 Remote Annunciator



Bring the power to control an IntelliKnight fire alarm control panel to every area within your facility.

Now you can operate and program your IntelliKnight system from up to eight locations throughout your facility. The 5860 remote annunciator provides the same advanced, easy-to-use interface found on the IntelliKnight panel's built-in annunciator. The 80-character display and

ergonomically designed keypad allow for simple and error-free system operation. All operations—including reset, silence, detector status checking, fire drill, and programming—are identical.

Access to the system is through a firefighter's key or an access code. For security, a special installation code is needed for programming functions. The 5860 connects to the IntelliKnight panel via the RS-485 system bus. Wire runs can be up to 6000 feet from the panel.

For more information about the IntelliKnight system, or to locate your nearest source, please call 1-800-446-6444, or in Minnesota, call 763-493-6435.

Description

Features include an 80-character backlit LCD providing easy-to-understand system messages. The annunciator is ergonomically designed with over-sized buttons for the most frequently used features, like Reset and Silence.

In addition to status messages displayed on the LCD, there are five LEDs for alarm, supervisory, trouble, silence, and AC power status.

The annunciator is available in gray to match virtually any decor and red for applications where the annunciator must stand out. The annunciator enclosure can be surface or flush mounted. A trim ring kit is available for surface mounting.

Features

- 80-character backlit LCD display (4 lines with 20 characters on each line)
- Tactile and audible feedback
- Accepts user codes or fire fighter's key
- Larger keypad buttons for system reset and silence
- Install up to eight 5860s per FACP

- Available in red or light gray
- Support for simultaneous use of multiple 5860s
- RS-485 interface to panel
- Operation and appearance is identical to 5860 built-in annunciator
- On-board piezo sounder audibly indicates alarms, troubles, and supervisory
- Five status LEDs for alarm, supervisory, trouble, silence and AC power conditions
- Wiring lengths up to 6000 ft. from the FACP (depending on wire gauge and number of devices on SBUS)
- UL listed, complies with NFPA 72
- CSFM approved

Electrical Specifications

Operating Voltage: 24 VDC

Standby Current: 20 mA max

Alarm Current: 25 mA


Wiring Distance: 6,000 max. from FACP (depending on wire gauge and number of devices on the SBUS)

Max Per System: 8

Mechanical Specifications

Physical 9.1" W x 7.4" H x 1.5" D (23.1 W x 18.8 H x 3.8 D cm)

Shipping Weight: 2.8 lbs (1.3 kg)



5860

Color

5680R: Red

5680: Gray

Environmental

Operating Temperature: 32°F – 120°F (0°C – 49°C)

Humidity: 10% – 93% non-condensing

Approvals

NFPA 72; UL Listed;
CSFM 7170-0559; 135;
MEA 429-92-E Vol. IX;
FM Approved



**SILENT
KNIGHT**

by Honeywell

5860 Remote Annunciator




Engineering Specifications

The main control must have a built-in annunciator and must support up to eight remote annunciators. Remote annunciators shall have the same control and display layout so as to match the appearance of the built-in annunciator. Remote annunciators shall be available in two colors, red or light gray.

Remote annunciators shall have identical functionality and operation as the built-in annunciator. All annunciators must have an 80-character LCD display and must feature five LEDs for: General Alarm, Supervisory, System Trouble, System Silence, and System Power.

All controls and programming keys are silicone mechanical type with tactile and audible feedback. Keys have a travel of .040 inches. No membrane style buttons will be permissible.

The annunciator must be able to silence and reset alarms through the use of a code entered on the annunciator keypad or by using a firefighter's key. The annunciator must have two levels of user codes that will limit the operating system programming to authorized individuals. The control panel must allow all annunciators to accommodate multiple user input simultaneously.



Compatibility

IntelliKnight 5820XL FACP

IntelliKnight 5808 FACP

IntelliKnight 5700 FACP

Ordering Information

5680R Remote Annunciator

Four line LCD annunciator with 20 characters per line. Red.

5680 Remote Annunciator.

Four line LCD annunciator with 20 characters per line. Gray.

Accessories

5860TR Red Trim Ring

For surface mounting.

5860TG Gray Trim Ring

For surface mounting.



**SILENT
KNIGHT**


by Honeywell

This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice. For more information, contact Silent Knight 7550 Meridian Circle Suite 100, Maple Grove, MN 55369-4927. Phone: (800) 328-0103, Fax: (763) 493-6475.

MADE IN AMERICA

FORM# 350224 Rev C, 05/06

Copyright © 2006 Silent Knight



SD500-LIM Line Isolator Module



Isolate SLC loop problems without losing the entire loop.

Isolate a short circuit wiring fault on a SLC loop using a SD500-LIM. Normally if a short on the SLC loop occurs, communication on the loop can be disrupted. When isolator modules are used and a short occurs on the SLC loop, it will be detected as a trouble but all the SLC devices that are protected by a line isolator module will continue to operate.

SD500-LIM Line Isolator Module

The SD500-LIM Line Isolator Module is compatible with Silent Knight's Addressable Fire control panels.

The SD500-LIM can be used on Style 7 (Class A), and Style 4 (Class B) wiring configurations.

The SD500-LIM mounts in a standard dual gang or 4" square electrical box.

Specifications

Operation
Temperature: 32° - 120°F
(0° - 49°C)

Dimensions:
Length: 4-7/8" (12.38 cm)
Width: 4-7/8" (12.38 cm)
Depth: 7/8" (2.22 cm)


Operating Voltage: 32 VDC

Battery Current
Draw During

AC Loss: .092 mA

SLC Current: .092 mA

Max. SLC
Loop Resistance: 50Ω



Features

- Isolates short circuits on an SLC loop.
- Protects other modules on the loop so other devices continue to operate.
- Can be used on Style 7 (Class A), and Style 4 (Class B) wiring configurations.
- Mounts in a standard dual gang or 4" square electrical box.

Listings/Approvals

- UL Listed
- CSFM listed 7170-0559:143
- MEA approval 429-92-E volume XI

Compatible Control Panels


5820XL
5808
5700




**SILENT
KNIGHT**

by Honeywell


SD500-LIM Line Isolator Module



Style 7 (Class A)



Style 4 (Class B)




Mounting



This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice. For more information, contact Silent Knight 7550 Meridian Circle Suite 100, Maple Grove, Mn 55369-4927. Phone: (800) 328-0103, Fax: (763) 493-6475. <http://www.silentknight.com>

MADE IN AMERICA
FORM# 350222 Rev. C 12/06
Copyright © 2006 Silent Knight



SD500-AIM & SD-500-MIM Addressable Input Modules



IntelliKnight's addressable contact monitor modules combine fast response with pinpoint location ID. A combination that saves lives and property.

The SD500-AIM and SD500-MIM are addressable input modules for use with Silent Knight IntelliKnight fire alarm control panels (FACP). The SD500-AIM and SD500-MIM are designed to be used with pull stations, water flow switches, and other applications requiring dry contact alarm initiation devices.

The SD500-AIM addressable input module mounts to a 4"-square box. The SD500-MIM mini input module fits inside a single gang box. The modules are supervised, single input contact monitors. Using an EOL resistor, they monitor for alarm contact closures and for open circuit wiring fault conditions.

The SD500-AIM and SD500-MIM offer a compact design for adaptability and pleasing aesthetics as well as easy installation and stable operation—a flexible solution for all your fire protection needs.

For more information about the IntelliKnight system, or to locate your nearest source, please call 1-800-446-6444, or in Minnesota, call 763-493-6435.

Description

The SD500-AIM and SD500-MIM are addressable input modules for use with the IntelliKnight fire alarm control panels (FACPs). The SD500-AIM addressable input module mounts to a 4"-square box. The SD500-MIM mini input module fits inside a single gang box. Both input modules are designed to be used with pull stations, water flow switches, and other applications requiring dry contact alarm initiation devices.

These modules are supervised, single input contact monitors. Using an EOL resistor, they monitor for alarm contact closures and for open circuit wiring fault conditions. If a fault occurs in the wiring, the module alerts the FACP. Each addressable input module is programmed with a unique signal line circuit (SLC) loop address.

Features

- Single contact monitor
- Support for Class A (Style 6 & Style 7) or Class B (Style 4) wiring
- Attractive ivory cover plate with the SD500-AIM
- Small and lightweight size allows for flexible mounting options with the SD500-MIM
- DIP switch programmable for fast installation

- Up to 2500 ft wiring distance from either input module to contact
- Use up to 14 gauge wire
- UL listed

Electrical Specifications

Standby Current: 0.55 mA

Alarm Current: 23 mA max for one device; 46 mA max for two devices; 0.55 mA for each additional device

Line Resistance: 50Ω max

Mechanical Specifications

SD500-AIM Physical Description
Dimensions:

4.9" W x 4.9" H x 1" D
(12.4 W x 12.4 H x 2.5 D cm)

Weight: 3.6 oz (120.1 g)

Color: Ivory cover plate

SD500-MIM Physical Description
Dimensions:


1.5" W x 2.5" H x 0.7" D
(3.8 W x 6.4 H x 1.8 D cm)

Weight: 1.6 oz (45.4 g)


Environmental

Operating Temperature:
32°F – 120°F (0°C – 49°C)

Humidity:
10% – 93% non-condensing



SD500-AIM



SD500-MIM

Approvals

NFPA 71 & NFPA 72

UL 864

CSFM 7300-0559: 132

MEA 429-92-E Vol. IX

FM Approved for use with the 5820XL



**SILENT
KNIGHT**

by Honeywell



SD500-AIM & SD500-MIM Addressable Input Modules



Engineering Specifications

The contractor shall furnish and install where indicated on the plans, addressable input modules Silent Knight SD500-AIM or SD500-MIM. The modules shall be UL listed and compatible with Silent Knight's IntelliKnight FACP's.

The SD500-MIM shall fit inside a single gang electrical box. The SD500-AIM shall be supplied with a plastic cover and shall be suitable for mounting to a 4"-square or double gang electrical box. The SD500-AIM addressable input module must provide a monitor LED that is visible from outside the cover plate



Compatibility

IntelliKnight 5820 FACP

IntelliKnight 5808 FACP

IntelliKnight 5700 FACP

Ordering Information

SD500-AIM Input Module

Addressable input module with ivory cover plate.

SD500-MIM Mini Input Module

Addressable mini input module.



This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice. For more information, contact Silent Knight 7550 Meridian Circle Suite 100, Maple Grove, Mn 55369-4927. Phone: (800) 328-0103, Fax: (763) 493-6475.

MADE IN AMERICA

FORM# 350231 Rev.C, 05/06

Copyright © 2006 Silent Knight



Model SD500-ARM Addressable Relay Module



Place relay applications anywhere on the IntelliKnight loop with the SD500-ARM Addressable Relay Module.

The SD500-ARM is an addressable device that adds great flexibility to the IntelliKnight system. Providing two Form C contacts rated at 2.0 amps @ 30 VDC or .6 amp @ 120 VAC. The SD500-ARM allows you to control a wide variety of normally open and normally closed applications, including elevator recall, door closing, fan operation, and auxiliary notification. And, because the relay module is addressable, these applications can be located at any point in the signaling line circuit.

Like other IntelliKnight SLC devices, the SD500-ARM is compact for adaptability and pleasing aesthetics. Combine this with the features you've come to expect from Silent Knight fire protection devices—easy installation and stable operation—and it adds up to a flexible solution for all your fire protection needs.

Model SD500-ARM Addressable Relay Module


The SD500-ARM provides two Form C contacts rated at 2A @ 30 VDC or .6A @ 120 VAC. These contacts can be used for virtually any normally open or normally closed application.

Operation

Each relay module is programmed with a unique SLC loop address. When an event that controls the relay module occurs, the relay is triggered by the IntelliKnight panel.

Features

- Two sets of Form C contacts.
- Contacts are rated at 2A @ 30 VDC or .6A @ 120 VAC.
- Up to 127 relays can be used on each SLC loop.
- Relay programming is completely flexible—can be mapped to zone conditions.
- Polling LED visible through cover plate.
- UL listed, complies with NFPA 72.
- CSFM approved
- MEA Approved, 429-92-E, Vol. 9
- FM approved



Model SD500-ARM

Specifications

Contact Rating:	Form C
	2A @ 30 VDC
	.6A @ 120 VAC
Standby Current:	.55 mA
Alarm Current:	.55 mA
Ambient Temperature	32°F to 120°F (0°C to 49°C)
Mounting	4-square electrical box



**SILENT
KNIGHT**

Model SD500-ARM Addressable Relay Module




Engineering Specifications

The contractor shall furnish and install where indicated on the plans, addressable relay modules, Silent Knight SD500-ARM. The modules shall be UL listed compatible with Silent Knight's Intelliknight FACP's.

The relay module must provide two Form C dry contacts rated at 2.0 amps at 30 VDC or .6 amp at 120 VAC.

The relay module must be suitable for mounting in a standard 4-square electrical box and must include a plastic cover plate. The relay module board must provide an LED that is visible from the outside of the cover plate.

The relay must be fully programmable for such applications as are required by the installation.



Model SD500-ARM Addressable Relay Module Dimensions



**SILENT
KNIGHT**

7550 Meridian Circle, Maple Grove, MN 55369-4927

800-446-6444 or in Minnesota 763-493-6435


FAX: 763-493-6475

World Wide Web: <http://www.silentknight.com>

MADE IN AMERICA

FORM# 350218, Rev. 11/01

Copyright © 2001 Silent Knight



Addressable Photoelectric Type Smoke Detector



Detect smoldering fires quickly and get help fast with IntelliKnight® photoelectric smoke detectors.

IntelliKnight addressable photoelectric smoke detectors are the clear choice for commercial settings where smoldering fires are a threat. In addition to accurately detecting a smoldering fire, each SD505-APS photoelectric detector has a unique address, which is recognized by the IntelliKnight panel. No precious seconds are wasted in determining location of an alarm.

The SD505-APS compensates automatically for contamination in the environment. And detector testing is simple—even from a remote site. Like other IntelliKnight detector models, the SD505-APS offers a low profile for pleasing aesthetics. The IntelliKnight family of detectors has been designed to use a common base, Model SD505-6AB, allowing complete application and placement flexibility. Combine all this with the features you've come to expect from Silent Knight smoke detectors—easy installation, stable operation, RF/transient protection, and vandal-resistant locking—and it adds up to a flexible solution for all your fire protection needs.

Model SD505-APS Analog / Addressable Photoelectric Type Smoke Detector

The SD505-APS is particularly suited to detecting dense smoke typical of fires involving materials such as soft furnishings, plastic, foam or other similar materials which tend to smolder and produce large visible particles.

The detector features automatic compensation for contamination and a simple detector calibration test procedure that can be run from the panel or remotely (using the Windows™ based downloading software).


Operation

The SD505-APS units made up of an LED light source and a silicon photo diode receiving element. In a normal standby condition, the receiving element receives no light from the pulsing light source. In the event of fire, smoke enters the detector and light is reflected from the smoke particles to the receiving element.

The light received is converted into an electronic signal. Under normal conditions, the status LED blinks approximately every 15 seconds, indicating that the head is communicating with the loop. The LED lights continuously during the alarm period.

Features

- Low profile, 2 inches, including base
- Simple and reliable addressing without mechanical switches
- Automatic compensation for sensor contamination
- Built-in fire test feature
- Simple detector calibration testing through the control panel or remotely through a Windows™ based computer software.
- Vandal-resistance locking features
- Field cleanable
- UL listed, meets NFPA 72 Ch 7 requirements
- CSFM approved
- MEA approved
- FM Approved



SD505-APS Smoke Detector

Specifications

Operating Voltage: 17-41 VDC

Current Consumption:

Standby:	.55 mA
Alarm:	.55 mA

Ambient Temperature: 32°F to 120°F
(0°C to 49°C)

Mounting: 4" Square, 4" OCT, Single gang mud ring

Relative Humidity: 85% noncondensing

Air Velocity: 0 - 300 FPM

Compatible Bases: SD505-6AB
(Sold Separately) (6" Base)
SD505-4AB
(4" Base)



**SILENT
KNIGHT**

by Honeywell

Model SD505-APS Addressable Photoelectric Type Smoke Detector



Engineering Specifications

The contractor shall furnish and install where indicated on the plans, addressable photoelectric smoke detector Silent Knight SD505-APS. The combination detector head, and twist-lock base, shall be UL® listed compatible with Silent Knight's IntelliKnight fire control panels.


The base shall permit direct interchange with Silent Knight SD505-AIS Ionization Smoke Detector, or SD505-AHS Heat Detector. Base shall be the appropriate twist-lock base SD505-6AB.

The smoke detector shall have a flashing status LED for visual supervision. When the detector is actuated, the flashing LED will latch on steady. The detector may be reset by actuating the control panel reset switch.


The calibration of the detector shall be capable of being selected and measured by the control panel without the need for external test apparatus.

The vandal-resistant, security locking feature shall be used in those areas as indicated on the drawing. The locking feature shall be field selectable as required.

The SD505-APS shall automatically perform a functional test of the detector. The test method shall simulate effects of products of combustion in the chamber to ensure testing of detector circuits.



Model SD505-6AB Detector Base
(front view)



Height = 2 inches,
including base

Model SD505-APS Detector Head
(front view)



**SILENT
KNIGHT**

by Honeywell


This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice. For more information, contact Silent Knight 7550 Meridian Circle Suite 100, Maple Grove, Mn 55369-4927. Phone: (800) 328-0103, Fax: (763) 493-6475.

MADE IN AMERICA

FORM# 350225 Rev C, 05/05

Copyright © 2005 Silent Knight

Addressable Heat Detector



IntelliKnight® addressable heat detectors combine accurate heat detection with pin-point location ID.

An essential combination for any installation.

IntelliKnight heat detectors are an essential component in virtually any IntelliKnight installation. The IntelliKnight panel recognizes each detector by its specific address, so precious seconds are not wasted in determining location of an alarm.

Like other IntelliKnight detector models, the SD505-AHS offers a low profile for pleasing aesthetics.

The IntelliKnight family of detectors has been designed to use a common base, Model SD505-6AB, allowing complete application and placement flexibility. Combine all this with the features you've come to expect from Silent Knight detectors—easy installation, stable operation, RF/transient protection, and vandal-resistant locking—and it adds up to a flexible solution for all your fire protection needs.

Model SD505-AHS Addressable Heat Detector

The SD505-AHS is a heat detector suited to virtually any commercial setting. The SD505-AHS is an absolute temperature device. This means that it responds in alarm if the temperature goes above the trip point (programmed at the panel).

The SD505-AHS provides accurate temperature measurement data to the fire alarm control panel. This heat detector is particularly suited to environments where smoke detectors cannot be used because of the presence of steam or cooking fumes, such as in a kitchen.

Operation

The SD505-AHS unit is made up of an externally mounted thermistor with a specially designed cover that protects the thermistor while allowing maximum air flow. The thermistor reads the temperature from the air it takes in. It then transmits a signal representing the temperature to the IntelliKnight panel.

If the temperature exceeds the trip point (programmed at the panel), an alarm occurs. The status LED lights continuously during the alarm period.

Under normal conditions, the status LED blinks approximately every 15 seconds, indicating that the head is communicating with the loop.


Features

- Low profile, 2 inches, including base
- Absolute temperature device
- Simple and reliable addressing
- Uses digital communication protocol
- The SD505-AHS is UL Listed and meets the requirements outlined in NFPA 72 Inspection Testing and Maintenance, Chapter 7.
- CFSM listed
- MEA listed
- FM approved



**SILENT
KNIGHT**

by Honeywell



SD505-AHS Heat Detector Specifications

Operating Voltage:	17 to 41 VDC
Current Consumption:	
Standby:	.55 mA
Alarm:	.55 mA
Detection Temperature Range:	135°F to 150°F (57°C TO 65°C)
Ambient Temperature:	32°F to 120°F (0°C to 49°C)
Mounting:	4" SQR, 4" OCT Single gang mud ring
Rated Spacing:	70' between sensors on smooth ceilings.
Compatible Bases: (Sold Separately)	SD505-6AB (6" Base) SD505-4AB (4" Base)

Model SD505-AHS Addressable Heat Detector



Engineering Specifications


The contractor shall furnish and install where indicated on the plans, addressable heat detector Silent Knight SD505-AHS. The combination detector head, and twist-lock base, shall be UL® listed compatible with Silent Knight's IntelliKnight fire alarm control panels.

The base shall permit direct interchange with Silent SD505-APS Photoelectric Smoke Detector, or SD505-AIS Ionization Smoke Detector. Base shall be the appropriate twist-lock base SD505-6AB.


The smoke detector shall have a flashing status LED for visual supervision. When the detector is actuated, the flashing LED will latch on steady at full brilliance. The detector may be reset by actuating the control panel reset switch.

The vandal-resistant, security locking feature shall be used in those areas as indicated on the drawing. The locking feature shall be field removable when not required.

Voltage and RF/transient suppression techniques shall be employed to minimize false alarm potential.



Model SD505-6AB Detector Base
(Front View)



Model SD505-AHS Detector Head
(Front View)



**SILENT
KNIGHT**

by Honeywell

This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice. For more information, contact Silent Knight: 7550 Meridian Circle Suite 100, Maple Grove, Mn 55369-4927. Phone: (800) 328-0103, Fax: (763) 493-6475.

MADE IN AMERICA

FORM# 350229 Rev B., 05/05

Copyright © 2005 Silent Knight